



ANNUAL REPORT 2022 - 23



TUNGABHADRA BOARD. T B DAM, HOSPET, KARNATAKA

TUNGABHADRA BOARD HIGHLIGHTS OF THE YEAR 2022-23

The Tungabhadra Project has completed 70 years of operation since the first release of water into canals on 1st July 1953.

The inflow realized in the Tungabhadra reservoir was 17277.913 Mm³ (610.182 TMC) during the water year 2022-23.

The utilization including evaporation losses and system losses was 5761.003 Mm³ (203.454 TMC) during the water year 2022-23.

The total withdrawals excluding evaporation and system losses by Karnataka, Andhra Pradesh and Telangana were 5392.272 Mm³ (190.432 TMC) for 2022-23.


The total withdrawals by Karnataka were 3558.924 Mm³ (125.686 TMC) against their share of 3490.088 Mm³ (123.255 TMC) for 2022-23.

The total withdrawals by Andhra Pradesh were 1669.879 Mm³ (58.973 TMC) against their share of 1669.8 Mm³ (58.973 TMC) for 2022-23.

The total withdrawals by Telangana were 163.468 Mm³ (5.773 TMC) against their share of 163.468 Mm³ (5.773 TMC) for 2022-23.

Tungabhadra Hydro–electric scheme generated power of 193.296 million units in 2022-23.

The same has been shared between Karnataka and Andhra Pradesh in the Ratio of 20:80.





ANNUAL REPORT 2022 - 23

TUNGABHADRA BOARD
TB DAM, Hospet, Karnataka



FROM CHAIRMAN'S DESK

Tungabhadra Board, which is a statutory organisation of Government of India, was initially formed in the year 1953. It was created for interstate river water cooperation among erstwhile states of Mysore, Andhra Pradesh and Hyderabad. As per KWDT award, the gross water allocation to TB Reservoir is 230 TMC, including reservoir evaporation losses of 18 TMC. The Board is mandated to regulate supplies of water and power among the states of Karnataka, Andhra Pradesh and Telangana as per the KWDT award.

As the Canal system of Tungabhadra Dam was constructed during the fifties as unlined section, it got damaged in many of the reaches. Further, the structures were also in dilapidated condition leading to loss of considerable amount of water. As such, modernisation of RBHLC was started by the TB Board during the year 2016-17, which mainly consists of restoration of canal section and C.C. lining. These works have been completed. Similarly, Modernization works of RBLLC were taken up from Km 0 to 205.450 and are mostly completed except a few patches. Modernisation of the canal system had resulted in good water management and increased water utilization.

The inflows of 610.182 TMC were received in the year 2022-23 and net utilization achieved is 190.432 TMC against 212.00 TMC as per the KWDT Award. Similarly, the TBHES, has generated hydropower of 193.296 MU, in spite of running with old generation units.

The Hagari aqueduct at km 121/000 of RBLLC constructed across the Hagari (Vedavathi) river got damaged due to unprecedented floods on 08.09.2022 & 13.10.2022. The restoration works of the aqueduct posed several challenges due to difficult field conditions and time constraints. However, the Board Engineers worked for days and nights and completed the herculean task within the time. I appreciate the efforts put by the officers of TB Board for accomplishing the engineering feat of Restoration of Hagari aqueduct on war footing. The timely restoration of the aqueduct saved about Rs.800 crores worth of crops in Kharif and Rabi seasons of 2022 - 23.

I take this opportunity to sincerely thank the Members of the Board for their suggestions, support and positive decisions in management of the Board. I appreciate the effort of all the staff of the TB Board for excellent water management and implementation of Board decisions effectively during 2022-23.

(D.M. Raipure)
Chairman,
Tungabhadra Board



MESSAGE FROM SECRETARY

I am very glad and delighted to bring out 'Annual Report of Tungabhadra Board for the year 2022-23'. The Report gives a comprehensive overview of the role of Tungabhadra Board and activities of Tungabhadra Board highlighting the contribution made in the Development and Water Management of TB Reservoir and Canal systems.

As the Right Bank Canals under TB Board were more than 60 years old RBHLC & RBLLC being an unlined canal, to deliver indented water to Member States as per the KWDT award, the Modernization of Tungabhadra Board Canals has been taken up in a phased manner since 2016-17.

The Modernisation of RBLLC & RBHLC for the past few years has resulted in good water management with increased utilization.

Hydrologically, the year 2022-23 is a good year, Tungabhadra Dam has got filled to its brim thus making a fifth consecutive good years owing to the good monsoon rains in the catchment area and the spillway gates were opened for releasing of surplus water into the river successfully 5th year in a row. The highest inflows of 610.182 TMC were received and 404.269 TMC water let out over spillway after 1961-62, and net utilization achieved in the year 2022-23 is 190.432 TMC against 212.00 TMC as per the KWDT Award. Similarly, the TBHES, TB Board has generated power of 193.296 MU, in spite of running with old generation units.

Specially, this year I appreciate my officers for timely action taken in Permanent Restoration of damaged piers of more than 60 years old Hagari Aqueduct (constructed at km 121/000 of RBLLC across the Hagari (Vedavathi) river) on war footing and thus saving Hundreds of crores of rupees worth of Khariff crop and supply of water to Rabi crops of the Ayacut downstream of the Hagari Aqueduct.

The goals achieved during the year 2022-23 by Tungabhadra Board are solely by the hard work and sustained efforts put in by the Officers and staff of Tungabhadra Board and consultant and contracting agency of Hagari Aqueduct. It gives me immense pleasure to acknowledge and appreciate their sincere efforts in ensuring smooth Water Management without any major disputes.

I express my sincere gratitude to the Chairman, TB Board and Members of the TB Board for their kind support and guidance to the Team of Board Engineers in discharging their duties efficiently. I thank all of them whole heartedly and hope for the same kind of support from them in future. Further, I thank all the Officers & staff of Tungabhadra Board for their continued sincere efforts in discharging their duties and request them to continue the same in the ensuing years also.

The publication of this Annual Report has been possible with the dedicated efforts of officers and staff of TB Board. I acknowledge the efforts of all who contributed in bringing out this report.

(O.R.K Reddy)
Secretary,
Tungabhadra Board

CONTENTS

Chapter	Subject	Page No
1	TUNGABHADRA PROJECT HISTORY	1-4
	River Tungabhadra	
	Harnessing of Tungabhadra Waters	
	Genesis of Tungabhadra Project	
	Project Construction	
2	TUNGABHADRA BOARD	5-32
	Constitution of Board	
	Present Composition of Board	
	Functions of the Board	
	Staffing pattern	
	KWDT Award	
	Statewise water allocation as per KWDT Award	
	Present Functions	
	Organization Structure	
	Applicability of Rules	
	Administration	
	Board Meetings	
	Transfers & Posting of Officers	
	Finance	
	Vigilance Cell	
	Legal Disputes	
	Estate Matters	
	Foundation Day Celebrations	
	VIP / Dignitaries List	
	Redressal of staff grievances	
	Monitoring of Reservation for SC/ST/OBC and physically Challenged	
	Committee for complaints on sexual Harassment	
3	WATER MANAGEMENT OF TB PROJECT	33-72
	Irrigation wing of TB Board	
	Functions	
	Inter-State Canals	
	River Assistance	
	Lift Irrigation Schemes	
	Other water demands	
	Negative inflows	

Chapter	Subject	Page No
	Losses in the Canal System	
	Operation of reservoir	
	Water Regulation during the water year 2022-22	
	Water Utilization during the water year 2022-23	
	Pipings and breaches	
	Flood management	
	Reservoir sedimentation	
	Topographic Survey of TB Reservoir	
	Modernization of Right Bank Canals	
	Live flow measurements in canal	
	Financial performance	
4	HYDRO POWER MANAGEMENT	73-86
	Introduction	
	Right bank dam power house	
	Hampi power house	
	Bellary sub station	
	Hydro electric wing Functions	
	Hydro Power Generation	
	Financial Performance (Expenditure & Revenue)	
	Royalty to Irrigation wing of TB Board	
	Rate of Electricity charges for Board employees	
	Maintenance Works	
	New mini Hydel power station	
	Power generation units on left side of the TB Dam	
5	DEVELOPMENT OF FISHERIES	87-88
	Introduction	
	Organization	
	Fish Farm	
	Ice Plant	
	The Aquarium " Parnaja"	
	Financial / Physical Performance (Expenditure & Revenue)	

Chapter	Subject	Page No
6	HEALTH AND MEDICAL CARE	89-94
	Introduction	
	Organization	
	Functions	
	Activities of the Public Health unit during the year 2022-23	
	Financial Performance	
7	PARKS AND GARDENS TOURIST ATTRACTONS	95-104
	Introduction	
	Organization	
	Tasks	
	Parks and Gardens	
	Other Attractions	
	Amenities to Visitors	
	Entrance fee / Parking fee	
	Expenditure / Revenue generated during 2022-23	
8	SECURITY SECTION	105-110
	Introduction	
	Organization	
	Functions	
	Security of Dam and Power Houses	
	Security of Canals	
	Other Security Interests	
	Financial Performance	
	Physical performance	
9	COMPREHENSIVE DAM SAFETY PROGRAMME	111-126
	Annexures	127-180
	Abbreviations	181

List of ANNEXURES

Annexure No.	Title	Page No
1.1	Index Map of Tungabhadra Project	129
1.2	Salient Features of Tungabhadra Project	131
2.1	Constitution of Tungabhadra Board	135
2.2	Extract of final award of KWDT (Clause IX and Clause XVI)	139
2.3	Organization chart Tungabhadra Board	142
2.4	Detailed Organization chart of Tungabhadra Board	143
2.5	Revision of Ground rent	144
2.5A	Tariff rates for vaikunta guest house & Annexure	145
2.6	Transfer & Postings of officers in TB Baord	146
3.1	Irrigation Benefits of Tungabhadra Project	148
3.2	Organization chart of Irrigation Wing	149
3.3	Details of Common Distributaries of RB LLC	150
3.4	Drinking water schemes approved by Board	151
3.5	Industrial Water Users Approved by Board	153
3.6	Canal wise drawals of water against pro-rata entitlement for the water year 2022-2023	154
3.7	Water account for the year 2022-23	155
3.8	Utilization of Water from 1978-79 to 2022-23	156
3.9	Pipings and Breaches Occurred During 2022-23	157
3.9A	Maximum & Minimum Reservoir levels & Spillway Discharge from 1963-64 to 2022-23	158
3.10	Capacities of Tungabhadra Reservoir from 1953 To 2016	159
3.11	Area – capacity table for TB Reservoir (As per Topographic Survey 2016)	160
3.12	Details of Ayacut and Discharges of DP's & Distributaries of RBLLC up to Board Limit	162
3.13	Details of Ayacut of DP's & Distributaries of RBLLC beyond Board Limit	165
3.14	Details of Ayacut and Discharges of Distributaries of RBHLC Up to Board Limit	166
3.15	Details of Ayacut of Main canal and Branch canals of RBHLC beyond Board Limit	167
3.16	Details of Ayacut and Discharges of Distributaries of Left Bank Main canal (LBMC)	168

3.17	Details of Ayacut and Discharges of Left Bank High Level canal (LBHLC) and Raya Basavanna Canal	170
3.18	Details of Telemetry Locations in TB Project Canals	171
4.1	Organization chart of Hydro Electric Wing	174
4.2	Power Generation and Utilization	175
4.3	Generation Cost per Unit	176
5.1	Organization chart of Fisheries Wing	177
5.2	Physical Performance of Fisheries Wing	178
6.1	Organization chart of Health & Medical Unit	179
8.1	Organization chart of Security Section	180
	Abbreviations	181

LIST OF FIGURES

3.1	Water Allocation in various Irrigation Systems of TB reservoir as per KWDT	47
3.2	10 day Water Indent and Actual releases made in RBHLC during 2022-23	48
3.3	10 day Water Indent and Actual releases made in RBLLC during 2022-23	49
3.4	Tungabhadra Dam – Inflows v/s Utilizations	50
3.5	Share of states and Actual Drawals	51
3.6	Tungabhadra Reservoir – Reduction in Capacity	52
4.1	TBHE Scheme – Total Power Generation and Cost per Unit (KWH)	85

1.1 RIVER TUNGABHADRA

Tungabhadra River is one of the major tributaries of Krishna River in South India. The river finds a mention in the epic Ramayana as Pampathirtha. Hampi, the seat of power of the Vijayanagar Empire founded in 1336 AD, is located on the southern bank of the Tungabhadra River.

Tungabhadra River derives its name from the confluence of two streams, the Tunga and the Bhadra, both of which rise in the wooded eastern slopes of the Western Ghats in the State of Karnataka and flow eastward. After confluence of these two streams at Kudali near Shimoga, the Tungabhadra runs for about 531 km and joins the river Krishna at Sangameswaram near Kurnool in the State of Andhra Pradesh. The river runs for 382 km in Karnataka, thereafter forms the boundary between Karnataka and Andhra Pradesh for 58 km and flows for the remaining 91 km in Andhra Pradesh. Tungabhadra sub-basin is part of the Krishna basin with a drainage area of 69,552 Sq.km. The river basin is influenced by the South-West monsoon, with copious inflows during monsoon which dwindles to few cumecs in summer months.

The drainage area of the Tungabhadra River in the Western Ghats receives about 4500mm of rainfall, while in the Rayalaseema area in the Peninsular

Plateau receives less than 500 mm of rainfall. As major portion of the Tungabhadra catchment lies in the center of the Peninsular plateau. The basin receives around 560 mm of rainfall only in a year.

The high spatial and temporal variation of the rainfall exposed the valley in the Peninsula to the vagaries of intermittent famine and droughts.

1.2 HARNESSING OF TUNGABHADRA WATERS

For harnessing the Tungabhadra water, the great Rayas of the Vijayanagar Empire built 17 anicuts across the Tungabhadra. With the fall of Vijayanagar Empire later in 1565 AD, these irrigation systems lapsed into despair. During pre-independence days, the Tungabhadra was the border between the Princely State of Hyderabad on the north bank and then British State of Madras on the south bank. These States were keen to harness waters of the Tungabhadra, but no agreement on sharing the water could be reached. The sharing of waters of Tungabhadra between Hyderabad and Madras began with the construction of Sunkesula Anicut in the year 1861 for diverting water to Kurnool-Cuddapah Canal.

1.3 GENESIS OF TUNGABHADRA PROJECT

Sir Arthur Cotton originally conceived the Tungabhadra Project in the year 1860 to alleviate the sufferings of the people of the districts of Bellary, Kurnool and Cuddapah in the then State of Madras on the south bank and Raichur district of the then Hyderabad on the north bank. However, the project was not taken up due to economic considerations. It was in 1902, Col. Smart, Chief Engineer of Madras Irrigation submitted a project report on Tungabhadra Dam to the First Indian Irrigation Commission. The report envisaged construction of a storage reservoir, to make a low-level canal on the right bank to supply water to Bellary District and to Kurnool District and at the same time a High level canal on right bank to cut through the watershed into Pennar and supplement the supply into that river which would then by means of storage serve portions of Anantapur, Cuddapah and Nellore Districts. A preliminary report was made in 1903. After detailed investigation Mr. Mackenzie, Chief Engineer of Madras Irrigation submitted a detailed project report in 1906. This report envisaged a reservoir at Mallapuram, at the present site, to provide irrigation for 3.23 lakh hectares of wet and garden crop, 0.61 lakh hectares of second crop and for protection of 3.34 lakh hectares of dry crops in the districts of Bellary, Kurnool, Anantapur, Cuddapah and Nellore.

In the year 1930, Government of Madras proposed a joint project with Hyderabad at the present dam site. After protracted negotiations and discussions, followed by arbitration of the Government of India, two agreements were reached, between Madras and Hyderabad during June 1944 and between Madras and Mysore during July 1944 finally clearing the ground for execution of the Tungabhadra Project.

The June 1944 agreement between Madras and Hyderabad provided that each side may draw 1841 Mm³ (65 TMC) of water for irrigation, construction of a large dam jointly at Mallapuram (present dam site) and an unspecified quantity of water to be used for hydro power generation and let down the river. The July 1944 agreement between Madras and Mysore provided that Mysore would not claim any share of water from the reservoir at Mallapuram after upstream abstraction of the agreed quantity.

1.4 PROJECT CONSTRUCTION

After, the two agreements executed between Madras & Hyderabad during June 1944 and between Madras & Mysore in July 1944 finally clearing the ground for execution of Tungabhadra Project, Sri C.C.Dalal, a Hyderabad Engineer proceeded to design the Dam. The Government of Madras entrusted a team of engineers under Sri M.S.Thirumale Iyengar to design the dam and canal system. Thus, two independent project reports were prepared.

The project report prepared by Sri M.S. Thirumale Iyengar in 1942 consisted of a dam at Mallapuram and two canals with alternative schemes for the right bank. The Government of Madras accepted this project report with certain modifications. The project was finally accepted as a Joint Project consisting of a Dam at Mallapuram to impound 3,766 Mm³ (133 TMC) of water in the reservoir. The irrigation system comprised a left bank main canal for irrigating areas in Raichur district, a right bank low level canal for irrigating areas in Bellary and Kurnool districts along with distribution system from these canals. Development of hydroelectric power through power houses at left and right banks at dam and a workshop was established on the Right Bank for manufacturing at Hampi was also envisaged.

By the end of year 1944, Government of India sanctioned the joint scheme. The index map of the project is at **Annexure 1.1**. The project was formally taken up for construction with laying of foundation stone on 28th February, 1945 by His Highness the Prince of Berar on the left bank and His Excellency Sir Arthur Hope, Governor of Madras on the right side as a joint venture of the Governments of Hyderabad and Madras.

Two independent builders, two governments, two Chief Engineers and two corps of workmen built the dam from opposite banks of the river. There were differences of opinion on many issues including designs, specifications and

method of execution. A Committee of Chief Engineers was setup to sort out these issues. The Committee often met to settle the arising issues. The eminent Engineer and Statesman Sir Mokshagundam Visvesvaraya was unanimously selected as Chairman of the Board of Chief Engineers in 1947. It was the decision of the Chairman that prevailed on many of the contentious issues of designs, use of surkhi mortar, single design for the dam and sharing of the cost etc. The Government of India was always available as a court of last resort. The field engineers were given complete set of drawings and printed specifications for each item of work. The use of surkhi in mortar made a big saving in cost of construction. A tram line was constructed to transport earth for surkhi. Due to adoption of stone masonry, use of machinery was kept to bare minimum. A workshop was established on the Right Bank for manufacturing the sluice gates and spillway gates. This workshop later became a pioneer fabricating company of India known as M/s Tungabhadra Steel Products Ltd.

As the Reservoir submerged the Valvapur and Hosakota anicuts constructed by the Rayas, a sluice was provided on the right side of the dam with a lead channel to connect the old Raya and Basavanna channel to provide irrigation for 11 months. Similarly, the old Koregal Anicut (left flank of Valvapur Anicut) and its channel got submerged in the Reservoir. So, a channel has been connected to the first tributary of the left bank main canal to serve the old ayacuts.

The 1.6 km long dam, with its two saddles on the left side was ready to impound the monsoon flow up to 491.642 m (1613 ft) level in the year 1953. Water was let into the canals on both banks on 1st July 1953. The full reservoir capacity was, however, not available as erection of 33 spillway gates was not completed by then. The erection of gates, Spillway Bridge, road on top of dam, utility tower, etc. were completed by June 1958. The salient features of Tungabhadra Project is at **Annexure 1.2.**

The Tungabhadra Dam Comprises of 1798.28m long masonry Dam including Spillway portion of 701 m with 33 Spillway gates, a 472.44 m long composite dam and 137.16 m long earthen Dam. The reservoir of the project is spread over 378.10 Sq.Km at FRL. Irrigation is provided through canal systems taking off from Left Bank and

Right Bank. The project generates hydro power through three power houses located at left right toe of Dam and at Hampi.

The breakup of the project cost is given in the following table. The project has a very high Benefit Cost ratio. The Benefit Cost ratio for irrigation alone was 11.8.

Breakup of Project Cost

Sl. No.	Scheme	Cost (Rs. crores)
1.	Irrigation Scheme: <ul style="list-style-type: none"> • Head Works • RB LLC • RB HLC • LBMC 	17.98 16.27 33.22 50.00
	Sub-total	117.47
2.	Hydro Electric Scheme	13.29
	Total	130.76

2.1 CONSTRUCTION OF THE BOARD

The Tungabhadra project was taken up by then States of Madras and Hyderabad during February 1945. With the formation of Andhra State, as per the Andhra State Act 1953, certain areas of the project on the right side of the river belonging to the then Madras State were transferred to the then Mysore State and the project became a Joint venture of the then States of Mysore, Andhra and Hyderabad. This resulted in more than 55 percent of irrigated area on the right bank of the river falling in the state of Andhra and the Reservoir with the head reaches of the canal system lying in the State of Mysore. The center line of the Tungabhadra River which was the boundary earlier no longer remained so and the canal on the right bank meandered through the State of Andhra and Karnataka. This situation warranted constitution of an independent body to look after the timely completion of the approved project, its maintenance and oversee distribution of benefits to the States. Subsequently, as per the Andhra State Act, 1953, President of India was authorized to give directions for the completion of the Project and its operation & maintenance thereafter. Accordingly, the Tungabhadra Board, a Statutory body was constituted by the President of India in exercise of the powers vested under sub section (4),

section 66 of Andhra State Act, 1953 for completion of Tungabhadra Project and its operation & maintenance. It started functioning from 1st October, 1953 vide notification No. DW II- 22 (129) dated 29.09.1953 of the then Ministry of Irrigation and Power.

The Board consisted of Chairman appointed by Government of India and six Members. The Members were Chief Engineers of both Irrigation and Power Departments of the Government of Andhra, Mysore and Hyderabad. Chairman of the Central Water and Power Commission was appointed as the Chairman of the Board in addition to his normal duties. The Board was entrusted with the task of completion of the Project and to deal with all matters relating to works, which were common to both the States of Andhra and Mysore.

The Board was reconstituted with effect from 15th March, 1955 vide Notification No DW VI (4) (9) dated 10.03.1955 of the then Ministry of Irrigation and Power (**Annexure 2.1**). The reconstituted Board consisted of a Chairman appointed by the Government of India and four Members representing Government of India, Andhra, Mysore and Hyderabad. After the reorganization of the States in 1956, the Hyderabad Government representative was deleted from Board vide Notification No. 39(25)/56 DW.VI dated 01.11.1956 by

the then Ministry of Irrigation and Power. The Board was further reconstituted as per AP Reorganization Act, 2014 that bifurcated the State of Andhra Pradesh into Telangana and residuary Andhra Pradesh State.

2.2 PRESENT COMPOSITION OF BOARD

The present composition of the Tungabhadra Board is as follows:

Chairman (Nominated by GoI)	Member-Secretary, KRMB, Hyderabad.
Member (Representing GoI)	Financial Adviser and Joint Secretary, Ministry of Jal Shakti, New Delhi.
Member (Representing GoAP)	Engineer-In-Chief (Irrigation) Water Resources Department, Vijayawada.
Member (Representing GoT)	Engineer-In-Chief (Irrigation), Irrigation & CAD Department, Hyderabad.
Member (Representing GoK)	Secretary to Government, Water Resources Department, Government of Karnataka, Bangalore.

The following were the Chairman, Members and Secretary during the year 2022-23:

Chairman, Tungabhadra Board:

Shri D.M.Raipure
(Since 16.06.2021)

Member, Government of India:

Ms. Richa Misra
(Since 08.03.2022)

Member, Government of Karnataka:

Shri Krishnamurthy B Kulkarni
(Since 01.10.2021)

Member, Government of Andhra Pradesh:

Shri C. Narayana Reddy
(Since 01.01.2020)

Member, Government of Telangana:

Shri C. Muralidhar
(Since 28.05.2014)

Secretary, Tungabhadra Board:

Shri G. Naga Mohan
(Since 06.08.2018)

2.3 FUNCTIONS OF THE BOARD

The important functions of the Board, initially laid down were:

- ✓ Completion of the construction of the sanctioned project;
- ✓ Regulation of supplies of water and power in accordance with such rules as may be made in this behalf by the Board (From 1976-77) onwards, in compliance of the KWDT Award, as notified by GOI);
- ✓ Maintenance of canals and other works common to both the States of Karnataka and Andhra Pradesh;
- ✓ Maintenance of the dam and reservoir of the project;
- ✓ Granting of lease of fisheries in the reservoir and in the canals;
- ✓ Proper utilization of land acquired for the purpose of the project; and
- ✓ Any other function incidental to or connected with the functions specified in above clauses.

In the discharge of its assigned functions, the Board exercises powers of a State Government. Board makes its own rules for the conduct of its own business. The Board appoints a whole time Secretary.

2.4 STAFFING PATTERN

All the posts in the Board are sanctioned on year-to-year basis by the Board. The post of Secretary is filled by Ministry of Jal Shakti, River Development & Ganga Rejuvenation and Assistant Secretary is

filled by Indian Audit and Accounts Service on deputation basis from the Government of India. All other regular posts of the Board are cadre posts of the participating States of GoK and GoAP in an agreed ratio. Work charged and Contingent staff of the Board are treated as Board employees. Officers and staff drawn on deputation from the GoI and posted by GoAP and GoK to the Board are governed by the respective service rules of their parent Department. However, they remain under the administrative control of Board during their tenure in Board.

Eight regular staff members comprising of four Assistant Sub- Inspectors & four Security Head Constables from Police Department of GoK are on deputation to Board and they are working in the Security Section of TB Board and they are repatriated to parent department on deployment of KSISF personnel.

2.5 KWDT AWARD

The award of the Krishna Water Disputes Tribunal came into force from the water year 1976-77. The relevant extracts of clause IX and clause XVI of the Final Order of the KWDT is at **Annexure 2.2**.

2.6 State wise Water Allocation as per KWDT Award (TMC)

State	Gross allocation	Reservoir Evaporation losses	Net allocation
GoK	151.49	12.50	138.99
GoAP	72.00	5.50	66.50
GoT	6.51	0.00	6.51
Total	230.00	18.00	212.00

As per the KWDT award, the reservoir evaporation losses of 509.70 Mm³ (18 TMC) shall be equally shared by the left canal system and right bank canal system (9.00 TMC each). The share of the reservoir loss of right bank canal system (9.00 TMC) shall be shared by Karnataka and Andhra Pradesh in the ratio of 3.5:5.5. Details of the water allocation to various systems are given in **Figure 3.1**.

The Krishna Water Disputes Tribunal (KWDT) award states that, the Board would continue to prepare the working table for utilization of the water stored in the reservoir and regulate the sharing of water between the States of Karnataka, Andhra Pradesh and Telangana as per the allocations made in the award.

2.7 PRESENT FUNCTIONS

The project was fully commissioned with completion of the Right Bank High Level Canal in 1970. Since then Tungabhadra Board has not taken up any major construction till 2016. Modernization of Right Bank Canals of TB Board has been taken up from January 2017 onwards. The present functions of the Board include:

- ✓ Regulation of supplies of water to the States of Andhra Pradesh and Karnataka in accordance with the clause IX E(1) to (5) of Final Order of the Krishna Water Disputes Tribunal relating to the Tungabhadra Project;
- ✓ Regulation & monitoring of power from the three power houses on the right side in accordance with such rules as may be made in this behalf by the Board;

- ✓ Maintenance of the dam and reservoir of the project, common to both the States viz., right half of the dam and 33 spillway gates including safety aspects of the dam and spillway;
- ✓ Maintenance of the common portion of the Right Bank High Level Canal and Low Level Canal including common distributaries of Right Bank Low Level Canal and any other works common to both the States of Andhra Pradesh and Karnataka;
- ✓ Maintenance of the two power houses on the right side including renovation and refurbishing;
- ✓ Granting of lease of fisheries in the reservoir and in the main canal;
- ✓ Proper utilization of land acquired for the purposes of the project;
- ✓ Development of new schemes for hydro power generation on common facilities and its regulation;
- ✓ Generation of revenue from the assets of the Board and create assets for increasing the revenue;
- ✓ Any other function incidental to or connected with the functions specified in above clauses.

2.8 ORGANIZATIONAL STRUCTURE

For carrying out its various functions the Board has been divided into the following two main Wings:

- Irrigation Wing (IW)
- Hydro Electric Wing (HEW)

In addition, the Board comprises a Fisheries Wing, a Park and Gardens Unit,

a Health and Medical Unit and a Security Section. All the Wings and Units of the Board are under the administrative control of the Secretary of the Board. The Secretary also functions as Chief Security Officer and Vigilance Officer of the Board. The IW and HEW are headed by part time Chief Engineers of the Karnataka and Andhra Pradesh respectively.

The Organization Chart of the Tungabhadra Board is at **Annexure 2.3 & 2.4.**

2.9 APPLICABILITY OF RULES TO BOARD EMPLOYEES

The Work charged and Contingent employees of the Board are recruited by the Board at the time of construction of Project and termed as "Board employees", and they are governed by the following rules.

Category	Rules Applicable
Work charged staff who have completed 10 years of service	Karnataka Civil Service Rules.
Contingent staff of Health and Medical Unit who have completed 10 years of service	Karnataka Civil Service Rules.
Work charged & Contingent staff of all wings and units, who have not put in 10 years of Service	Work Charged Service Rules as laid down in the KPWD Code and Other orders of Karnataka Government.

2.10 ADMINISTRATION

The administrative control of all officers and staff working in the Board rests with the Board. Their appointments, repatriation from the Board and their internal postings and transfers within the Board are decided by the Board. Secretary is the executive head of the Board and authenticates all orders and decisions of the Board. He is assisted by a Secretariat and exercises administrative control over the IW, the HEW and other Units. Day to day administrative control of all officers and staff working in the various wings of the Board rests with the respective heads of Wings.

2.11 BOARD MEETINGS

During the year 2022-23, Board meeting was held on 19th May 2023 at Hyderabad and took decisions on the issues placed before it. Some of the important decisions are as below;

1. Constitution of Tender Evaluation Committee for works in TB Board for both Irrigation & TBHES wings and modification of existing procedure for according Administrative approval for works in TBHES wing.

Board noted that, in accordance to the Board decision, Tender Evaluation Committee for works amounting to Rs.10 Crs & above in TB Board is being followed for both Irrigation & TBHES wings with effect from 20.06.2022. Further, for according Administrative approval for works in TBHES wing, the modified procedure as per 218th Board Meeting decision is being followed with effect from 20.06.2022.

2. Raising of Spillway Gates height to avoid the overtopping of water over the Gates as per the recommendations of Dam Safety Review Panel (DSRP).

Board noted that, as per its decision to raise the height of the Spillway Gates by "one feet" to avoid the overtopping of water over the Gates as per the recommendations of Dam Safety Review Panel (DSRP), the work of "Providing additional skin plate for a height of 300 mm & suitable stiffeners to spillway gates of TB Dam" has been entrusted to the Agency Sri R.Nagabhushanam, Contractor, Hosapete and the work is in progress.

Board also noted that, as per the suggestion of DSRP for raising the height of gates beyond 300mm upto 1500mm the matter has been referred to CWC

3. TB Board – Mini Zoo – Cancellation of Recognition of Mini Zoo as per provisions of Subsection 6 of Section 38-H of Wild Life (Protection Act) 1972 by Central Zoo Authority (CZA).

Board noted that, in line with the directions of CZA, the transfer of animals from Tungabhadra mini Zoo was successfully completed on 09.11.2022. Further, Board agreed for usage of the mini Zoo area to an extent of nearly 10 Acres for establishing MULTIMEDIA LASER SHOW PROJECT on PPP model.

4. Modernization Works of TB Board Right Bank Canals.

Board took note of the progress made on Modernization works for Tungabhadra Board Canals (both RBHLC & RBLLC) right from 2016-17 onwards and the present status along with intricate problems being

faced in getting adequate finances from Andhra Pradesh Govt.

The Modernization works for Tungabhadra Board Canals was taken up in a phased manner starting with RBHLC from 2016-17 onwards and the present status of the RBHLC & RBLLC are as given under;

I. Right Bank High Level Canal (105.435 Km)

Lining of canal for major length between Km 0 to Km 105.435 has been completed except Canal Cross drainage works (UT, Aqueduct & Super passage), Km 0 to 40 deep cut reaches and related stabilization works.

Due to the completion of major portion of modernization work of RBHLC from Km 0 to Km 105.435 i.e., up to AP border) the canal is now able to draw the design discharge of 4000 cusecs (against earlier discharge of 3200 cusecs) at its head and now capable of carrying the design discharge of 2575 cusecs at Andhra Pradesh border (against earlier discharge of 1400cusecs). At present, we have already delivered a discharge of 2350 cusecs and are in a position to deliver the design discharge of 2575 cusecs at Andhra Pradesh border provided they (AP side) are ready to take it.

Balance modernization works

- The Modernization works awarded during 2022-23 in the left over reaches from Km 53 to 95 are in progress and likely to be completed in 2023-24.
- The Modernization works for the year 2023-24 are proposed in the leftover reaches from Km 0 to 40 along with CM & CD repair works (UT & Aqueducts) and the same

was got approved on 28.12.2022. These modernization works are under tender evaluation stage and after fixing the Agencies, the works will be taken up during the working season of 2023-24 subject to assurance from GoAP.

II. Right Bank Low Level Canal (21.3+250.580 Km) Power Canal (21.3Km)

Lining of canal except for few deep cut portions between Km 0 to Km 20 has been completed. **RBLLC (250.580 Km)** The Modernization of RBLLC was planned to be completed in a span of 5-6 years.

Km Range	Progress of Work
0-72	Started in 2019-20 and completed during 2021-22
72-115	Started in 2020-21 and completed during 2022-23
115-205	Started in 2022-23 and 60% of the works are completed

The quality of works for all the packages is being monitored through third party reputed agencies like Bureau VERITAS in addition to the Departmental Quality control and Vigilance Unit of TB Board.

Due to partial completion of modernization works in RBLLC (including Power Canal) up to Km 205 has resulted in increased realization of around 1100 cusecs at Km 133 (against earlier realization of 750 cusecs) and around 600 cusecs at Km 250.580 i.e., AP border (against earlier realization of 350 cusecs).

The Board also noted that, the Board Secretariat has accorded Administrative Approval during February, 2023 for modernization works from Km 205.450 to

Km 250.580 & Distributaries of RBLLC and leftover reaches of RBHLC from Km 2 to Km 20 and Km 22 to Km 40 anticipating additional funds during the Month of March 2023 from Andhra Pradesh as it is a general practice.

5. Emergency works taken up for Restoration of Hagari Aqueduct and proposal for construction of New Aqueduct parallel to the present one.

Board took note of more than 60 years old Hagari Aqueduct and its survival during monsoon floods of 2022 as follows;

Due to heavy floods on 08.09.2022, around one lakh cusecs of water was flowing in the Hagari River resulting in visible cracks over the Road Slab of Hagari Aqueduct at Pier No.9 and 10. There was horizontal displacement of about 150mm and vertical settlement of about 300mm of stone masonry of Pier No.9 towards upstream of river at upstream edge. These observations were made from the top of the Road Bridge and there was no possibility to go down to bed level of the River as the water in the River was flowing with high velocity. The Pier No. 9, 10, 12, 13, 14 of Aqueduct were settled down and detached from the trough, and also well caps were twisted, tilted and broken down.

As a part of taking immediate restoration measures, steps were taken, i) to clear the blocked vents and remove the over burden on upstream and downstream side of Aqueduct for entire length of Aqueduct ii) for the formation of Ring bund cum Road, and On 01.10.2022, the flood increased in the river and the water over flowed over and above the formed bund. Due to continuous rains and affected roads, collection of boulders by the Tippers or Lorries were slowed down

and Temporary restoration was also became tough. Gradually the wells and well caps were also damaged for the Piers No. 9 to 12. On 13.10.2022, due to heavy rain fall in the upstream catchment area and water releases of 12,000 cusecs from the Bhairavanithippa Project, the Hagari River water rose back to around 60,000 cusecs at site. Due to which the Pier No.15 is completely collapsed and the trough was hanging without any support. On 21.10.2022 after receding of flood, a temporary support was given to the trough between Pier No.14 and 16 in place of washed out Pier No.15 using Lifting Mechanism and providing Cribs as per designs obtained from Sri Jaigopal, Struct Geotech, Bengaluru, a Technical Consultant who was engaged by the TB Board for this purpose. The Pier No.11 was also in gorge portion of the River and has experienced the same flood. To avoid further damages and to safeguard the Pier No.11 structure, the Consultant advised to include the same for permanent restoration work along with other piers for the time being until a New Aqueduct is constructed.

Immediate action for restoration of Hagari Aqueduct was taken up based on the report given by Shri R K Jaigopal, Managing Director, Struct Geotech Research Laboratories, Bengaluru and a temporary support was given for Pier No.15 (which was washed away) by using steel 'I' sections (ISMB 600), Steel plates, Wood reapers and 100 Tonne capacity jacks and released water on 02.11.2022. The temporary restoration work was completed in all respects by 30.11.2022. Thereafter permanent restoration works

were taken up and the same are under progress

All the Members of the Board watched the photos of the restoration work of Hagari Aqueduct taken up on a war footing basis and appreciated for the timely action taken by the Board officers and thus saving Hundreds of crores of rupees worth both Khariff and Rabi crops of the Ayacut downstream of the Hagari Aqueduct.

On deliberating the issue, the Board ratified the actions taken for Temporary restoration & Permanent restoration of Hagari Aqueduct.

Further, Board was informed that, the technical experts along with several political representatives who had visited the site during the above incident have suggested to construct a New Aqueduct on Hagari River at the earliest in place of the present 70 years old Aqueduct. Since, after completion of the present permanent restoration works, the present Aqueduct may likely to sustain for another 5 to 10 years, it was proposed for preparation of a DPR for construction of a new Aqueduct just upstream and parallel to the existing Aqueduct i.e., across Hagari river with a carrying capacity of 1500 cusecs for RBLLC at Km 121.00. For this Agenda item, the Member, Karnataka gave his consent whereas Member, AP sought further discussion.

Deliberating on this issue Board decided that, let a scientific study be carried out regarding the stability of the existing Aqueduct (both substructure and superstructure) first and to confirm how

long the present permanent restoration work under progress will be sufficient and when a new Aqueduct is required to be constructed. After obtaining the Expert opinion, the proposal of preparing DPR if required may be placed in the subsequent Board meeting for taking appropriate decision by the Board.

6. Design, Supply, Installation and Commissioning of Multimedia Laser and Video Show on Water Screen With Musical Dancing Fountain with Light & Sound and its Operation & Maintenance for 25 Years at TB Dam Gardens on PPP Model.

Board after due deliberations agreed to utilize the Board land used earlier for mini Zoo for establishing MULTIMEDIA LASER SHOW PROJECT on PPP model and directed that, it should be in a grand scale similar to the one in Akshardham in Ahmedabad to fetch additional revenue to the Board without incurring any expenditure. Further, Board directed the Board officials to explore such models and try to replicate or improve over it duly discussing with the Agencies running similar shows.

2.12 TRANSFER AND POSTINGS OF OFFICERS TO AND FROM THE BOARD

The transfer and postings of Officers to and from the Board is given at **Annexure 2.6.**

2.13 FINANCE

The Tungabhadra Board is an Interstate Project, the funds required for functioning of all the three wings are initially allotted by Govt. of Andhra Pradesh in every year by passing in its Legislative Assembly. The Funds

required for irrigation wing, hydroelectric wing and Fisheries wing are recommended and routed through Water Resources Department. Energy Department and Commissioner of fisheries Department of Govt. of Andhra Pradesh respectively. The entire expenditure for every month in respect of the TB Board is being initially borne by the Government of Karnataka through Sub Treasury, Hospet & District Treasury, Ballari. In turn the expenditure and receipt vouchers are forwarded to Ballari District Treasury and from there it is sent to Accountant General (A&E), Andhra Pradesh where the expenditure will be apportioned between Govt. of Andhra Pradesh and Govt. of Karnataka as per the agreed ratio/shares indicated below.

Share of Expenditure and Receipts

Sl. No.	Wing	Share of	
		GoAP	GoK
1.	Irrigation Wing:		
	RBHLC	71.00 %	29.00%
	RBLLC	55.56 %	44.44%
2.	Hydro Electric Wing	4/5	1/5
3.	Fisheries Wing	5/18	13/18

The Accountant General (A&E), Andhra Pradesh will send advice to RBI, CAS (Central Accounts section), Nagpur where necessary adjustments are done among the Member States (i.e. AP & Karnataka).

2.14 VIGILANCE CELL

The Vigilance Cell was set up in the Board with effect from June, 1957 to ensure high standard of work to prevent corrupt practices in the Board. Secretary, Tungabhadra Board is the Chief Vigilance Officer of the Board and enquires into all the complaints / allegations received against the officer's/officials working in the Board. As per the clarifications issued by the Ministry of Water Resources, Government of India vide its letter No.16/4/87-PII dated 23.08.1991 the Central Vigilance Commission has no jurisdiction over the Tungabhadra Board. As per the decision taken by the Board in its 146th meeting held on 20.02.1993 that, all cases of allegations against officials working in Tungabhadra Board shall be investigated by Chief Engineer, IB/Chief Engineer, Elec., TBHES or the Secretary himself as the case may be. Respective Chief Engineers shall send their investigation reports to the Secretary, TB Board who shall decide whether a prima- facie case exist or not. In case prima-facie case is established, Secretary, TB Board shall send his report to the respective State Governments of Karnataka/Andhra Pradesh for taking suitable action against the concerned official/officer. Such officials shall be repatriated by the Board to the respective State Governments. The Board in its 166th meeting held on 29th June, 1998 resolved that, "views of the Secretary, TB Board who framed charges against officers/officials on deputation to TB Board shall be ascertained before deciding the cases having financial

implications and irregularities. All cases of allegations against TB Board Work-charged employees (WCE) shall be investigated by the Secretary, Tungabhadra Board and will take suitable action against such WCE”.

STRENGTHENING OF VIGILANCE AND QUALITY CONTROL UNITS UNDER THE BOARD.

I. VIGILANCE UNIT

The Board decided to form a vigilance unit under the direct control of Secretary, Tungabhadra Board as decided in the 204th meeting held 03.08.2013 with the following set up;

1. Executive Engineer (AP Cadre)
2. Sub-Divisional Officer
(Karnataka Cadre)
3. 2 Section Officers (1AP & 1KA)

II. QUALITY CONTROL UNIT

Quality control unit consists of 1 SDO and 2 SO's. Board directed that Quality Control reports of various works under taken by the QC & ST Unit need to endorse a copy of the report to the Secretary, TBB including third party QC. This helps Secretary, TB Board in discharging Vigilance function in a better way which needs strict compliance.

III. INTERNAL AUDIT CELL

A team consisting of Assistant Secretary and Divisional Accounts Officer was constituted during 2013 to conduct internal auditing of Divisions, Sub-Divisions and all Offices under the Board every year.

2.15 LEGAL DISPUTES

Since the formation of the Board, many disputes have arised between the Board management and its employees,

contractors, public etc., and are at various courts in the States of Karnataka and Andhra Pradesh. Such disputes have been generally resolved amicably as far as possible.

2.16 ESTATE MATTERS

The Board had acquired considerable land for the construction of Dam, Canals, Office buildings, Residential colonies and also for meeting the community requirements. In the beginning, leasing of small extent of areas in and around the residential colonies was made, facilitating traders to run different types of commercial establishments for the benefit of Project staff. This has created inherent problem of encroachments of vacant lands in the colonies as well as along the canals. Encroachments along the canals restrict the borrow area for closing the breaches of the canals. Similarly, encroachment in the natural rivulets and drains near the escapes creates problems for operating the shutters of the escapes, whenever necessary.

In order to prevent encroachments, plantation of the vacant land and all along the canals has been taken up on a large scale. This has controlled encroachment of Board's land to a large extent. Efforts have also been made to evict the illegal occupants. Further, decision has been taken in the Board meetings relating to leasing of Board land as follows:

1. In 171th meeting held on 07.04.2001: "In view of the likely expansion of activities of the Board in future and status of the board as trustee of the land in its possession, the Board opined that, its land should not be transferred by it directly for any other work”.

2. In 187th meeting held on 04.04.2008: "Further Board directed that gardening / fencing / Plantation may be taken up in the vacant land to avoid encroachments".
3. In 207th meeting held on 01.08.2015: " The land under T.B Board are the property of three states of Karnataka, AP and Telangana and the land can only be leased to the Government Organizations and Public Sector Undertaking".

The Board reviewed the ground rent in its 213th meeting held on 27.12.2018 and accorded approval as shown in **Annexure 2.5**. These rates have come into effect from 01.01.2019.

Board accorded approval for enhancement of rent for the TB Board Quarters for allotting to the Non-Board Employees as under with effect from 01.01.2022 and directed to revise the rates once in every 5 years as below;

Sl No	Colony	Previous Rent Per Sq.Ft 2012	Enhanced Rent Per Sq.Ft 2022
1	2	3	4
1	Official Colony, TB Dam/ Toranagallu	2.50	5.00
2	P.L.C Area, TB Dam/ TBHES Colonies	1.50	3.00
3	Amaravathi Colony, Hospet	3.00	6.00

Note:

1. For Non-Board employees (Central/State/PSU employees): An amount equal to their HRA or above proposed rent at column 4 whichever is higher.
2. For Non-Board employees (other than Central/State/PSU employees): Proposed Rent as per the above table at column 4.

Further, the Board accorded approval to enhance the tariff rates for occupation of Vaikunta Guest House, Annexure and Inspection Bungalow with effect from 01.01.2022 as shown in **Annexure 2.5 A**.

The amount of license fee/rent towards Board land leased, Board quarters allotted to Non- Board / Private persons etc., collected for the year 2022-23 in respect of Irrigation Wing and Hydro Electric Wing is Rs.1,53,24,731/- and Rs. 36,63,834/- respectively.

2.17 A. LEASING OF M.S. THIRUMALE IYENGAR HALL ON PPP MODEL

The M.S.Thirumale Iyengar hall was handed over to the agency on PPP model for 7 years from 01.01.2021 to 31.12.2027 at the rate of Rs.84,60,000/- payable in 14 half yearly installments.

B. PROVIDING ROPEWAY CABLE CAR IN TB DAM GARDENS ON PPP MODEL.

The work of providing Ropeway cable car in TB Dam Gardens on PPP Model was awarded to M/s Ropeway & Resorts Pvt. Ltd. Kolkata jointly with M/s MD Quad Infrastructure Pvt. Ltd. Bengaluru and the agreement was concluded on 10.05.2022 and survey work for preparation of DPR work is under progress.

2.18 FOUNDATION DAY CELEBRATION OF TUNGABHADRA PROJECT (1945-2023)

Tungabhadra Project was taken up for construction by laying of foundation stone on 28th February 1945 by His Highness the Prince of Berar on the left bank and His Excellency Sir Arthur Hope, Government of Madras on the right side as a joint venture of the Governments of

Hyderabad and Madras. Tungabhadra Project stepped into 79th year foundation day on 28th February 2023. On this account, TB Board has celebrated its foundation day by organizing games/sports/ competitions like Shuttle, Carom, Running, Cooking, Rangoli etc. with TB Board staff & their families. All the employees and their families have participated in these competitions/celebrations very actively. Foundation day function was organized with grand cultural program at Gundlakere (At Km 0.00 of RBLLC), Board employees & their families participated in the cultural program. The winners of different games/sports/ competitions and also to those who participated in the cultural program were awarded with prizes by Chief Guest Shri D.M.Raipure, Chairman, TB Board, Shri G. Naga Mohan, Secretary, TB Board & Shri K.Sreekantha Reddy, Superintending Engineer, IB, TB Board & S Rushabendrappa, Superintending Engineer, TBHES, TB Board.

2.18 A. During the Last year following VIP's/Dignitaries and other Teams visited the TB Dam

SI No	Visitor's Name	Date of Visit
1	Sri Thawar Chand Gehlot, Hon'ble Governor, Karnataka	08.12.2022 & 21.03.2023
2	Sri MP Singh, Chairman, KRMB, Hyderabad	29.12.2022
3	Sri. Narayana Reddy, Member (AP), TB Board & ENC (AP), Vijayawada	26.07.2022
4	Sri. Govind M Karjol, Major & Medium irrigation Minister, GoK	15.12.2022
5	Officers of Monitoring South Organization, Central Water Commission, Bangalore, National Dam Safety Authority, Southern Region, Chennai	24.03.2023
6	CECRI team, Karaikudi, Tamilnadu	14.02.2023 to 24.02.2023

2.19 REDRESSAL OF STAFF GRIEVANCES

All the regular posts of Board are cadre posts of Government of Karnataka and Andhra Pradesh, except that of the Secretary and Assistant Secretary, who are drawn from Government of India on deputation basis. The grievances of all staff regarding service matters are thus dealt by their parent departments only.

2.20 MONITORING OF RESERVATION FOR SC/ST/ OBC AND FOR PHYSICALLY CHALLENGED

All the regular posts of Board are cadre posts of Government of Karnataka and Andhra Pradesh, except that of the Secretary and Assistant Secretary, who are drawn from Government of India on deputation basis. There is no direct recruitment in the Board. The State Governments, both Andhra Pradesh and Karnataka have to monitor and deploy their staff as per prevailing rules in their respective States. The following committees have been constituted to look into the complaints of Scheduled Castes and Scheduled Tribes community.

SC Committee;

1	Shri G. Naga Mohan, Secretary, TB Board	Chair person
2	Shri. R.Sreekantha Reddy, SE, IB, TB Dam	Member
3	Shri S Rushabendrappa SE, TBHES, TB Dam	Member
4	Shri. M.Neelakanta Reddy Executive Engineer, LLC Division, Ballari.	Member
5	Shri.G.T.Ravichandra Executive Engineer, HW & HLC Division, TB Dam	Member
6	Shri Y.Danakarna(SC) Deputy Executive Engineer/Shift, Hampi Power House.	SC Member

ST Committee;

1	Shri G. Naga Mohan, Secretary, TB Board	Chair person
2	Shri S Rushabendrappa SE, TBHES, TB Dam	Member
3	Shri. R.Sreekantha Reddy, EE, Vigilance , TB Dam	Member
4	Shri.G.T.Ravichandra Executive Engineer, HW & HLC Division, TB Dam	Member
5	Shri P.V.Krishna Kumar (SC), Sub Divisional Officer, No.2 LLC Sub-Division, Ballari.	ST/SC Member

2.21 COMMITTEE FOR COMPLIANTS ON SEXUAL HARASSMENT

In accordance with the guidelines laid down by the Supreme Court to deal with complaints of sexual harassment of women employees, following Committee

has been constituted to look into the complaints of women employees at work place under Tungabhadra Board.

1	Shri G. Naga Mohan, Secretary, TB Board	Chairperson
2	Shri S Rushabendrappa SE, TBHES, TB Dam	Member
3	Shri R Sreekantha Reddy, SE, IB., TB Board TB Dam	Member
4	Smt K Tejaswini, DEE, TBHES, TB Dam	Member
5	Smt. J.Sashi Rekha, Asst. Engineer, Elecl, TBHES, TB Dam	Member
6	Kum Chaitra H Gadad, Section Officer, TB Board, TB Dam	Member

The Committee has held its meetings from time to time and also met the women employees of the Board. No formal complaints were received by the Committee during the year 2022-23.

79th YEAR FOUNDATION DAY CELEBRATIONS







**VIP'S/DIGNITARIES VISIT TO TB DAM
SRI. THAWAR CHAND GEHLOT, HON'BLE GOVERNOR, KARNATAKA**



**SRI. GOVIND M KARJOL, MNINISTER OF MAJOR AND MEDIUM IRRIGATION,
KARNATAKA**



**ENGINEER-IN-CHIEF (IRRIGATION),
WATER RESOURCES DEPARTMENT, AP, VIJAYAWADA**



SRI. M.P SINGH, CHAIRMAN, KRMB



**INAUGURATION OF CHILDREN PARK
BY SRI D.M RAIPURE, CHAIRMAN, TBB**





INAUGURATION OF WATER PARK BY SRI D.M RAIPURE, CHAIRMAN, TBB





INAUGURATION OF RENOVATED TBHES QUARTERS BY SRI D.M RAIPURE, CHAIRMAN, TBB



15TH AUGUST-2022 INDEPENDENCE DAY CELEBRATIONS



CELEBRATION OF ENGINEERS DAY ON 15TH SEPTEMBER 2022



ACTIVITIES OF SWACHH BHARAT ABHIYAN



AWARENESS PROGRAM ON IMPROVED WATER RESOURCES MANAGEMENT TO STAKEHOLDERS OF TB DAM COMMAND CONDUCTED ON 24.03.2023 AT TB DAM.



**AWARENESS MARCH ON WATER CONSERVATION
CONDUCTED ON 24.03.2023 AT TB DAM**



TREE PLANTATION CAMPAIGN CONDUCTED ON 24.03.2023 AT TB DAM



**LAKE FESTIVAL-Grameena Cultural Activities
CONDUCTED ON 24.03.2023 AT TB DAM**



3.1 IRRIGATION WING OF THE TB BOARD (IW)

Irrigation Wing (IW) of the Board is in charge of the right half of the main masonry dam, all 33 spillway gates, whole of the reservoir, Right Bank High Level Canal (RBHLC) and Right Bank Low Level Canal (RBLLC) up to Board's limit. The RBLLC also includes Power Canal and certain common distributaries. The Tungabhadra Project has been allocated 212.00 TMC of water by the KWDT, which is excluding reservoir evaporation losses. The utilization for the year 2022-23 is 5392.272 Mm³ (190.432 TMC). As the Left Bank Canals serve command areas exclusively in Karnataka, water regulation and maintenance of these canals are carried out by the Government of Karnataka. The total area benefited by irrigation through the right and left bank canals in the States of Karnataka and Andhra Pradesh is 13.38 Lakh acres apart from about 3.95 lakh acres of existing irrigation systems already established. The Irrigation benefits of Tungabhadra project is at **Annexure 3.1**

It is the responsibility of the Board to release indented quantity of water to the States of Andhra Pradesh and Karnataka at their off- take points beyond which, the responsibility lies with the respective State Governments.

3.2 FUNCTIONS

Primary Functions of Irrigation Wing are:

- To prepare working table for operation of the reservoir on the basis of water indent furnished by States, as well keeping with the KWDT award;
- To follow Reservoir operation in accordance with the Working Table including flood management and Dam safety
- To supply indented quantity of water, conforming to the working table, for Right bank Canal systems and River assistance
- To deliver specific discharges at Board limits of the RBHLC & RBLLC and at the common distributaries
- To render the water account of the reservoir and canal systems, including collection of daily drawals data for the systems on the left side from GoK

In addition to the above, the following maintenance and operation works are also entrusted to the IW:

- To maintain Right half of main dam from Ch 0.00 ft to Ch 3069.67 ft including drainage gallery and operation and maintenance of all the 33 spillway gates
- To maintain common portion of the Right Bank Canal system i.e., RBHLC from Km 0.000 to Km 105.435, RBLLC from Km 0.000 to Km 250.580 and the Power Canal from Km 0.000 to Km 21.300 and their regulators and distributary heads
- Common distributaries of the RBLLC

between Km 131.500 to Km 250.580 serving both Karnataka and Andhra Pradesh

- To execute and maintain civil works in the colonies and for all the Board's buildings including Guest House and Inspection Bungalows and
- To improve the horticultural activities in the dam area, colonies and canal banks.

The IW is headed by a Chief Engineer (part-time), who belongs to the Water Resources Department of GoK. Chief Engineer, Irrigation Central Zone (ICZ), Munirabad is normally deputed by GoK to act as Chief Engineer of the Board in addition to his normal duties. There is one post of Superintending Engineer, which is filled up by an officer from Water Resources Department of GoAP.

There are two Divisions headed by Executive Engineers - one at Tungabhadra Dam, which is filled by an officer from GoK and the other at Bellary which is headed by an officer from GoAP. All the other officers and staff of the Irrigation Branch of the Board are drawn from the Water Resources Departments of GoAP and GoK on 50:50 basis. Organization chart of Irrigation Wing is at **Annexure 3.2**.

3.3 INTER STATE CANALS

The RBLLC and the RBHLC serve the ayacuts in both the States and are termed as inter-State canals. The Board undertakes water management of these canals at distributary level. Maintenance

of these canals together with the distributaries serving the two states rests with the Board. There are 86 Nos. off take points in the RBLLC and 24 Nos. at RB HLC for releasing water to the States apart from delivering indented discharge to AP at Board limit of RBHLC and RBLLC.

(i) RIGHT BANK LOW LEVEL CANAL (RBLLC)

The RBLLC under the jurisdiction of the Board serves an ayacut of 37,518 ha (92,670 acres) in Karnataka and 63,588 ha (1,57,062 acres) in Andhra Pradesh. It originates as Power Canal from the tailrace pool of the Dam Power House with a designed capacity of 70.79 Cumecs (2500 Cusecs), carries water for a length of 21.300 Km and empties into the Hampi Fore bay for power generation at Hampi Power House. The tailrace of Hampi Power House falls into the Gundlakere Lake. The RBLLC continues from the Gundlakere Lake with Km 0.000 as chainage. Its designed discharge is 50.970 Cumecs (1800 Cusecs) and is 348.200 Km in length, of which the initial 250.580 Km is under the control of the TB Board. The rocky- undulating terrain in the initial 10 km length called for side walling, tunneling, aqueduct, high embankment, etc. Before finally entering into the State of Andhra Pradesh, the RBLLC meanders through the States of Karnataka and Andhra Pradesh. The details of the canal reaches in Andhra Pradesh and Karnataka are as shown.

RB LLC Reaches in States

Karnataka Reach	Total Length in km	Andhra Pradesh Reach	Total Length in km
0.00 to 131.50	131.50	131.50 to 135.70	4.20
135.70 to 147.80	12.10	147.80 to 148.00	0.20
148.00 to 156.00	8.00	156.00 to 188.00	32.00
188.00 to 190.80	2.80	190.80 to 250.58	59.78
Total	154.40		96.18

The RBLLC generally runs for nine to ten months in a year and is closed during May & June for maintenance works. Originally, it was an unlined canal. Subsequently, the lining of the canal has been taken up in a phased manner in identified vulnerable reaches in order to improve the efficiency of the canal. There are 10 common distributaries between Km 131.810 and Km 250.580, which serves ayacuts in both the States. The details of these common distributaries are given in **Annexure 3.3**.

The details of RBLLC up to Board Limit and beyond Board limit distributaries wise schedule discharge and ayacut are given in **Annexure 3.12 and 3.13**.

As per the KWDT award the water allocated for RBLLC for Karnataka and Andhra Pradesh is 538 Mm³ (19.00 TMC) and 679.60 Mm³ (24.00 TMC) respectively, which is exclusive of pro-rata reservoir evaporation losses of 99.11 Mm³ (3.50 TMC) and 155.74Mm³(5. 50 TMC) respectively.

As per the design of RBLLC, transmission losses were envisaged at a rate of 4 cusecs per million square feet of wetted area for unlined reaches and 1.50 Cusecs per million square feet of wetted area for lined reaches. In the Board meeting held on 5th

and 6th May, 1989, based on the results of joint gauging, Board granted approval for adopting transmission losses at 4 cusecs per million square feet of wetted area for the present. The Board has also permitted to make provision towards system losses not exceeding 3.4 Cumecs (120 cusecs).

(ii) Right Bank High Level Canal (RBHLC)

The agreement of June, 1956 between Andhra Pradesh and Mysore provided that the quantity of water to be drawn annually in right bank high level canal is to be 1415.84 Mm³ (50.00TMC) and is to be shared in the ratio of 35:65 between Mysore and Andhra Pradesh and the cost is to be shared on cusec mile basis between the two Governments. The agreement also provided that the common works of the canal should be undertaken by the Board. Accordingly, the joint scheme submitted by the States, was approved by Government of India in 1958 for executing in two stages. The Board commenced the construction works within its jurisdiction in 1958. This canal passes through a very rough terrain dotted with hillocks, which necessitated deep cuts, high sidewalls, tunnels etc. It cuts across the Uravakonda ridge through a deep cut and drops into Pennar Valley to join the Penna Ahobilam Balancing Reservoir (PABR). The first stage of the canal was commissioned by releasing water on 27th July, 1966. The second stage work was commenced in 1967 and got completed by June 1970. The total length is 196. 430 km. The Board's jurisdiction ends at 105.437 km, where it enters Andhra Pradesh territory. The RBHLC has a design capacity of 113.27 Cumecs (4000 cusecs) at the head. The details of Ayacut and Discharges of RBHLC distributaries up to Board Limit are given in

Annexure 3.14 and beyond Board limit are given in **Annexure 3.15**.

The details of Ayacut and Discharges of LBMC distributaries, LBHLC and Raya Basavanna canals are given in **Annexure 3.16 & Annexure 3.17**.

The KWDT has not made any change in the allocation of water to RBHLC for the States. The RBHLC was designed to deliver a maximum of 72.87 Cumecs (2,575 cusecs) at Board's limit for use in Andhra Pradesh. This included a provision of 1.42 Cumecs (50cusecs) as transmission losses from the dam upto Board's limit. In the meeting held on 22nd October 1974, observing that the carrying capacity of the canal had reduced to 90.56 Cumecs (3,200 cusecs), Board approved pro-rata reduction of the discharges to 29.720 Cumecs (1,050 cusecs) for Karnataka and 60.840 Cumecs (2,150 cusecs) for Andhra Pradesh inclusive of 5.660 Cumecs (200 cusecs) of transmission losses.

3.4 RIVER ASSISTANCE

There were fourteen anicuts built by the Raya Kings downstream of the Tungabhadra Dam up to the Rajolibanda Anicut, constructed in 1960, with independent channels collectively known as Vijayanagar Channels. Water requirements of these channels are met either by the regenerated water and river releases or the releases made through the Raya and Basavanna Channel and Power Canal by the Board. The ayacuts of the Rajolibanda Anicut depend on the regenerated water and the river releases from the Tungabhadra dam.

Similarly, the Kurnool-Cuddapah Canal too depends on the regenerated water and river releases made from the Tungabhadra dam. The KWDT has awarded specific allocations to Vijayanagar channels, Rajolibanda Anicut and K.C. Canal system, which are indicated in **Figure 3.1**.

3.5 LIFT IRRIGATION SCHEMES

There are a number of lift irrigation schemes located on the foreshore of the Reservoir, which directly draw water for irrigation. In order to account for such drawls during Rabi season, the Board in its 133rd meeting held on 11th January, 1989 resolved to debit 1.25 TMC water from 15.10.1988 to 31.12.1988 and 0.75TMC from 01.01.1989 to 15.02.1989 to Karnataka share provisionally towards drawals for lift irrigation schemes on the foreshore of the reservoir during the Rabi season. Pending final decision of the Board, debit as well as accounting of inflow of this 2.00 TMC in the manner aforesaid is continued. The Board in its 216th meeting held on 22.10.2020 directed to conduct the joint inspection of SE's of member States along with SE(IB),TB Board during November/ December 2020 on defunct, existing, ongoing and proposed lift schemes for irrigation, drinking and industrial water and submit a report to the Board. Accordingly, The Joint Inspection was carried out on right side of the fore shore area on 09.12.2020 and 10.12.2020 and on Left side of the foreshore area on 17.12.2020, 18.12.2020, 12.01.2021 and 02.02.2021. The actual utilization as per the joint inspection from the foreshore area is submitted along with comments of Member states. Finally, the Board in its 218th meeting held on 26.05.2022 decided that the utilization of the existing/working and new Lift irrigation/Drinking/Industrial schemes from foreshore of TB Reservoir is as below;

a) Existing/working LIS;

SL No	Purpose of Utilization	Quantity permitted earlier by TBB (TMC)	Actual Utilization to be accounted (TMC)
1	Irrigation	2.00	2.330
2	Drinking	0.33	0.843
3	Industrial	0.95	0.950
Total		3.28	4.123

b) New LIS / Drinking / Industrial Schemes;

SL No	Purpose of Utilization	Quantity permitted by TBB (TMC)	Actual Utilization to be accounted (TMC)
1	Irrigation	0.00	3.335
2	Drinking	2.34	2.340
3	Industrial	0.735	0.735
Total		3.075	6.410

Further, Board decided that the beneficiary need to mandatorily fix outlets of the above Existing & New Schemes with **Electro Magnetic Flow meter along with Telemetry.**

3.6 OTHER WATER DEMANDS

The Tungabhadra Project is a major source for meeting domestic and industrial water requirement of the region.

a) Drinking Water

Through the network of canal systems, the drinking water demand is also met along with the irrigation demands of the project. Board has permitted drawal of drinking water out of the share of water for the two States. Details of the drinking water schemes approved by board are given in **Annexure 3.4.**

b) Industrial usage

With the overall economic development of the area due to commissioning of the Tungabhadra Project, many industries have come up around the dam. The water demands of industries are met out of the share of the respective States. The details

of industries drawing water from various systems of the Project as approved by the Board is given in **Annexure 3.5.**

3.7 NEGATIVE INFLOWS

The daily inflows into the Tungabhadra reservoir are indirectly computed based on the change in the reservoir levels, evaporation losses and the outflows on account of canal drawls and spillway surplus during the preceding 24 hours using the storage equation:

$$I = O + E \pm D, \text{ where}$$

I = Inflows into the reservoir.

O = Outflows from the reservoir.

E = Evaporation losses.

(Measured as per evaporation from standard pan evaporimeter and applying a co-efficient of 0.8 to represent evaporation from the water spread area of the reservoir).

D = Difference in the storage capacity during the preceding 24 hrs. (Computed using the capacity- elevation table obtained through hydro-graphic surveys)

The inflows assessed using the above equation generally becomes negative during the months from December to April of a water year. Earlier the negative inflows were not accounted for and were considered as zero inflow. However, from 1976-77 onwards the negative inflows are accounted for.

Negative inflows recorded during the last 10 Years are given below.

Sl.No.	WaterYear	Negative inflows (inTMC)
1.	2013-2014	18.100
2.	2014-2015	17.053
3.	2015-2016	10.152
4.	2016-2017	1.889
5.	2017-2018	0.037
6.	2018-2019	0.000
7.	2019-2020	0.000
8.	2020-2021	0.000
9.	2021-2022	0.000
10.	2022-2023	0.000

Due to Implementation of Telemetry for all the canal heads from 2017-18, the negative inflows have gradually decreased and recorded as zero from 2018-19 onwards.

3.8 LOSSES IN THE CANAL SYSTEM

I. TRANSMISSION LOSSES

Board in its 88th meeting held on 20th August, 1976 has decided that the canal transmission losses are to be apportioned in the ratio of X/2 to Y where the drawals of X is of Karnataka State and drawals of Y is of Andhra Pradesh State. It was also decided that tentatively till more accurate data are collected, the Low-Level Canal transmission losses may be taken as 275 Cusecs. The transmission losses in respect of High Level Canal may be taken as 200 Cusecs. At present, the transmission's losses are considered as 200 Cusecs for both LLC & HLC.

II. SYSTEM LOSSES.

Whenever piping or breaches occur in the canals a certain quantum of water is allowed to flow through the escapes to deplete the water level at the piping/breach site quickly, to take up repairs. Certain amount of water also flows through the breaches whenever they occur. Board in its 130th meeting held on 29th January, 1988 being aware of the water losses due to certain unauthorized drawals by various means and noting that the law enforcing authorities are not able to effectively prevent / control these unauthorized drawals, permitted to make provision for these losses, termed as system losses. This is in addition to the usual provision of transmission losses. In respect of RBLLC, the Board permitted to account a maximum of 3.40 Cumecs (120 cusecs) as system losses from the water year 1987-88. Similarly, during the 165th meeting, the Board permitted to account for a maximum of 3.40 Cumecs (120 cusecs) as system losses in RBHLC also with effect from 1998-99. At present Transmission and system losses are considered as below.

Sl. No	Losses	RBHLC (in Cusecs)	RBLLC (in Cusecs)
1	Transmission Losses	200	200
2	System Losses	120	120

3.9 OPERATION OF RESERVOIR

A Water Review Committee at the level of Superintending Engineers of the participating States with Superintending Engineer, Irrigation Branch of the Board as Chairman has been constituted to assist the Board for assessing the quantum of utilization, distribution and regulation of water in various systems of the project. The Committee holds its first meeting generally in the month of June and recommends the probable utilization for the year and its distribution in various systems as per KWDT award. Based on the suggested probable inflow and pattern of drawals for each system furnished by the respective States the Working Table for operation of the reservoir on 10 daily basis is prepared and submitted for approval of the Board. The operation of the reservoir is carried out on the basis of approved working table. The working table was reviewed from time to time based on actual inflows received and pattern of drawals indicated by States for various uses.

3.10 WATER REGULATION DURING THE WATER YEAR 2022-23.

The first meeting of the Water Review Committee was held on 09th June 2022 and the utilization was suggested as 4842.036 Mm³ (171.000 TMC) for the likely inflow of 186.260 TMC. The second meeting of the Water Review Committee held on 16th November 2022 and the committee decided an abstraction of 188.000 TMC.

3.11 DATE OF OPENING OF CANALS FOR THE YEAR 2022-23

The dates of opening of canals as per working table and actual dates of opening are given below:

Canal	As per working table	Actual date of opening
RBLLC	16.07.2022	16.07.2022
RBHLC	12.07.2022	12.07.2022
LBMC	10.07.2022	10.07.2022

3.12 MEETING IRRIGATION DEMANDS 2022-23

KHARIF SEASON

The reservoir at the beginning of the Khariff season on 01.06.2022 was 1611.22 feet with a storage of 37.634 TMC. The inflows realized were 602.402 TMC as against 186.260 TMC originally considered in the Working Table. The water surplused over spillway was 404.269 TMC in addition to 35.374 TMC of water drawn for extra power generation by the power houses on both the sides without jeopardizing the Irrigation interests. Water of 99.948 TMC was drawn by Karnataka, Andhra Pradesh & Telangana States.

The reservoir evaporation and system losses recorded during Kharif season were 5.471 TMC and 2.542 TMC respectively. At the end of Kharif season on 30.11.2022 the water level in the Reservoir was (+) 1629.56 feet with a storage of 92.424 TMC.

RABI SEASON 2022-2023

The reservoir level at the beginning of Rabi season was (+) 1629.56 feet with a storage capacity of 92.424 TMC. The inflows realized during Rabi season is 7.780 TMC.

During Rabi season a total quantity of 90.475 TMC of water was drawn by Karnataka, Andhra Pradesh & Telangana States. The Reservoir evaporation and system losses recorded during Rabi season were 2.998 TMC and 2.011 TMC respectively. Ultimately, at the end of the Water Year on 31.05.2023, the Residual storage in the Reservoir was 4.719 TMC. The final annual abstraction came out to be 190.432 TMC.

RBHLC was closed on 25.02.2023, RBLLC on 11.04.2023 and LBMC on 12.04.2023. However, the drawals into Raya Basavanna canals were continued till the end of the year i.e., up to 31.05.2023.

3.13 WATER UTILIZATION DURING THE WATER YEAR 2022-23.

The quantity of water drawn by the States of Karnataka and Andhra Pradesh through different systems for the year 2022-23 as against allocations made in the KWDT award are given in **Annexure 3.6**. The 10- day water indent and actual releases made in RBHLC and RBLLC during 2022-23 are graphically represented in **Fig 3.2 and 3.3**. The utilization for Karnataka shown in the Annexure is inclusive of water drawn from the canals for other utilizations and water drawn from the reservoir directly for industrial use. The water utilization shown for Andhra

Pradesh is inclusive of water drawn for drinking water supply. The water account for the year 2022-23 is given in **Annexure 3.7**.

The year wise utilization for the last 45 years is given in **Annexure 3.8** and graphically represented in **Figure 3.4**.

The annual share of Karnataka and Andhra Pradesh on pro-rata entitlement of actual availability and actual drawals for the past 45 years are graphically represented in **Figure 3.5**.

3.14 PIPINGS AND BREACHES

Initially at the time of construction of RBLLC and the RBHLC locally available material was used in construction of canal embankments and compaction achieved through dry rolling. At many locations, the material used was calcareous, not ideal for the construction of embankments. In reaches where the canal embankments were as high as 8m, homogeneous section of calcareous filling got dissolved with the aging of these canals resulting in formation of large cavities inside the embankment. A number of pipings and breaches have taken place in such vulnerable reaches over the years.

Patrolling all along the canals was intensified for quick detection of vulnerable points, piping, siphons if any and to curtail illegal drawals. The breaches and pipings occurred during 2022-23 as given in **Annexure 3.9**.

3.15 FLOOD MANAGEMENT

The Tungabhadra reservoir has not been provided with flood storage capacity for

flood absorption. The FRL and MWL of the Reservoir are same and is at 497.740 Mt.(1633.00 ft.). However and acquired for submergence upto contour level 1635 feet. This extra 2 feet height is allowed for wavewash and consequential health hazards to the population bordering reservoir.

Therefore, the entire flood impinging the Reservoir has to be either stored to the extent possible or passed over the spillway. The spillway with 33 gates is designed to allow a maximum discharge of 18,406 cumecs (6,50,000 cusecs) at Full Reservoir Level of 497.740m (1633 ft). The operation of spillway gates is carried out in accordance with approved schedules duly ensuring the safety of the dam.

Central Water Commission provides daily information about the floods and rainfall occurrence at (i) Thirthahalli on the Tunga river, (ii) Harlahalli on the Tungabhadra River and (iii) Marol on the Varada river. Based on the Hydro-Meteorological data of these stations CWC issues inflow forecasts to the Reservoir with a lead time of 24 hours to enable operation of the spillway gates. The forecasts are communicated to the Board through Wireless and whatsapp.

The maximum level attained during the year 2022-23 was 497.740 M (1633.00 ft.), on 24.07.2022 and the reservoir level started receding from 27.10.2022 onwards. Statement showing Maximum and Minimum Reservoir levels and Spillway Discharges from 1963-64 to 2022-23 as given in **Annexure 3.9 A**

3.16 RESERVOIR SEDIMENTATION

Periodic assessment of the capacity of the Reservoir has been made since impounding of water in 1953. The gross storage capacity of the Reservoir was assessed in 1953 as 3,751.17 Mm³ (132.47 TMC) at FRL 497.740 m (1633 ft) and dead storage capacity as 32.83 Mm³ (1.160 TMC) at 472.440m (1550 ft). A siltation rate of 4.29 ha m/100 km² / year (0.427 TMC / year) was adopted in the design of the project.

In order to update the reservoir capacity at closer intervals, remote sensing technology was tried during 1995-96. The work was got done through Andhra Pradesh State Remote Sensing Application Center. But due to inconsistencies in the reservoir capacity obtained through the remote sensing technique vis-à-vis hydrographic surveys, the board did not approve the same for adoption. The Remote Sensing Directorate of Central Water Commission also evaluated the capacity during 1993-94 and 1999-2000. However, in view of the variation in capacities indicated by the study same has also not been considered by the Board.

Previously, hydrographic surveys are conducted in 1963, 1972, 1978, 1981, 1985, 1993, 2004 and 2008 conventional method was used and the storage capacity worked out based on the above surveys are 114.66 TMC, 121.080TMC, 117.695TMC, 115.680TMC, 111.832TMC, 111.500TMC, 104.34 TMC and 100.855 TMC respectively.

3.17 TOPOGRAPHIC SURVEY OF TB RESERVOIR.

To overcome the inconsistency in the Hydrographic survey data, physical survey i.e., Topographic survey and Bathymetric survey of the reservoir has been taken up to assess the present capacity and status of siltation, which will be considered more reliable and authentic. The survey work was entrusted to M/ s Aarvee Associates, Hyderabad during June 2016 and draft report has been submitted by the consultancy M/s Aarvee Associates, Hyderabad. The outcome of the survey is an increase in the storage capacity from 100.855 (2008 Survey) to 105.788 TMC. The same have been examined and compared with the discharges recorded through telemetry and submitted in the 214th Board meeting held on 17.08.2019 for approval of Board. Finally, after thorough & detailed deliberations, the Board in its 218th meeting held on 26.05.2022 decided to accept the topographical survey conducted through M/s AARVEE Associates, Hyderabad during 2016-17 for a Reservoir capacity of 105.788 TMC and same was adopted from 22.06.2022.

The report on the survey of TB Reservoir estimated that the storage now is 2995.49 Mm³ (105.788 TMC) against 3751.17 Mm³ (132.470 TMC). The average annual rate of decrease in the reservoir capacity is 0.423 TMC in 63 years.

The capacity of the Reservoir as per various surveys done from 1953 to 2016

with annual rate of decrease are given in **Annexure 3.10** and graphically represented in **Figure 3.6**. The capacity elevation table obtained from 2016 Survey of the Reservoir approved by the Board is shown in **Annexure 3.11**.

3.18 MODERNIZATION OF RBHLC & RBLLC (INCLUDING PC)

RBHLC MODERNIZATION

As per KWDT award, the water allocation for TBP-RBHLC is 50.00 TMC, out of which the share of Karnataka State is 17.50 TMC and Andhra Pradesh State is 32.50 TMC. Similarly, the water allocation for TBP-RBLLC is 43.00 TMC, out of which the share of Karnataka State is 19.00 TMC and Andhra Pradesh State is 24.00 TMC.

The primary responsibility of TB Board is to supply water to the Member States as per the KWDT award. But the Member States are not receiving their quota as per KWDT award due to the decreased carrying capacity of TBP-RBHLC (more than 50 years old) and TBP-RBLLC (unlined) (more than 60 years old). The lining portion of TBP- RBHLC was damaged in most of the reaches and structures were in dilapidated condition. If any major damage occurs to the canal system, the canals water management fails to deliver the indented water to the Member States. The Left Bank Canal System and Distributary system of Right bank canals in the jurisdiction of Govt. of

Karnataka were already modernized.

To deliver the rightful share of water of GoAP as per KWDT Award, it was felt very essential to modernize both the canal systems under the jurisdiction of TB Board with cement concrete lining for delivering the indented water at the border of Andhra Pradesh.

TB Board in its 177th meeting held on 18.09.2003 agreed to modernize both RBLLC & RBHLC, but the same could not be taken up due to financial constraints. Again, TB Board in its 194th meeting held on 16.11.2010 agreed to modernize both TBP-RBHLC and TBP-RBLLC (unlined). During the meeting held in November 2014 between the Govts. of Andhra Pradesh and Karnataka, it was mutually agreed to modernize the TBP-Canal System.

The DPRs for Modernization of TBP-RBHLC and TBP-RBLLC under the jurisdiction of TB Board were vetted by Member States (GoK & GoAP) and CWC (Central Water Commission). Meanwhile the HECRAS Model studies in case of RBHLC were conducted by Shri. Rama Prasad, Retired Professor of Civil Engineering, IISC, Bangalore. The recommendations are as under:

“In deep cut reaches the bed width of the canal be increased to 11 mtrs in the reach from Km 14.925 to Km 22.425, and to 10

mtrs in the reach from Km 27.450 to Km 38.950 without lining in rock cut reaches. This will enable 4000 Cusecs to be released into the canal with water levels within permissible limits. At some places of deep cut sections, the masonry lining has fallen off. This can be removed and no fresh lining is necessary. Concrete lining may be repaired where it is damaged”.

As per the recommendation of Shri. Rama Prasad, Retired Professor of Civil Engineering, IISC, Bangalore all the estimates for special repairs of RBHLC were sanctioned. The Chief Engineer, Irrigation Branch, TB Board, TB Dam also accorded technical sanction for the works of Special repairs (modernization works) from Km 0.00 to Km 14.33 reach of RBHLC vide letter dated 16.05.2016 and the tenders for the above works were called on 13.06.2016 for fixing the agencies. The modernization works for the above reach were taken up in four packages during 2016-17 and completed during the month of June 2017.

Further the modernization works of RBHLC were taken up from Km 15.000 to Km 105.000 and improvements and reconstruction of structures from Km 15.000 to Km 105.435 in a phased manner from 2017-18 to 2019 20 in 13 Packages and all works are completed by March 2020. Apart from this Bed lining

about 10 km length where ever necessary in deep cut reaches was taken up and completed in 2022.

The Modernization works awarded during 2022-23 in the left over reaches from Km 53 to 95 are in progress and likely to be completed in 2023-24.

After completion of modernization of RBHLC from Km 0.00 to Km 105.00 (except for widening of the few reaches), the velocity of water flow in the canal has improved a lot and indented discharges of 4000 cusecs are being carried with ease at the canal head and able to deliver a discharge of around 2200 cusecs (against earlier discharge of 1500 cusecs) at Andhra Pradesh border i.e., at Km 105.00 of RBHLC.

POWER CANAL MODERNIZATION

The Modernization works from Km 0.000 to Km 20. 300 were taken up in two packages (Package Nos. 9 & 10) during the fag end of 2017-18 and completed successfully by July 2019.

RBLLC MODERNIZATION

As per the decision of the Board in its 213th meeting held at Hyderabad on 27.12.2018 and as per the recommendations of Shri Rama Prasad, Retired Professor of Civil Engineering, IISC, Bangalore, the modernization works of RBLLC from Km 0.000 to Km 72.000 were taken up in 7 Packages during May, 2019 and

completed in 2021-2022. Modernization works from Km 72.00 to KM 115.00 were taken up in 3 Packages and completed in 2022-23. Modernization works from Km 115.00 to KM 205.00 were taken up in 10 Packages and completed in 2022-23 (except package 12,13,&14) and these three packages will be completed during 2023-24. Further modernization works from Km 205.450 to Km 250.580 tenders called, Agencies were finalized, but due to meagre funds received from GoAP during the financial year 2022-23 and meagre allocations were made in financial year 2023-24 and due to non-receipt of additional funds from Govt. of Andhra Pradesh, the agreement is yet to be conclude for the package works from Km.205.450 to Km.250.580.

3.19 New Initiative in Water management – Live Flow Measurement in Canals and Distributaries using Telemetry and ADCP.

During 210th Board meeting held on 28.01.2017 it was decided to take up Telemetric gauging of all canals of TB Dam. As per the decision, 45 locations were selected in both left & right bank canals.

As per the Board decision online tenders were called and the work was entrusted to M/s Mechatronics systems Pvt. Ltd. The telemetry started initially at head reaches

i.e., TLBC, RBHLC, Power canal & AP Border of RBHLC and started recording from 22.09.2017 onwards and continued for water accounting since 2017-18 water year. Due to implementation of Telemetry/ Live flow data, the negative inflows were avoided since 2018-19 and overall average savings was around 10.00 TMC (as per statement of Negative inflows) which can be used in the crucial time to save the crops & drinking water needs for all the canals.

The TB Board entrusted the work of calibration and checking the correctness of telemetry stations to CWPRS, Pune & they visited each Telemetry station and calibrated the Telemetry equipment's with an error of $\pm 2\%$ which is within the acceptable limits.

The TB Board has also demonstrated and compared the telemetry/live flow data with Board ADCP in front of ICC members, MLAs, Farmers & public. On comparing/ cross checking they expressed their satisfaction with discharges obtained by telemetry/Live flow data.

Stakeholders such as farmers and officials can get the details of discharges of canal

system by browsing the TB Board official website: **www.tbboard.gov.in** or **www.tbbliveflow.com** or by installing the **TBPLIVE app** from the Google play store in android mobiles. The details of telemetry locations are given in **Annexure 3.18**.

3.20 FINANCIAL PERFORMANCE

The budget allocation for the Irrigation Wing for the past 8 years i.e., from 2015-16 till 2022-23 under the Major Head

Year	Head of account	Budget allotted	Expenditure
2015-2016	MH 4700	2000.00	1324.46
	MH 2700	6380.00	5548.25
2016-2017	MH 4700	5712.00	3787.26
	MH 2700	6810.00	6358.81
2017-2018	MH 4700	31439.00	23203.56
	MH 2700	6810.00	6452.37
2018-2019	MH 4700	26253.53	26253.53
	MH 2700	8408.00	8408.00
2019-2020	MH 4700	49015.00	47950.50
	MH 2700	8736.53	8124.81
2020-2021	MH 4700	22590.00	22318.61
	MH 2700	8132.22	7730.37
2021-2022	MH 4700	26669.00	24930.00
	MH 2700	8270.00	7151.00
2022-2023	MH 4700	11500.00	11500.00
	MH 2700	8026.00	6965.00

Figure 3.1





Figure 3.1: Water Allocation in various Irrigation Systems of TB reservoir as per KWDT

10 DAY WATER INDENT AND ACTUAL RELEASES MADE IN RBHLC DURING 2022-23 (KARNATAKA)



10 DAY WATER INDENT AND ACTUAL RELEASES MADE IN RBHLC DURING 2022 -23 (ANDHRA PRADESH)




Figure 3.2

Figure 3.3





Figure 3.4




Figure 3.5

Fig. 3.5

SHARE OF STATES AND ACTUAL DRAWALS





Figure 3.6



MODERNIZATION OF RBLLC











INSPECTION OF WORKS ON RBLLC BY CHAIRMAN, TBB



MODERNIZATION OF RBHLC









SAND BLASTING AND PAINTING WORK TO THE SPILLWAY GATE NO. 12 TO 22





ERECTION OF WAVE DEFLECTOR OVER THE SPILLWAY GATE





INSPECTION OF SPILLWAY GATE WORK BY SECRETARY, TBB



DAM SAFETY WORKS OF TUNGABHADRA DAM (RIGHT SIDE)





INSPECTION OF WORKS ON DAM BY CHAIRMAN , TBB



CECRI TEAM, KARAIKUDI, TAMILNADU INSPECTION OF SPILLWAY GATES



HAGARI AQUEDUCT

PIER NO.15 WASHED OUT (NOT TRACEABLE) COMPLETELY DUE TO HEAVY RAINS IN THE UPPER CATCHMENT AREA



TEMPORARY RESTORATION TO HAGARI AQUEDUCT



CONSULTANT SRI R K JAIGOPAL, MD, STRUCT GEOTECH RESEARCH LABORATORIES, BENGALURU VISITED TO HAGARI AQUEDUCT



INSPECTION OF HAGARI AQUEDUCT WORK BY CHAIRMAN, TBB





INSPECTION OF HAGARI AQUEDUCT WORK BY CHAIRMAN TBB AND CHIEF ENGINEER, IB, TBB



PERMANENT RESTORATION WORK TO HAGARI AQUEDUCT





INSPECTION OF HAGARI AQUEDUCT WORKS BY CHARIMAN, TBB







INSPECTION OF HAGARI AQUEDUCT WORK BY MEMBER, TBB, AP



4.1 INTRODUCTION

The Tungabhadra Hydro Electric Scheme (TBHES) of Tungabhadra Board comprises two power houses, one on the right bank at the foot of the Dam and another at Hampi, located 21 km from the Dam. Though the Scheme was sanctioned by the then Government of Madras in the year 1950, work on the Dam Power House was started in 1951 and that of Hampi Power House in 1956. The power generated by the two power houses on the right side is shared between Karnataka and Andhra Pradesh in the ratio of 20:80. Another power house located at the left bank of the Dam is under the control of Karnataka State. The hydro power generated on the left side is entirely utilized by Karnataka. The salient features of the power houses of the Tungabhadra project is at **Annexure 1.2**.

4.2 RIGHT BANK DAM POWER HOUSE

The Right Bank Power House is located at the foot of the Dam. The gross head available at the Dam powerhouse for power generation varies from 13 to 26.8m. Four steel penstocks, each of 3.3m in diameter carry water from reservoir to generator turbines. In the first stage, two units each of 9 MW were commissioned on 26th January, 1957 and 23rd May, 1957 respectively. The First unit Generators and indoor switch gears were supplied and erected by M/s Brown Bowery, Switzerland through Valkart &

Bros, the Indian agents and Turbines with accessories by M/s Escherways Ltd., Switzerland through Kumara Dholi Engineering Works, Calcutta. The second Unit Generators, indoor switch gears and turbines accessories were supplied and erected by M/s. Hitachi Company Ltd, Tokyo, Japan. The two units each of 9 MW of second stage were commissioned on 26th February, 1964 and 17th June, 1964 respectively.

The total installed capacity of the Dam Power House is 36 MW with 4 units of 9 MW each.

As the main objective of the TB Project being irrigation, the electricity generation is dependent on the water releases made for irrigation in the RBLLC, RBHLC and river assistance to the RDS and K.C.Canal. Water releases vary from time to time as per the irrigation demands indented by the States. During rainy season, especially when the reservoir is nearing full level or is overflowing, generation at full capacity of 36 MW is done at the Dam power house, drawing water at the rate of 160.27 cumecs (5660 cusecs) with maximum differential head of 26.8 m.

4.3 HAMPI POWER HOUSE

The tailrace water of the Dam Power House is fed through the Power Canal to the fore bay located at Hampi, which has a storage capacity of 0.74 M cum with

normal level of 463.1 m (1519 ft). Water from forebay is carried to power house through two pipe lines, each of 5.48m diameter and 868.3m in length. At the end of each penstock there is a steel differential surge tank of 18.3m diameter with a height of 18.3m. Two penstock pipes each of 3.66m diameter with a maximum discharging capacity of 31.15 cumecs (1,100 cusecs) takes off through the surge tank diverting water to four turbines in the power house. Each penstock is provided with a 3.66 m butterfly valve & an air valve at surge tank end and 3.05 m butterfly valve & venturi meter at power house end.

The first unit of 9 MW was commissioned on 10th February 1958 and the second unit of 9 MW on 26th March 1958. The two units were supplied and erected by M/s Brown Bowery Company, Switzerland.

The remaining two units, each of 9 MW, were commissioned in April and July 1964 and were supplied and erected by M/s Hitachi Ltd., Tokyo, Japan. The total installed capacity of Hampi Power House is 36 MW.

As the discharge carrying capacity of the Power canal is limited to 70.79 cumecs (2,500 cusecs), the maximum generation at Hampi Power House is limited to 20 MW against an installed capacity of 36 MW. The generation at Hampi Power House is dependent on water discharge through Power Canal. The water discharged from Hampi Power House enters in to Gundlakere Lake and from there it is led into Right Bank Low Level Canal and Gundlakere escape.

During the months of May and June when the Right Bank Low Level Canal is closed or when the minimum drawdown level of 482.35m (1,582 ft) is reached, the power houses are being shut down.

4.4 BELLARY SUB-STATION:

The Board has installed a 66 KV Sub-station at Bellary to evacuate part of Power Generated from the Dam and the Hampi Power Houses to Andhra Pradesh and Karnataka. The substation is not in operation since 2007. But circuit breakers, CT's, PT's, Feeder panels and structures exist in the substation which are in obsolete condition which is under the control of Executive Engineer, O & M Division, Dam Power House.

The quarters (27 No's) are being maintained by the Executive Engineer, LLC Division, Bellary. The electricity consumption charges are being collected by the TBHES, TB Board.

4.5 HYDRO ELECTRIC WING OF BOARD

A Chief Engineer belonging to APGENCO heads the Hydro-Electric (HE) Wing of Board on part time basis. The Chief Engineer (Electricity, Projects), APGENCO, Vijayawada is the present part-time Chief Engineer of the HE Wing. A Superintending Engineer belonging to KPTCL heads the TBHES Circle located at TB Dam. There are two Divisions, one at TB Dam and the other at Hampi. These Divisions are headed by Executive Engineers of APGENCO cadre. There are 14 Deputy Executive Engineers (3 GoK + 11 GoAP). Other staff members are drawn from the APGENCO and KPTCL, in the proportion

of 80:20. The Organization Chart of Hydro Electric Wing is at **Annexure 4.1**.

4.6 FUNCTIONS

The HE Wing is responsible for generation of hydroelectricity, transmission of the hydro-power generated to Andhra Pradesh and Karnataka in the ratio of 80:20, and also to take up special repairs & maintenance of the power houses, equipment and transmission & distribution of electric power in the Board's colony at TB Dam and Hampi Camp colony.

4.7 HYDRO-POWER GENERATION

Hydro-power generation has been going on at two power houses since commissioning of the plants, by utilizing water released for irrigation purposes. The power generated at both the power houses of Board is shared in the ratio of 80:20 between GoAP and GoK. The extra power used if any, by GoK/GoAP is paid by the KPTCL/APTRANSCO as the case may be. The plant-wise generation achieved, auxiliary consumption, shares and utilizations by Andhra Pradesh and Karnataka for the last 15 years i.e., from 2008-09 to 2022-23 are furnished in **Annexure 4.2**. The details of power generated and generation cost per unit for the period from 2004-05 onwards are given in **Annexure 4.3**, from which it could be seen that, the cost of generation per Unit during the last five years is as indicated below;

Year	Power Generation in Mu.	Cost of Power Generation (Paise)
2018-19	134.670	181.05
2019-20	176.973	113.01
2020-21	173.118	126.44
2021-22	205.203	125.16
2022-23	193.296	177.82

The power generated and costs per unit of generation for the period from 1994-95 to 2022-23 are depicted in **figure 4.1**.

4.8 FINANCIAL PERFORMANCE

The budget allocation, expenditure & revenue from 2018-19 to 2022-23 pertains to HEW is as follows;

(Rupees in Lakhs)

Year	Voted grants	Expenditure	Revenue Generated @Rs.2/unit
2018-19	2730.38	2438.13	2693.40
2019-20	2000.94	2000.00	3539.60
2020-21	2188.91	2188.91	3462.40
2021-22	2568.29	2568.29	4104.10
2022-23	3338.66	3437.21	3865.90

The expenditure towards establishment and other sharable expenses relating to previous years for which advises from the Accountant General, Andhra Pradesh, Vijayawada were received during 2021-22. The same is included in the expenditure of the year 2022-23.

The expenditure on account of salaries of O&M staff, Civil Maintenance works of Colonies and maintenance works in both the power houses is met from the budget allocation under the head of account 272 maintenance & 070 work charged establishment. The allocation provided under this head of account has been utilized for salary component of O&M staff and only very essential maintenance works were taken up during the year 2022-23.

4.9 ROYALTY TO IRRIGATION WING OF TB BOARD

The Board in its 202nd meeting has revised the rates of royalty charges payable by

HEW to Irrigation wing (IW) of TB Board from then existing rate of Rs. 212.00 per KW per year to Rs. 429.00 per KW per year with effect from the financial year 2012-13 and directed that the royalty charges may be reviewed every five years as per previous decision of the Board.

Accordingly, the rates of Royalty charges payable by TBHES to irrigation department was reviewed during the 215th meeting of the Tungabhadra Board held on 15th February, 2020 and the rate was fixed at Rs. 680.65 per KW year with effect from 01.04.2020 based on All India Consumer Price Index. The details of which are as given below;

Year	Revise rates/KW year Paisa
1996-97	134.89
2001-02	212.00
2012-13	429.00
2019-20	680.65

The Total Royalty charges for the year 2022-23 is Rs. 1,50,19,100/- According to the TB Board decision taken in its 217th meeting held on 29.09.2021, The Fisheries farm and Ice factory of TB Board has been leased on PPA model to the third party agency. The power to the fish form and ice factory is being supplied by HEW and electrical charges are being collected as per industrial category LT-5 (a) rates of GESCOM, Hospet.

4.10 RATE OF ELECTRICAL CONSUMPTION CHARGES APPLICABLE TO THE TB BOARD EMPLOYEES:

The TB Board in its 216th meeting held on 22-10-2020, through Video conference

accorded approval for revision of Electricity Consumption Charges applicable to all employees of the Board commencing from 01-01-2021 are as follows.

	CATEGORY	REVISED RATES
1	APGENCO Employees	0.2% OF BASIC PAY
2	KEB Employees 0 - 200 Units/Month 200 - 280 Units/Month 280-400 Units/Month Above 400 Units/ Month	Free 10 Paisa 50 Paisa AEH (LT2a) tariff of KPTCL+ Rs.20/- Minimum charges
3	TB Board Employees 01-30 units 31-100 units 101-200 units 200-300 units Above 300 units Minimum charges	Rs. 1.90 Rs. 2.60 Rs. 3.40 Rs 3.90 Rs 7.80 Rs 60.00
4	Pensioners and Non-Board Employees & other Establishment	As per KPTCL Rates

Further, Board agreed to extend TBHES power supply to BSNL exchange office situated in TB Dam and to the Tirumala Iyengar Hall, Stalls, Amusement Park, Dashing Cars at Boating area which are leased to the private agencies by the TB Board as per KPTCL rates under the Category-4 in the above table.

4.11 MAINTENANCE WORKS:

Important repairs and maintenance works attended during the year are;

TB Dam Power House:

- ❖ Replacement of Re-babbitted Turbine Guide Bearing, Carbon segment seals, Labyrinth seal and fabrication of shaft seal cooling water pipe line for Unit-I and II at Dam Power House.

- ❖ Providing underwater services for arresting water leakages from PSG and DT Gates pertaining to Unit-1, II, IV and house set cut-off gate at Dam Power House.
 - ❖ Replacement of Rebabitted Turbine Guide Bearing and Bakelite segment seal for Unit-IV at Dam Power House.
 - ❖ Re-babbiting and machining of damaged/failed Turbine Guide Bearing of Stage-I&II units at Dam Power House.
 - ❖ Repair and Re- winding of 66/11 KV, 2 MVA transformer 5 pertaining to Outdoor section, Operation sub division at Dam Power House.
 - ❖ Design, Fabrication, supply, erection testing and commissioning of House set Cutoff gate at Dam Power House.
 - ❖ Re-babbiting of thrust pads pertaining to mechanical section, mechanical sub division of TB Dam Power House.
 - ❖ Capital Overhaul works on Generator, Turbine, Auxiliary equipment and butterfly valves of units-3 at Dam Power House, TB Dam.
 - ❖ Overhauling and Reconditioning of 22 HP Dewatering Pump pertaining to Mechanical section, TB Dam Power House.
 - ❖ Outsourcing of maintenance works in Electrical & Mechanical sub divisions of TB Dam Power House.
 - ❖ Arresting of TB Dam Power House roof leakages.
 - ❖ Attended bus shut down maintenance works at station outdoor yard.
 - ❖ Provided RCC to the 06 No's of E Type and 04 No's of F Type Quarters in TBHES Colony.
 - ❖ Renovation of control room windows, Chambers of DyEE and AEE,s of TB Dam Power House.
 - ❖ Painting of TB Dam Power House.
 - ❖ Construction Security Room at the entrance of TB Dam Power House.
- Hampi Power House**
- ❖ Forebay maintenance works at hampi power house.
 - ❖ Replacement of Turbine Guide Bearing, Carbon segment seals, and arresting of leakage water from the TGB Pit of Unit-II at Hampi Power House.
 - ❖ Removing. Damaged and failed stator coils, Replacement of new and re- insulated stator coils for 10.6 MVA, 11KV Alternator-1 and 2 at Hampi Power House.
 - ❖ Outsourcing of maintenance works in Electrical & Mechanical sub divisions of Hampi Power House.
 - ❖ Cleaning and painting of generator stator air coolers.
 - ❖ Cleaning of generator transformer coolers.
 - ❖ Attended bus shut down works in station outdoor yard.
 - ❖ Attended minor repair works in surge tank.
 - ❖ Cleaning and painting of intake gate trash rack.

- ❖ Attended roof leakage works by providing tar felt to the quarters in Hampi Power Colony.
- ❖ Provided RCC to the 04 Nos of E Type and 04 Nos of F Type Quarters in Hampi Power Colony.

4.12 NEW MINI HYDEL POWER STATION

A. M/s. NCL Energy Ltd

Water is released from reservoir to the Right Bank High Level Canal through 10 high level sluices 6' x 12' size. Board decided to utilize the head and discharges available at 3 of these 10 sluices for power generation. Accordingly, a mini-Hydel power plant was contemplated to be setup in private sector under Built, Own, Operate and Transfer (BOOT) basis. The Board identified an Independent Power Producer (IPP) M/s. NCL Energy Ltd., Hyderabad and permitted them to set up the plant. Tungabhadra Board has provided required land in RBHLC stilling basin to IPP on lease for a period of 30 years. The IPP will own the mini power house for 30 years from the date of commissioning and thereafter will transfer the ownership to Tungabhadra Board.

The power plant comprises 3 units of 2.75 MW capacity each. From the consideration of head and power draft horizontal Full Kaplan Turbine and synchronous generator was selected. The annual generation available with the installed capacity of 8.25 MW is estimated to be 27.93 million units. The total project capital cost was Rs.22 crores.

As the power plant is located adjacent to the masonry dam and to keep the vibration level within the safe limit, the excavation works were carried out using controlled blasting techniques in

technical collaboration with National Institute of Rock Mechanics, Kolar Gold Fields, Karnataka. The guidance of Central Water Commission was also obtained in this regard.

The Civil and Electrical works of the mini-Power Plant were completed in a record time of 8 months and the Units were commissioned and synchronized with the grid on the following dates.

- ❖ Unit-I Commissioned on 28.09.2004
- ❖ Unit-II Commissioned on 09.10.2004
- ❖ Unit-III Commissioned on 25.10.2004

The power generated from this mini power house for the last five years are as indicated below.

Year	Power Generated (In million units)
2018-19	20.3694
2019-20	27.7173
2020-21	26.0690
2021-22	33.8200
2022-23	30.6990

Generated power purchased by transmission corporations are as indicated below:

Transmission Corporations	Rate of purchase of power
KPTCL	Rs.1.98 per unit for the first 20 years and Rs. 1.89 per unit for the balance 10 years, including 10% royalty charges payable to Board.
APTRANSCO	Rs.1.782 per unit for the first 20 years and Rs. 1.701 per unit for the balance 10 years, excluding royalty charges.

**B. M/s. Khandaleru
Power Company Ltd.**

Water is released from reservoir to the Raya basavanna canal through a single sluice. Board decided to utilize the head and the discharge available at single vent of sluice for power generation. Accordingly, a mini-Hydel power plant was contemplated to be set up in Private sector under Built, Own, Operate and Transfer (BOOT) basis. Independent Power Producer (IPP) M/s Khandaleru Power Company limited; Hyderabad was permitted to set up the plant. Tungabhadra Board has provided required land in Rayabasavanna Stilling Basin to IPP on lease for a period of 30 Years.

The power plant comprises a single unit of 1.4 MW capacity, from consideration of Head and Power, Horizontal full Kaplan Turbine and Synchronous Generator were selected. The Annual Generation available with the installed capacity of 1.4MW is 7.19 MU. The total project capital cost was Rs.11.50 crores.

The project construction was started in September-2012 and commissioned in record time of 11 months i.e., 31.08.2013. The power generated from this mini powerhouse for the last five years are as indicated below;

Year	Power Generated (in million units)
2018-19	7.0003
2019-20	6.3642
2020-21	6.3249
2021-22	7.6756
2022-23	9.0853

Generated Power is purchased by GESCOM at the Rate of RS 2.80/- per unit.

**4 .13 POWER GENERATION UNITS
ON LEFT SIDE OF THE TB DAM**

Similar to power generation units on the Right side of the dam, the following four units are working on Left side of the TB Dam, which are being maintained by KPTCL (GoK). The power generated from these units for the last five years as indicated below:

Year	Generation (MU)
2018-19	90.82
2019-20	97.04
2020-21	103.25
2021-22	132.58
2022-23	115.55

**CHIEF ENGINEER, TBHES INSPECTION TO
TB DAM & HAMPI POWER HOUSES**








UNIT 4 CAPITAL OVERHAULING WORKS AT DAM POWER HOUSE



Figure 4.1

**TUNGABHADRA HYDRO-ELECTRIC SCHEME
TOTAL POWER GENERATION AND COST PER UNIT (kwh)**



5.1 INTRODUCTION

Construction of the Tungabhadra dam has created a vast reservoir spread over an area of 378 sq km providing tremendous scope for development of fisheries for social upliftment of the people of the Region. The Board thus set up a fish farm for producing quality fish seeds for raising fishery wealth in the Tungabhadra reservoir and for sale to Government and private agencies in Karnataka and Andhra Pradesh. In addition, for the convenience of the fishermen of the area to facilitate preservation of fish catch, Board is also running an Ice Plant.

5.2 ORGANIZATION

Fisheries Wing (FW) consists of following four units.

- Fish Farm Unit (FFU)
- Reservoir Unit (RU)
- Ice Plant
- Aquarium

Organization Chart of Fisheries Wing is at **Annexure 5.1.**

The Fisheries Unit works under the control of the Secretary, Tungabhadra Board. The Fisheries Development Officer (FDO) posted by Fisheries Department of GoK, looks after the day-to-day activities of the Wing. The staff of the Wing is drawn from GoAP and GoK in the ratio of 5:13 respectively.

5.3 FISH FARM

The Fish Farm was set up in the year 1959 in an area of 8.10 ha. This farm is having 20 earthen ponds of different sizes ranging from 15mx33m to 32mx80m and 87 cement ponds of size ranging from 3mx2m to 24mx12m. A glass jar hatchery

with a capacity for hatching 50 lakhs eggs per cycle (5 days) was commissioned in the year 1982 and is non-functional since 2011 due old equipments and machineries. Two Chinese / circular hatcheries were setup in the year 2011 with a capacity of 25 Lakhs eggs per cycle apart from two old Chinese / circular hatcheries each with a capacity of 15 lakhs of eggs per cycle which were constructed during the year 1992. The details of fish farm ponds are given below;

DETAILS OF FISH FARM PONDS

Brood Stock ponds	2.60 ha
Rearing & Nursery ponds	1.60 ha
Water sedimentation ponds	0.20 ha
Breeding, hatching & conditioning ponds	0.20 ha
Total Water spread area of Farm	4.60 ha

The Fish Farm Unit (FFU) is producing spawn of major carp and common carp utilizing the parent stock (brood stock) raised in fish farm by induced breeding technique. Brood fish are injected with synthetic hormone which induces the fish to release eggs in stagnant water. The spawn so produced, apart from rearing further to fry stage and then to fingerling stage for supply are disposed off at spawn stage also. The FFU is a leading producer of Catla fish seed which is in great demand in the Region. It is ideal in respect of its location, design, maintenance of breeders, hatching facilities etc. The fishermen & aqua culturists of this area have great faith in the quality of seeds provided by FFU.

Many under graduate and post-graduate students of Zoology and Fisheries from various colleges pay visit to FFU every year as part of their practical training in fish culture and breeding aspects.

5.4 ICE PLANT

Fish is a highly perishable commodity. Its preservation soon after its catch from the water is very essential. Icing the fresh fish is the simplest preservation method. In order to meet the ice demand of the fishermen, 5 ton capacity Ice Plant and 10 ton capacity cold storage plant were established in the year 1966. Again, in order to meet the ice demand of the fisherman 10 ton capacity of ice plant was established in the year 1986 as the earlier 5 ton capacity ice plant was non-functional due to long run which needs replacement. As there was no demand for the cold storage space, 10 ton cold storage plant machineries along with abandoned 5 ton ice plant machineries have been disposed off through public auction in the year 1995. The ice produced from present working 10 ton capacity plant is being marketed throughout the year, with its peak season falling between February and May.

5.5 THE AQUARIUM PARNAJA

As the Tungabhadra Project attracts large number of visitors annually, in order to inculcate the essence of aquatic lives in the visitors, an aquarium by name "Parnaja" was constructed in the Japanese Park at a cost of Rs.45.00 lakh and opened to the visitors during August, 1999. The aquarium with about 60 varieties of cultivable, indigenous and ornamental fish provides a feast to the eyes and relaxation to the mind. It also provides latest information on the aquatic lives to the inquisitive minds. The

aquarium is constructed as a thematic building and equipped with modern aeration and filtration system to maintain good hygiene.

5.6 FINANCIAL CONSTRAINTS OF FISHERIES WING

From the past few years, fisheries wing is not getting budgetary support from the Govt. of Andhra Pradesh. Due to this, fisheries wing is not able to carry out the developmental activities and maintenance of the fish farm, ice plant and aquarium. In the 217th board meeting it was agreed to outsource Fish Farm & Ice Factory including Fishery rights in the TB Reservoir on PPP basis. Accordingly tender was called for with an upset value of Rs.2,00,00,000/- per year and work has been awarded to highest bidder with an agreement value of Rs. 2,42,05,000/- per year for Lease – Develop – Operate - Transfer basis of Fish farm, Ice plant & Fisheries rights of Tungabhadra Reservoir with effect from 01.06.2022.

5.7 FINANCIAL/PHYSICAL PERFORMANCE

The physical performance of the Fish farm unit / Reservoir Unit and ice plant units of Fisheries wing from 2007-08 to 2022-23 is at **Annexure 5.2**. And the financial performance during last five years is as given below;

(Rupees in lakhs)

Year	Budget Allocation	Expenditure	Receipts
2018-19	239.08	160.54	168.98
2019-20	140.87	149.64	152.31
2020-21	125.75	135.93	162.55
2021-22	83.30	174.86	175.01
2022-23	78.18	78.55	254.12

6.1 INTRODUCTION

Health and Medical Unit of the Board is taking medical care of Board's employees and is responsible for general sanitation of Board's colonies at TB Dam, Hampi and Bellary.

Dr. Kanakappa.Y, MBBS, MS General Surgeon holds the full charge of Health and Medical unit of TB Board Hospital at TB Dam & Hampi camp Dispensary since 12.07.2019.

6.2 ORGANIZATION

Health Officer Class-I (Jr.) is In-charge of the Unit. He is in the rank of Deputy Surgeon in Government of Karnataka. For assisting him in health activities there are two Health Inspectors one each from Andhra Pradesh and Karnataka for the effective discharge of the Public Health Activities i.e., one at TB Dam and another at Hampi Camp. There are two Civil Assistant Surgeons from Karnataka one each at the Project Hospital, TB Dam and at Dispensary, Hampi Camp. Further, there is one Lady Medical Officer in the rank of Civil Assistant Surgeon (Karnataka) in the Project Hospital, TB Dam. There are other para medical staff and ministerial staff in the Hospital and Dispensary. There are Health Mazdoors born on Work charged and contingent establishment and they are treated as Board employees. The Organization chart of the Health and Medical Unit is at **Annexure 6.1.**

6.3 FUNCTIONS

The important functions of the Unit are:

- General sanitation of colonies.
- Immunization programme for child health.
- Bacteriological and Chemical Examination of drinking water.
- Prevention of epidemics.
- Anti-Larval measures.
- Control of Dengue & Chikungunya
- National Malaria Eradication Programme.
- Medical facilities for outpatients and in patients.
- Minor operations.
- Family welfare measures and small family norms.
- X-Ray section
- Laboratory Section

6.4 ACTIVITIES OF PUBLIC HEALTH UNIT DURING THE YEAR 2022-23

- **Vital Statistics:** The District statistical officer Births & Deaths registration office, Bellary had advised not to register Births & Deaths from 26.03.2017 onwards and hence registering Births & Deaths has been stopped there after.
- **Cholera:** The Tungabhadra Board area is free from cholera and other epidemic diseases.
- **National Malaria Eradication Programme:** The Anti-Malaria drugs supplied by the District Malaria Officer, Bellary and Dist. Health & Family Welfare Officer,

Bellary were given to all the fever cases duly collected blood smear (samples) for all the fever cases under active and passive surveillance in the TB Board area. Malaria positive cases are treated with Radical Treatment by 4 Chloroquine and 8 Primaquine Tablets for each case. General Laboratory investigations also carried out in this TBP Hospital during 2022-23.

- **Spraying:** Malathion & 50 EC has been under for Spraying, Fogging and for controlling adult Mosquitoes. Temephos 50 EC is also used for spraying and controlling mosquitoes in the TB Board colonies in the TB Dam/ Hampi Camp / Toranagallu and Bellary. "Temephos 50 EC" is being used in the TB Board colonies to kill the Larvae of the Mosquito. This has been sprayed on the water surface area as a measure of Anti Larval Operations. Responsar insecticide is also used for destroying mosquitoes, cockroaches, and flies of indoors.
- **Bacteriological and Chemicals analysis of water:** The water samples of TB Dam and Hampi Camp were sent periodically for conducting Bacteriological and Chemical analysis at MSV Analytical laboratories Ballari during the years 2022-23. The Drinking water samples from TB Dam & HPC have been sent for Chemical & Bacteriological examination once in every 3 months.

- **General sanitations:** TB Dam / Hampi Camp colonies are kept clean and tidy. The drains are cleaned on alternate days, apart from the sanitation. Malathian 50 EC is used for controlling the adult mosquitoes. Regular sanitation works were carried out during the year 2022-23 Removal of Juli flora and parthenium weed has been cleared off during the year 2022-23 on job work. basis.
- **Immunizations:** The children of the TB Board were immunized to prevent the communicable diseases by Vaccinating 'O' Polio, BCG, pentavalent, Measles & Rubella (MR),JE (Japanese Encephalitis), Vit A Booster DPT Booster with coordination of Health department Hosapete.
- **Deliveries.** Total 03 Deliveries are conducted in this TBP Hospital during the year 2022-23.

6.5 TBP HOSPITAL, TB DAM & HPH DISPENSARY

Activities of the Medical Unit of the TBP Hospital, TB Dam and TBHES Dispensary, Hampi Camp during the year 2022-23 are as given below;

TBP Hospital, TB Dam

- Out-patient Department – Nearly 45,603 outpatients and 529 in-patients were treated during the year 2022-23.
- Family Welfare Programme – All the couples in the TB Board area were advised to adopt small family welfare norms.

TBHES Dispensary, Hampi Camp

- Outpatient Department – Nearly 6,415 out patients were treated during the year 2022-23.
- Inpatients are not treated in the TBHES dispensary, Hampi Camp.

6.6 AMBULANCE SERVICES AT TBP HOSPITAL, TB DAM

A New ambulance was purchased during the month of May 2019 and is being used for the benefit of the patients.

6.7 X-RAY SECTION

The X-ray section is being maintained by the Hospital. During the year 2022-23, 214 X-rays have been taken and out of which 141 are Male and 73 are female.

6.8 LABORATORY SECTION

The laboratory section is being maintained by the Hospital authorities. Tests like HB, CBC, BT, CT, Blood sugar, Renal function test, Lipid profile, Liver function test and other Hematological tests are routinely conducted in the lab by semi auto analyzer. The total number of tests done during the year 2022-23 are 2091 out of which 726 are Male, 1033 are female and 332 are children.

6.9 OPERATION AND MAINTENANCE BY THE DIFFERENT UNITS

One Health Inspector each were working in TB Dam and Hampi Camp for Health & sanitation work and for smooth functioning of the scheme.

6.10 FINANCIAL PERFORMANCE

The budget for the Health and Medical activities at TB Dam, Torangallu and Bellary is provided under Irrigation wing of TB Board, whereas for Hampi Camp is provided under TBHES wing.

The financial performance for the last five years is indicated below-

(Rupees in Lakhs)

Year	Wing	Budget allocation	Expenditure incurred
2018-19	Health	140.66	281.38
	Medical	87.12	72.51
2019-20	Health	142.68	103.91
	Medical	76.26	71.81
2020-21	Health	165.97	122.12
	Medical	62.25	67.59
2021-22	Health	236.69	126.86
	Medical	186.00	115.31
2022-23	Health	173.93	150.99
	Medical	62.11	91.96

OPERATION AT TBP HOSPITAL



HEALTH CHECKUP CAMP FOR KV SCHOOL, TB DAM



ADMITETED PATIENTS IN TBP HOSPITAL



CONDUCTED BLOOD TEST FOR CHAIRMAN, TBB



HEALTH OFFICER VISIT TO THE TB BOARD COLONY



7.1 INTRODUCTION

The Tungabhadra Gardens in the downstream of Dam area is the main source of attraction for the tourist/visitors, who are visiting TB Dam. It is one of the oldest and biggest existing gardens since 1956 in the North Karnataka area. About more than 5 lakhs tourists/visitors are visiting the gardens annually, out of 10 to 12 lakh visitors who are visiting the TB Dam. Due to COVID-19 Pandemic, visitors are decreased as the garden was closed for visiting public due to lockdown restrictions. The Garden Unit (GU) under the Irrigation Wing is incharge of all Horticulture activities in the Dam area, colonies and canal banks under the jurisdiction of the TB Board. It is also responsible for the development and maintenance of plant wealth in the Board's area.

7.2 ORGANIZATION

The Senior Assistant Director of Horticulture who has been deputed from the Department of Horticulture, GoK is working as Superintendent of Gardens in TB Board. He is looking after all the technical/scientific matters of Garden Unit. The Garden Unit was upgraded in the year 1999 vide 167th Board meeting, on par with Sub Divisional Officer, until then it was acting as a Garden section office. Superintendent of Gardens of Garden Unit is assisted by one Assistant Horticulture Officer in Horticulture activities and one Section Officer for civil works of the Garden Unit. For administrative, accounting and execution of the works, the Garden Unit is functioning as a Sub

Division under the Administrative and financial control of Executive Engineer, HW & HLC Division, TB Board, TB Dam.

7.3 TASKS

The tasks of the Garden Unit are given below:

- To maintain the existing parks, gardens and Children's park.
- To maintain still fountains, Musical Dancing Fountains.
- To maintain Boating Pond, vehicle parking, Garden Entrance fee collection etc.,
- To Execute and monitor all approved works in garden unit.
- To look after all PPP projects and tendered works like Water Park, Children play & dashing car etc.,
- To maintain the Mini Bus facility, Canteens, Toilets etc.,
- To maintain canal plantations, woodlots and Vaikunta Guest House hillock plantations;
- To rejuvenate existing lawns in various parks and gardens of the Board;
- To raise seasonal and annual flower beds in parks and gardens and to make floral arrangement;
- To raise the new plantation in vacant lands of TB Board.
- To maintain Gardens at Hampi Power House colony and
- To make special arrangements for celebration of the national festivals like Independence Day & Republic Day.

7.4 PARKS AND GARDENS

Since completion of the Dam, the Board has developed and maintained many parks, gardens at downstream of the Dam, plantation adjacent to canals and in the TB Dam colonies on the right side. These gardens are attracting many tourists. A brief description of the important parks and gardens, maintained by the Board is given as below;

I. NANDANAVANA

Nandanavana was developed during the year 1956-57 soon after completion of the Dam. This garden is located just below the Dam running parallel to it. It has an area of about 2.43 ha and is designed and developed on the lines of Brindavan Gardens at Krishna Raja Sagar Dam near Mysore. It is well laid with four terraces at different elevations. The first terrace is housing circular type fountain with a Nandi statue at the center. All terraces are provided with fountains of various designs, with different colour lights running parallel and perpendicular to the layout of the garden. At the end of the last terrace lord Shiva statue is placed at the top of the artificially created hillock. A water fall is also provided utilizing the height of the hillock. This garden has well maintained lawns, lantana on the slopes, seasonal and annual flower beds, Christmas trees, cypress plants and topiary arches.

Anandavana Garden, attached to Nandavana garden also have beautiful circular fountains, Ornamental Entrance arch. During this year improvements to the footpath with Granite slabs taken to enhance scenery of Anandavana Garden.

II. JAPANESE PARK

Japanese Park was developed in the year 1968-69 with a total area of 7.29 ha and is located adjacent to Nandanavana garden. It has 3 water ponds. Namely mango shaped Pond, bean shaped pond and children peddle pond. This park has arches, ornamental flowering trees, flower beds, well laid out lawns, etc., Also facilities like children play equipment provided to enhance the joyfulness of the children in TB Garden. Entertainment facilities like 9D virtual reality show, children peddle boating also provided in the Japanese Garden.

III. VAIKUNTA GUEST HOUSE GARDEN

Garden at Vaikunta Guest House was developed during the year 1960-61. It is a formal garden with well-designed fountains, flower beds, topiary arches, flowering trees, aesthetically cut lawns etc.,

IV. CHAKRAVANA AND TRIVENI BAGH

A Circular Park called as CHAKRAVANA and a triangular park called as TRIVENI BAGH are located in front of the Administrative Building. They are developed at the time of construction of the Dam. It is also a formal garden with lawns, flowering trees, shrubs, arches etc. In the centre of the Chakravana the concept of "GOVARDHANA GIRI GOPALA" art is created. It is provided with jet and flower fountains with colorful lights. The concept is suitably illuminated. The entire periphery of the Chakravana is provided with ornamental grill which provides protection apart from looking beautiful.

With the Backdrop of Vijayanagara Empire

and stone city of Hampi, a beautiful granite arch is created at the entrance of the garden and is also beautifully illuminated using RGB lights, which is visual delight to watch in the evening. Flag hoisting on Independence Day and Republic Day will be carried out every year by the Secretary, TB Board at TRIVENI BAGH.

V. PLANTATION

As a mark of World Environment Day, Garden Wing has developed tree plantations by planting about 4000 plants in TB Board vacant areas to safeguard the Board land as well as for enriching the greenery as a mark of minor contribution in reducing the Global Warming.

VI. BOATING FACILITY

During 2010-11, the Boating facility in pond of 200 x 90 Mtrs size was created at old TSP yard with beautified surrounding area. Later on, it has been renovated during 2012- 13 and has been made available to tourists visiting the gardens. It is further renovated and beautified by providing SS railing, light poles and LED lamps around the pond. There is a small refreshment counter providing coffee, Tea and snacks for the visitors. The boating pond is more beautified by providing turfing (lawn) on sloping sides of pond area which enhanced the beauty of the pond with lush greenery around the pond.

VII. ROSE GARDEN

A new rose garden with about 500 rose plants was established by the side of Japanese park in 2001. The rose garden has varieties of blooming plants aesthetically arranged.

7.5 AMUSEMENT PARK & DASHING CARS

The Garden unit has taken up the following works in the vacant place of Garden area of TB Board on PPP model as a part of Tourist attraction.

- a) Amusement Park for children in vacant place of Garden area of TB Board for the period from 01.01.2021 to 31.12.2027 @ Rs.1,51,200/- per month payable to the TB Board.
- b) Dashing Cars for children in vacant place of Garden area of TB Board for the period from 01.01.2021 to 31.12.2027 @ Rs.1,51,200/- per month payable to the TB Board.
- c) Water Park in vacant place of Garden area of TB Board for the period from 01.01.2021 to 31.12.2027 @ Rs.90,480/- per month payable to the TB Board. This facility is yet to be commissioned.

7.6 OTHER ATTRACTIONS

The gardens, parks and lush green surroundings of the Dam attracts a lot of visitors every year. In addition to the parks and gardens the visitors are much fascinated by seeing and enjoying the Aquarium, Musical Dancing Fountain, Mini Zoo, Aviary and Children's park.

I. MUSICAL DANCING FOUNTAIN

A set of fountains dancing to the rhythm of the music with varying colour lights using the state of art technology has been provided as a source of attraction and entertainment to the visitors. The musical dancing fountain was constructed in the year 1992 in the Japanese Park. The computerized operation to synchronize with the music was introduced in 1999 the

reverberating music, fascinating colourful lights and vivacious fall of Water droplets dancing to the tune of music from the fountains take away the stress of themind and offers full recreation to the young and old people alike. The visitors assemble around to enjoy the fountain as soon as the dusk falls. Musical Dancing Fountain (MDF) is surrounded by Avenue plant groves. All these Avenue plant groves are highlighted by providing RGB focus lights to enhance the beauty of the Garden. This made the Vicinity of MDF is more pleasing, colourful and beautiful.

II. TB DAM MINI ZOO AND AVIARY

The TB Dam Mini Zoo is located by the side of Japanese Park. It was developed in the year 1982 in an area of about 6.07 ha. It had about 165 spotted deers and 30 black bucks. Also, A small aviary was housed near the Rose Garden and was developed in the year 1989, it had 5 Pea-fowls. But, As per the Central Zoo Authority's directions the zoo is closed since 07.01.2022. In line with the directions of CZA, All the animals and birds have been shifted with all the precautions, in front of the Forest department Officers.

III. CHILDREN'S PARK

Children's park is located in the township area of TB Dam on the main road and was developed during 1984. This year renovation of park has taken up and park is provided with plenty full new varieties of play articles like Outdoor multi activity play system, Sea-Saw, Double wave slide, Triple swing, Rockers etc., which aimed at providing good entertainment

and exercise to improve the mental and physical health of children.

IV. VERMI CULTURE COMPOST UNIT

The Gardens are known for their healthy atmosphere and as a result many people wish to spend more time in the Gardens. But the use of inorganic fertilizers and plant protection chemicals for day to day maintenance adversely affected healthy environment of gardens. In order to keep the garden free from pollution and at the same time to provide eco-friendly manure for the health of the plants, Garden Unit has established vermi culture compost units in the TB Dam Garden. The establishment and production of vermi culture compost unit has resulted in beneficial use of garden waste as well as other biologically degradable waste from TB Dam colony.

7.7 IMPLEMENTATION OF 'SWACHH BHARAT ABHIYAN'

As part of 'Swachh Bharat Abhiyan' a Nation wide programme, the Garden Wing has taken up 'Cleanliness Campaign' at regular intervals in and around TB Dam with the active participation of the TB Board staff with the objective to promote the cleanliness awareness among the public.

7.8 PUBLIC AMENITIES TO VISITORS

Tungabhadra Dam, being 6 km away from the District headquarters Hosapete, is well connected by rail and road. The National Highways 50 and 67 pass through TB Dam. In addition to the Vaikunta Guest House and Inspection Bungalow maintained by the Board,

dormitory accommodation is provided in M.S Tirumala Iyengar Hall for the visitors. Further, there is accommodation provided by Karnataka State Tourism Development Corporation. The Board for the benefit of common visitors provided a free tourist shelter at the main entrance of TB Dam with facilities like canteen, cloak room, beverages / bakery items and bath & toilets rooms etc. The salubrious climate, beautiful surroundings, variety of attractions including amenities available in the gardens and parks attract the visitors and they happily pay repeated visits year after year.

7.9 MINI BUS FACILITY

Mini Bus facility has been provided to the tourists to enable them to enjoy stress free journey in the site seeing, the beauty of the TB Dam, Gardens and places like Vaikunta Guest House, Dam Model house, Boating Pond area at a cost of Rs.20/- for adults and Rs.10/- for children.

7.10 ENTRY FEE FOR GARDENS

The Board in its 217th meeting held on 29th September 2021, accorded approval to revise the entry fee for

Sl.No	Garden Entrance Fee	Revised rates (Rs.)
1	General Public above 10 years of age	10.00
2	Children below 10 years of age/ Physically challenged persons/ Members of recognized farmer organization/ Fisheries co-operative society/Social welfare Organization/Primary School children visiting TB Dam and gardens under Chinnara Karnataka Darshan Programme/ TB Board employees and their family members.	No Entry Fee

II) Entry Fee for Fish Aquarium

Sl. No	Fish Aquarium Entrance Fee	Revised rates (Rs.)
1	General Public above 10 years of age	10.00
2	Children below 10 years of age	No Entry Fee

III) Vehicle Parking fee

The Board in its 215th meeting held on 15th February 2020, decided to enhance the entry fee for vehicle parking with effect from 01.04.2020 @ the following rates.

Sl. No	Category of Vehicle (PerDay)	Existing Rates (Rs.)	Enhanced rates (Rs.)
1	Bus, Truck, Mini Bus, Van and such other heavy vehicles	40.00	60.00
2	Tractor, Car, Jeep and other such other light Vehicles	20.00	30.00
3	Auto Rickshaw	10.00	20.00
4	Two wheeler	10.00	10.00
5	Cycle	02.00	free

7.11 EXPENDITURE/REVENUE FOR THE LAST FIVE YEARS FROM GARDEN UNIT

(Rupees in Lakhs)

Year	Expenditure	Revenue
2018-19	643.85	140.83
2019-20	811.70	168.66
2020-21	506.26	77.38
2021-22	464.10	89.96
2022-23	260.37	165.90

7.12 SOURCE OF REVENUE GENERATED DURING 2022-23

Sl. No	Particulars of source of revenue	Amount In Rs.
1	Collection of Garden entry fee from Tourists	66,19,003
2	Collection of vehicle parking fee from Tourists	15,52,746
3	Providing of Mini Bus Service to the Tourists	17,65,000
4	Running of Boating facility by using pedal Boats for Tourists	1,68,000
5	Kiddy hand pedal boating in Japanese garden	1,46,664
6	9D VR cinema show in Japanese Garden	17,688
7	Installation of BMI Electronic Weighing Machine Near Fish Aquarium	13,200
8	Installation of coin operated weighing machine near Fish Aquarium & Public Amenity Centre near Main entrance gate	13,560
9	Running of canteen at Public Amenity Centre	2,15,220
10	Shop for selling of Bakery items and chats etc. near main entrance left side Public Amenity Building TB Dam	33,600
11	Running the canteen in TB Dam Japanese Garden Near Musical Dancing Fountain and Fish Aquarium	2,00,500
12	Installation of Nandini Milk Product Parlor at Parking area	37,800
13	Running the canteen to sell Refreshment items in Childrens Pedal boating premises to TB Dam Gardens	8,640
14	Amusement Park for children vacant places of gardens	18,14,400
15	Dashing Cars	18,14,400
16	Water Park in vacant places of garden area	6,33,360
17	Installation of 04 Nos. Massage Chairs & 06 Nos. of Knee Massage Chairs	24,000
18	Running the Canteen Situated in Japanese Garden behind MDF	4,74,000
19	Fish Aquarium Entrance Fee	10,38,000
Grand Total		1,65,89,781

GARDEN ATTRACTIONS







PLANTATION AT TB GARDEN BY SRI C. NARAYANA REDDY, MEMBER TB BOARD, AP



PLANTATION AT TB GARDEN BY SECRETARY, TB BOARD



SECURITY SYSTEM



8.1 INTRODUCTION

The Security Section is in charge of the overall security of various structures, installations, canals and colonies maintained by the Board. Even though the Board has the status of a State Government with regard to the operation and maintenance of the project within the limits of the Board, it has no police staff of its own to deal with the law breakers, criminals, etc. Also, it has no judicial powers to punish anyone taking water without authorization either from the reservoir or all along the canals maintained by the Board. For these matters, the local revenue and police authorities of Karnataka assist the Board.

8.2 ORGANIZATION

The Secretary, Tungabhadra Board is also designated as Chief Security Officer and the Assistant Secretary as Security Officer. The Security Section functions under the direction of Chief Security Officer.

The Board in its 213rd meeting held on 27.12.2018 at Hyderabad decided to go for the Karnataka State Industrial Security Force (KSISF) for Tungabhadra Dam, Power Houses (TB Dam & HPC), Dam Gate, & Canals (HLC & LLC). Tungabhadra Board had requested to deploy 52 personnel initially (i.e., PSI 02, HC 10 & PC 40) for an initial period of five year under phase-I. Accordingly 33 Nos., of KSISF personnel have joined in Tungabhadra Board on 27.04.2021. The Board has addressed to the Additional Director General of Police, Internal Security Division, KSISF, Bengaluru to deploy remaining 19 KSISF Personnel as soon as possible. Subsequently, the 29 Nos of DAR Police and 08 Nos Civil Police who were working earlier in TB Board

were relieved and repatriated to the Office of the Superintendent of Police, Ballari on 30.04.2021. In addition to the above, Private Security Agency is entrusted with watch & ward of vulnerable areas on the Canals, Office premises, Board Colonies etc.,

The Organization Chart of Security Section is at **Annexure 8.1**.

8.3 FUNCTIONS

The Security staff has been assigned with the following duties:

- To check entry of visitors in the restricted areas.
- To perform day and night patrolling duties.
- To carryout night checking of security guards, night watchmen and private security guards.
- To collect intelligence information regarding activities against the interest of the Board.
- To take part in prevention of TB Board land encroachment/ unauthorized occupations etc., in the Board's colonies
- To carry out special work of investigation on complaints.
- To render assistance to the Officers in the issue of passes for vehicles, visitors, tourists, etc and
- To perform any other duties assigned by the Chief Security Officer.

8.4 SECURITY OF DAM AND POWER HOUSES

The Dam and the Power Houses situated on the right and left banks of the river and

at Hampi have National importance. Realizing the need to provide security at these places, GoK approved Industrial Security Scheme covering this installation vide Order No HD 68 SGD 63 dated 10.05.1963. This scheme has laid down detailed security instructions. The then Sub- Station at Bellary also came under the Industrial Security Scheme since 1973 vide Go K Order No HDIS/ SCD 73 dated 27.09.1973. This was completely revised and a fresh Scheme was approved by GoK vide their Order No HD 779 SST 81 dated 25.11.1981. The Dam, the three power houses and the Sub-Station at Bellary have been declared as prohibited places by the GoK. Under the Industrial Security Scheme, five security posts have been established at the following locations:

- Left Bank gate of Dam
- Right Bank gate of Dam
- Left Bank Power House, Munirabad
- Right Bank Dam Power House
- Right Bank Hampi Power House

The Left Bank gate of Dam security post is manned by the personnel of the District Armed Reserve (DAR) guards, who are deputed by the Superintendent of Police, Koppal, GoK and the expenditure for their deployment at the Left bank gate of the Dam is borne by the KNNL, Munirabad.

The Right Bank gate of Dam security post is manned by the personnel of KSISF, who are deputed from Government of Karnataka. The expenditure for their deployment at the Right bank gate of the Dam, Right bank Dam Power House and Hampi Power House is borne by the TB Board. For the left bank power house, the expenditure is directly paid by KPCL to the Police Department.

8.5 SECURITY OF CANALS

Many a times farmers resort to forcible excess drawals of canal water and also damage Board' s properties, thereby disturbing water management and disrupting the entire irrigation system. To prevent such activities and also to give protection to its staff in safeguarding various structures on the canals from vandalism and damage, Government of Karnataka and Andhra Pradesh were requested by the Board to declare certain areas around these structures as prohibited areas. Government of Karnataka vide their notification No. HD/268/ SST/95 dated 17.10.1997 has declared 140 such structures falling within the territory of Karnataka as prohibited areas. Arrangements are already made to restrict the movement of general public in these prohibited areas.

The number of KSISF Personnel were proposed to deploy on different security posts as below.

Security Post	PSI	HC	PC
TB Dam Dam/DPH/HPH/ Colonies	01	06	20

8.6 OTHER SECURITY INTERESTS

Government of Karnataka has established a regular police station at TB Dam under the control of one Sub-Inspector, which is catering to the requirement of the Board and its employees living in the colonies at TB Dam.

The Board in its 135th meeting held on 06.05.1989 decided to entrust the job of watch and ward of vulnerable areas, office

premises, stores, etc., to private security agency as the watchmen employed by the Board were insufficient. Accordingly, a private security agency M/s Professional Security Service, Bangalore was engaged for the security of the drainage gallery, office premises, rounding Official colony, rounding Hampi camp colony etc., with effect from 16th January, 1997. During the year 2022-23, a private security agency M/s. Security & Intelligence Service (India Limited), Hosapete has engaged 80 male security guards, 4 women Security guards, 3 Security Supervisors, 5 computer operators and 4 Security Drivers. As advised by Central & State Intelligence Bureau, 22 Cameras were installed at vulnerable / sensitive places and also Hand-Held Metal Detector (HHMD) & Door Frame Metal Detectors are provided for the safety & security of the vital installations and monitored daily by Security Section of Tungabhadra Board.

8.7 FINANCIAL PERFORMANCE

The Budget of the Security Section is included in the Irrigation Branch grant. Irrigation wing of the Board will fix-up the private security agency once in two years by calling open tenders and the total expenditure is initially borne by Irrigation wing of the TB Board.

Later on the expenditure incurred is shared between the Irrigation wing and TBHES wing of TB Board appropriately. The expenditure of Security Section incurred during the year 2022-23 is as given below;

(Rupees in Lakhs)

SI No	Description	Expenditure
1	KSISF Personnel	195.87
2	Security unit at Secretary office	14.79
3	Private Security at Dam, Power Houses, TB Dam & Hampi camp Colonies.	454.79
	Total	665.45

8.8 PHYSICAL PERFORMANCE

The routine duties assigned to the Security staff were accomplished. Vigilance to safeguard the properties of the Board was increased. As advised by the Police Department, Government of Karnataka the movement of vehicles nearer to the Dam has been stopped and pedestrian visitors were only allowed to go near the Dam.

ACTIVITIES OF KSI SF PERSONNEL ON TB DAM





9.1 Latest Dam Safety Review Panel Inspection.

The Government of Karnataka has reconstituted the Dam Safety Review Panel (DSRP) vide GO No:WRD:7:DSP:2021 Bangalore dated 12.08.2021 to evaluate the safety of existing large Dams of the State of Karnataka once in 10 years for effective monitoring of safety aspects of large dams in operation and for the dams among them to which the State proposes to carry out repairs, rectification and rehabilitation under the world bank founded DRIP Phase II & III programme of the Government of India.

The State DSRP team headed by Sri. A.K Bajaj, Chairman, DSRP has inspected the Tungabhadra Dam on 08th October 2021. The Review and recommendations of DSRP and follow-up action by the Project authority is as given below.

Sl. No.	Review and Recommendations of DSRP	Follow-up action by the project authorities
1	3.4.1 The effect of the grouting carried out and the seepages in the pegmatite zone between LS 1380 ft and 1460 ft in the dam site should be evaluated for taking further action.	The grouting work is in progress, the studies on effects of grouting will be carried out soon after completion of grouting work.
2	3.4.2 Information and data of occurrence of any earthquake events along this zone should be collected and studied to initiate further Precautionary measures. In this connection, it is emphasized for Installation of seismic monitoring instruments at dam site.	Action been taken to install the Seismic Monitoring instrument and the work is under progress.
3	3.4.3 As verified from the details the masonry and spillway structures are constructed on stable rock formations and necessary foundation treatment has been carried out at the time of construction. As such there are no specific remedial measures for the foundation considered necessary by the panel at present from the geological point of view.	The curtain grouting work is proposed for foundation treatment from ch.0.00 ft to ch.3069 ft and work is under progress.

4. 3.4.4 It should be checked whether grouting at the dam masonry and Upstream protection of the dam slopes by racking and gap filling with mortar has been undertaken or not and remedial measures if necessary are to be initiated. 3.4.5 From consideration of safety of the dam under normal and seismic conditions of loading coupled with development of high uplift pressures recorded in the drainage gallery of the dam, it is advisable to consult Land Sat Map (satellite Imaginary) if not done so far to confirm the above assessment of foundation condition and take remedial measures if so warranted
5. 3.4.5 From consideration of safety of the dam under normal and seismic conditions of loading coupled with development of high uplift pressures recorded in the drainage gallery of the dam, it is advisable to consult Land Sat Map (satellite Imaginary) if not done so far to confirm the above assessment of foundation condition and take remedial measures if so warranted.
6. 3.4.6 The dam is constructed long back and there was no facility of satellite imageries at that time and it would not have been possible to assess any faults/ folds in the foundation. Now, it is better to consult satellite imageries regarding; foundation of the dam and remedial measures if necessary, should be initiated.
7. 4.4.1 Reservoir operation schedule needs to be developed keeping in view of the decision to provide protective works that may be required to provide head works of Raya Basavanna canal and Right bank Hydroelectric power units existing between Ch. 1360ft to 1520ft from inundation under flood if spillway is operated to full discharging capacity of 18406 cumecs (6,50,000cuses). Depending on the outcome of decision, the reservoir operation schedule should be finalized and implemented accordingly.

The curtain grouting work is proposed for foundation treatment from ch.0.00 ft to ch.3069 ft and work is under progress. The grouting & PICC pointing on upstream portion works are under progress at left side portion of Dam by the O/o CE, KNNL, ICZ Munirabad which has been taken under DRIP-II & III & right side portion has been taken by TB Board with its own regular funds.

It will be initiated.

It will be initiated.

Presently Gate operation is being carried out as per the CWC operation schedule and as per the CWC approved Rule Curve Report for TB Reservoir which was received on 03.03.2022.

8 4.4.2 Develop Rule curves, taking into consideration loss of storage owing to sedimentation in the reservoir, for reservoir operations during significant floods including HOF and PMF by routing of these floods without exceeding MWL RL 497.74 m (RL 1633 ft).

9 4.4.3 Determine maximum Free-board requirement of the dam adopting Saville's method of analysis and provide top level of dam accordingly.

10 4.4.4 The reservoir operation schedules should be developed for the existing capacity of the reservoir after siltation and adopting the procedure outlined in **IS: 7323 - 1994** or its latest version.

The CWC has provided the Rule Curve Report for TB Reservoir on 03.03.2022. The same is being followed appropriately.

The study of free-board is already done by M/s Aarvee Associates Architects Engineers & Consultants Pvt. Ltd, Hyderabad, and in Present DSRP report Sl. No **4.2 Adequacy of Spillway capacity** it is Stated like "The dam is in operation since 68 years and the maximum flood passed through the surplussing arrangements is 10453 Cumecs (369152 cusecs).

From consideration of gross storage capacity of 2855.887 Mcum, the Dam falls under the category of large dam. The available freeboard for the dam while passing the discharge considered in the design of spillway is 2.14 m (TBL 499.88 m – MWL 497.74 m) which is more than 1.50 m minimum prescribed for the category of large dam. However, the required free board of 1.50 m above the MWL needs to be ensured when passing the PMF. So far it is clear that, the free board for revised PMF is sufficient.

Presently gate operation is being carried out as per the CWC operation schedule and as per the CWC approved Rule Curve Report for TB Reservoir on 03.03.2022.

- | | | |
|-----------|---|--|
| 11 | 6.8.1 Check the stability of composite dam both under seismic and non-seismic conditions of loadings creating soil structure simulation using Non-linear Finite element model. | Stability of composite dam both under seismic and nonseismic conditions studies already done by M/s Aarvee Associates Architects Engineers & Consultants Pvt. Ltd, Hyderabad. |
| 12 | 6.8.2 The undulations on the downstream slope of earth backing of composite dam should be improved and surface drainage provided as recommended in item (a) of Para 6.2. The berm provided on the downstream slope should be re-sectioned to conform to the design section. | The composite dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, the re-sectioning work is included under the DRIP-II & III but CWC/CPMU/SPMU has not given clearance for the composite dam works. |
| 13 | 6.8.3 Action should be taken immediately to implement the recommendations (1) to (8) made under Para 6.2 above for the composite dam. | The composite dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, action may be taken by CE, KNNL, ICZ Munirabad |
| 14 | 6.8.4 Seepage measurements should be commenced henceforth on the V-notches provided in the toe drain of the earth backing provided downstream of composite dam. Measurements should be analysed and assess the stability of dam. | The composite dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, it will be implemented by CE, KNNL, ICZ Munirabad |
| 15 | 6.8.5 Surface drainage for the roadway should be provided on the top of the composite dam and also on the downstream earthen slope up to its toe to drain water during rainfall. A collector drain should be provided all along the downstream edge of roadway discharging into paved chutes aligned along downstream slope covering the earth backing and spaced at 30 to 45 m to eventually discharge into open drain to be provided between rock toe and CC cut-off along the upstream periphery of the pond formed below and lead the discharge into existing valley below. The surface drainage now proposed should conform to the provisions made in IS: 8237-1985 .
6.8.6 Cause for the slight bulge observed near the FRL level on the upstream for the natural hillock should be properly assessed and remedial measures, if necessary to be taken up. | - do - |

- 16** 6.8.6 Cause for the slight bulge observed near the FRL level on the upstream for the natural hillock should be properly assessed and remedial measures, if necessary to be taken up.
- The natural hillock comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, action will be taken for remedial measures by CE, KNNL, ICZ Munirabad.
- 17** 6.8.7 Vegetation observed on the upstream toe at FRL level in the natural hillock portion at Ch. 2257.61 to 2955.60 m (Ch. 7407 to 9697 ft.) should be cleared and kept clean.
- The natural hillock comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, the vegetation has been removed.
- 18** 6.8.8 Vegetation observed on the downstream slope of earthen dam from Ch. 2105.21 m to Ch. 2257.61 m (Ch. 6907 to 7407 ft) should be cleared and the seepage locations are to be identified.
- The Earthen Dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, the vegetation has been removed.
- 19** 6.8.9 Surface drainage for the roadway provided at top of the earthen dam and also of the downstream slope up to its toe should be provided to drain rain water. A collector drain should be provided all along downstream edge of roadway discharging into paved chutes aligned along the downstream slope of the dam. The spacing of paved chutes and its layout shall conform to the provisions made in **IS: 8237-1985**. The discharge from the paved chutes should be carried in a closed (pipe) conduit of required size and drain at the discharge end of LBHLC sluices located at Ch.10875 ft. The alignment of closed conduit may be decided considering existence of structures built on the downstream of the dam.
- The Earthen Dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, action will be taken by CE, KNNL, ICZ Munirabad
- 20** 6.8.10 Vegetation grown on the entire downstream slope of the earthen dam should be cleared for providing turfing.
- The Earthen Dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, the vegetation has been removed.
- 21** 6.8.11 Large trees are growing below the toe of downstream slope. One major tree has grown at the top level of the downstream side. This tree should be uprooted completely and back filled with properly compacted material. Any deep rooted tree will roots extending towards the upstream of the dam can affect the stability of slope, by developing of piping.
- The Earthen Dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, the vegetation/tree/roots has been removed.

- 22** 6.8.12 Action should be taken to clear the silt accumulated in the outlet of the drain provided at Ch 1761.74m for the roadway over the dam top in the non-over flow section and lead the discharge to nearby valley.
- The Earthen Dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, Silt have been cleared.
- 23** 6.8.13 Pitching should be provided for the downstream slope of the hillock at the junction of the non-overflow dam with the natural hillock at Ch. 1749.55 m.
- The Earthen Dam comes under the Jurisdiction of O/o CE, KNNL, ICZ Munirabad, action may be taken by CE, KNNL, ICZ Munirabad.
- 24** 6.8.14 Carryout dam stability analysis adopting insitu density and strength of insitu masonry after grouting and actual uplift developed after grouting of foundation rock both under seismic and non-seismic conditions of loadings stipulated in **IS 6512** and **IS 1893** — “Seismic Resistant design of Structures” and evolve safe and stable sections after strengthening as required.
- The Grouting work is under progress on both left & right sides of dam. Once the grouting work completes, action will be taken to carryout dam stability analysis under seismic and non-seismic conditions of loadings stipulated in **IS 6512** and **IS 1893**.
- 25** 6.8.15 Assess strength of in situ stone masonry and of the mortar used in the construction of the masonry dam by extracting cores of masonry in the zones of maximum stress at few critical locations in the dam body and at interface of masonry and foundations by core drilling NX size holes deploying double core barrel assembly for the drilling rigs.
- M/s Aarvee Associates Architects Engineers & Consultants Pvt.Ltd, Hyderabad carried out the tests and submitted the report.
- 26** 6.8.16 All the seepage points in the Non over flow dams on both left and right banks should be marked to identify reaches requiring grouting.6.8.17 Reasons for the sweating observed on the downstream face of the Non overflow section from Ch. 1798.38 m to Ch. 1314.56 m should be investigated and the possibility of lime leaching be investigated and remedial measures to be initiated. Topological mapping of the dam for confirmation of stretches of saturation of the downstream masonry should be got done.
- M/s Aarvee Associates Architects Engineers & Consultants Pvt.Ltd, Hyderabad carried out the studies (tomography method) and identified the seepage points.

- 27** 6.8.17 Reasons for the sweating observed on the downstream face of the Non overflow section from Ch. 1798.38 m to Ch. 1314.56 m should be investigated and the possibility of lime leaching be investigated and remedial measures to be initiated. Topological mapping of the dam for confirmation of stretches of saturation of the downstream masonry should be got done.
- M/s Aarvee Associates Architects Engineers & Consultants Pvt.Ltd, Hyderabad carried out the studies and identified the sweating patches based on the investigation, the body grouting work has been taken both left and right side of dam and the work is under progress.
- 28** 6.8.18 Action should be taken to make the downstream zone of masonry water tight by grouting after determination of the in-situ permeability as per procedure laid down in **IS: 11216-1985.**
- As per the recommendation, the in-situ permeability test been carrying before grouting as per IS code.
- 29** 6.8.19 Grout the dam masonry wherever high permeability exists and sweating and isolated patches of seepage are visible. In addition, carryout grouting of foundation rock wherever high uplift pressures are developing to minimize uplift pressures.
- As per the recommendation, wherever high permeability exists, body grouting work is being carried out & wherever high uplift pressure are developing, curtain grouting work is being carried out. As per the recommendations, only the work of PICC pointing is being carried out on upstream face of dam.
- 30** 6.8.20 Undertake grouting of the masonry dam body covering the area where water is seen issuing on the downstream face. Before undertaking grouting work, it is necessary to create a grout cap in the entire area on the upstream face in the zone to be grouted. This treatment will consist of deep raking of the joints to a depth of at least 38 mm and same thoroughly cleaned by compressed air jet. Thereafter the joints should be filled with epoxy mortar under pressure using mortar guns to effectively seal the joints.
- 31** 6.8.21 Cause for the leakage observed on downstream side of the Non overflow masonry dam at Ch. 1477.38 m should be investigated and remedial measures to be initiated to plug the leakage early.
- The body grouting & PICC pointing works on both left side & Right side Non-Overflow section are under progress.

- 32** 6.8.22 It should be ensured that the floor level of the transformer yard of left and right bank power houses are well above the tail water level in the mother valley when passing routed PMF flood to ensure that the entire transformer yard is safe from flooding.
- The floor level of the transformer yard of left and right bank power houses were checked and both are well above the tail water level and it is safe.
- 33** 6.8.23 It is necessary to check and verify the existing guidelines of gates operation with relevant **IS:7323-1994** for operation of vertical lift gates for hydraulic structures and revise accordingly. 'The methodology adopted for gate operations are given in Para 6.3.2 which should be followed.
- Presently Gate operation is being carried out as per the CWC Operation Schedule and it is verified that, it is as per the existing guidelines of gates operation only.
- 34** 6.8.24 Seepage observed on the downstream face of non-overflow dam between Ch. 1475.56 to Ch. 1314.56 m at the junction of overflow section (161 m) should be measured; monitored and necessary remedial measures need to be initiated immediately.
- The mentioned part comes under the Jurisdiction of O/o the CE, KNNL, ICZ, Munirabad, action may be taken by CE, KNNL, ICZ, Munirabad.
- 35** 6.8.25 Seepage observed all along the right bank non-overflow section from Ch. 110 m to 613.56 m (Ch. 360 ft. to Ch. 2013 ft) should be measured, monitored and necessary remedial measures need to be initiated immediately. Blackish material found in the joints of the downstream face should be raked properly and pointing is to be done.
- As per the Recommendation, the works viz., grouting, PICC pointing on upstream portion and regular pointing on downstream portion of dam are under progress.
- 36** 6.8.26 The stability and strengthening of spillway piers should be finalized in consultation with CWPRS, Pune considering unsymmetrical transfer of load to the adjacent NOF monoliths due to their eccentricity with spillway blocks.
- The CWPRS, Pune will be consulted for the recommended studies.

- 37** 6.8.27 Undertake hydraulic model studies of the existing spillway energy dissipating device to assess its efficacy to dissipate the energy content of flow by hydraulic jump particularly in the end bays having higher apron levels. If found unsuitable evolve efficient energy dissipating device like flip bucket etc. for end bays, with provision of required height of guide walls separating adjacent bays.
- The CWPRS, Pune/ KERS, KR Sagara will be consulted for the Hydraulic model studies of existing spillway.
- 38** 6.8.28 As described under Para 6.3.2 tail water level for different discharges up to PMF should be determined properly and monitored to prevent submersion of the downstream, structures by providing protective works to the extent required.
- This will be done in consultation with KERS, KR Sagara or with CWPRS, Pune.
- 39** 6.8.29 The performance and efficacy of the existing spillway stilling basin with floors at different levels may be checked by carrying out hydraulic model studies once again in consultation with KERS, KRS and in case the present arrangement of varying floor levels in the stilling basin and apron is not suitable then it is recommended that the model studies with flip bucket for the extreme ten end bays covering gate numbers 1 to 8 on the right bank and gate numbers 32 and 33 on the left bank may be tried and if suitable can be adopted.
- The CWPRS, Pune/ KERS, KR Sagara will be consulted for the Hydraulic model studies of existing spillway stilling basin with floor levels.
- 40** 6.8.30 The divide wall separating the bays 31 and 32 from the adjoining bay should be extended suitably to avoid cross flows and the same may be proposed by model studies.
- This portion Will come under the jurisdiction of O/o the CE, KNNL, ICZ, Munirabad. The work may be taken by the CE, KNNL, ICZ, Munirabad.

- 41 6.8.31 Extent by which to raise the height of divide wall between spillway bays 18 and 19 be determined from model studies and provided accordingly using high strength concrete duly anchored to the supporting masonry below with 20-25 mm steel anchor rods. -do-
- 42 6.8.32 Commence collection of data of leaching of lime from tests of seepage water at least once in a fortnight and determine extent of lime leached from the mortar used in the dam construction periodically to assess loss of strength of mortar and increase in the permeability of existing masonry to help undertake rectification measures. For this purpose, it is necessary to collect data on total quantity of mortar used during dam construction for assessing loss of lime and resulting strength of stone masonry. Previous data is not available, this will be initiated now onwards.
- 43 6.8.33 Reasons for excess uplift pressure registered on the foundation drainage hole a Ch 1039 ft under full reservoir conditions should be investigated and stability analysis verified. Strengthening measures should be initiated if warranted. As per the recommendation, Curtain grouting work is being carried out at ch.1039 ft.
- 44 6.8.34 All the recommendations made by the Dam Safety Review Panel during its inspection in February 1998, in February 2015 and as well as by CWC in their report of February 2000 should be implemented in a time bound manner by drawing up action plan. Will be followed up by preparing action plan.
- 45 7.4.1 The gates and hoists should be operated and maintained in accordance with the standards brought out in **IS 7718-1991** in respect of "Fixed Wheel and Slide Gates". In this connection it is mandatory to also follow the recommended guidelines for Same is following and it will be followed further also.

inspection brought out by the Water Resource Department of Government of Karnataka. In addition, it is also necessary to follow guidance and recommendations contained in the operation and maintenance manuals supplied by the manufacturers of gates and hoists.

46 7.4.2 The operating condition of the gates and hoists should be checked periodically and more often during monsoon months when severe floods are expected to enter the reservoir.

47 7.4.3 Considering the life of hydraulic gates fixed as 45 years by CWC and the life of concrete 100 years to ascertain the balance life, the condition of gate members be got examined by Central Electro Chemical Research Institute (CECRI) Karaikudi-Tamil Nadu.

48 7.4.4 Rubber seal of Gate No. 23 where leakage is occurring may be examined and replaced if necessary to stop leakage.

49 7.4.5 The seal replacement of gates may be provided with 35 dia bulb Teflon cladded seals of "Z' type in place of existing ordinary Z seals for longer life and to achieve zero leakage.

The said procedure is following by TB Board every year before the start of the monsoon season.

As per the recommendations and Board decision the work of "**Ascertaining the condition of spillway Gates of TB Dam and their balance Life**" was entrusted to Central Electro Chemical Research Institute (CECRI) Karaikudi-Tamil Nadu. Accordingly, the CECRI carried out the study with a team of 8 scientists and collected the gate materials for electrochemical analysis in their lab in the month of February -2023, The Project Report was received on 12.09.2023. All the comments and queries of TB Board on the Project Report were communicated to CECRI for clarification and its incorporation in the Report. Final Project Report is awaited from CECRI.

The said rubber seals have been replaced.

It will be adopted while replacing the Rubber seals.

- 50** 7.4.6 The proposal of providing Hydraulic hoist in place of screw hoist for river sluice gates should be examined in detail and provided if feasible. This have been replaced long back now it is operated by Hydraulic hoist only.
- 51** 7.4.7 It is recommended to provide stop log gates (three sets as per norms) to avoid risk in loss of storage in the event of non-functioning of any of the main crest gates. However this may not be possible in the existing piers and may be considered if the CRM piers are being replaced with RCC piers. Noted.
- 52** 7.4.8 It is recommended an extension of more than 300 mm for the gate leaf as described in Para 7.1. may be provided. Project Officers are advised to get wave height calculations done as per **IS: 10635** or other codes and decide the height of plate extension. As per the recommendations and Board decision, the work of "Providing additional skin plate for a height of 300 mm & suitable stiffeners to spillway gates of TB Dam" has been carried out and completed during 2022-23.
- As per the suggestion of DSRP for raising the height of gates beyond 300mm up to 1500mm, the matter was referred to CWC (Member (D&R), Designs & Research wing, New Delhi) along with designs of all Dam components on 08.08.2022 with subsequent reminders, the latest being 05.07.2023. The reply is awaited from CWC.
- 53** 8.6 It was observed that only Plumb Line, two Uplift pressure meters and V Notches are available for observations. No other instruments are in working condition. Some damaged wiring of instruments (CH- 1150 of NOF & CH- 2150 OF) were found in the gallery of the structure. The installation of instruments for the measurement of temperature, strain and stress may not be possible for the existing structure. The Noted.

instruments for movements and pressures (like joint meters, incline meters and uplift pore pressure) are very vital for any Dam structure. Accordingly, the following suggestions and recommendations are given below;

- | | | |
|-----------|---|---|
| 54 | 8.6.1 Water Level gauges at Ch. 2016 ft. The readings of the float type Water Level gauge and the digital water level gauge (radar type) differ by 500 mm, the correction be incorporated.8.6.2 Display of Discharges through Telemetry at Ch-2016 ft is working. However it would be appreciable if the Alarm Settings are incorporated for Danger Levels through SMS or GPRS. | Calibrated and corrected. |
| 55 | 8.6.2 Display of Discharges through Telemetry at Ch-2016 ft is working. However it would be appreciable if the Alarm Settings are incorporated for Danger Levels through SMS or GPRS. | It will be initiated. |
| 56 | 8.6.3 Earthen Dam at Ch 2105 ft to Ch 2257 ft. Measurement of Pressure is recommended and suggested to install one Vibrating Wire Piezometer.8.6.4 Composite Dam at Ch. 2955 ft to Ch. 3428 ft. 2 No's Vibrating Wire Piezometers need to be installed in the Berm (recommended for construction) to monitor the water pressure. It is observed that two pipes are provided on the slopes of the composite dam. These may be used to measure the water column through Echo sounding method. There may be additional open pipes which may surface after cleaning the slopes of the downstream. | Action has been taken to install the recommended instrument and the work is under progress. Action has been taken to install the recommended instrument and the work is under progress. |
| 57 | 8.7.5 Gallery at Ch. 1039: Uplift Pressure meters have not been calibrated since a very long period. | Noted. |
| 58 | 8.7.6 it is recommended to Install 17 No's Uplift pressure meters of Vibrating Wire type throughout the Gallery of the Structure, | Action has been taken to install the recommended instrument and the work is under progress. |

covering Overflow & Non Overflow sections. All the Pore Holes and Drain Holes need to be cleaned.

- | | |
|--|--|
| <p>59 8.7.7 It was observed in the gallery that porous holes and drainage holes from Ch. 110 ft to Ch. 8067 ft. have been maintained well. Whereas, for the gallery section from CH-3067 ft. to CH-5690 ft. these has not been maintained well. It is suggested to maintain uniformity in terms of maintenance for the whole of the gallery</p> | <p>Action has been taken to install the recommended instrument and the work is under progress.</p> |
| <p>60 8.7.7 It was observed in the gallery that porous holes and drainage holes from Ch. 110 ft to Ch. 8067 ft. have been maintained well. Whereas, for the gallery section from CH-3067 ft. to CH-5690 ft. these has not been maintained well. It is suggested to maintain uniformity in terms of maintenance for the whole of the gallery</p> | <p>Noted and it is maintained uniformly.</p> |
| <p>61 8.7.8 It is recommended to set up 3 Nos. of Strong Motion Accelerograph (SMA). The consultancy work towards SMA or Micro-seismic set up can be provided by the EES (Earthquake Engineering Science) Division of CWPRS.</p> | <p>As per the recommendation, action has been taken to install the SMA and the work is under progress.</p> |
| <p>62 The following instruments are recommended for Health Monitoring of the structure.</p> <ol style="list-style-type: none">1) 4 Nos Inclinometers (Vibrating Wire type) may be installed. Two in the gallery and two on the dam top.2) 17 No's Uplift pressure Meters (Vibrating Wire type) may be installed in the Gallery of the Dam.3) Biaxial Joint meters of (Vibrating Wire Type) - Qty 4Nos. may be installed between the joints in both OF and NOF sections4) V-notches (Vibrating Wire types) to be installed adjacent to the existing ones. | <p>Action has been taken to install all the recommended instruments and the work is under progress</p> |

- 5) One no. Data Logger is required to connect the digital output of all the above Vibrating Wire type instruments.
- 6) The existing water level data recorded at CH-2016 may be taken to the data logger for storage and further transmission.
- 7) 6 nos. Piezometers (Vibrating Wire type) are required i.e. two for earthen dam and four for Composite dam.
- 8) Digital Plumb Line (X-Y coordinator) may be

63 9.4.1 Since more than 13 years have passed after the last Survey was carried out in 2008 it is desirable to carryout Hydrographic survey (IBS) of the Reservoir now and periodically thereafter for determination of extent of reservoir sedimentation in dead and live storage portions to assess extent of loss of storage and consequent reduction in the annual benefits to help formulate schemes for minimization of rate of sedimentation such as adoption of watershed management techniques like contour bonding, provision of gully traps, anti-soil erosion measures, etc.

The Topographical survey 2016 Capacity - Elevation table i.e. Reservoir capacity 105.788 TMC at FRL is adopted for the calculation of status of Tungabhadra Reservoir from 22.06.2022 as per the decision of Board in its 218th TB Board meeting and as per the 219th TB Board meeting decision, the CWC, New Delhi was addressed for taking up the Capacity Survey of TB Reservoir. The Director, Remote Sensing Directorate Central Water Commission New Delhi informed that, "Remote Sensing Directorate, CWC has already initiated a study titled 'Sedimentation assessment of forty reservoirs in India using Remote Sensing Techniques'. The ongoing study includes the evaluation of the sedimentation in live storage zone of Tungabhadra Reservoir, which is being conducted by a consultant. Upon completion of the study, we will send you the report for your reference". The report is awaited.

64 10.3.1 The Department should prepare Emergency Action Plan including suitable communication system of flood forewarning to the habitants living downstream of the dam within the zone prohibited for dwelling. For this purpose, the department should prepare necessary inundation map of the downstream valley showing flood contours of different intensities duly demarcating "Prohibited Zone", "Restricted Zone" and "Caution Zone" to avert possible hazards to life and property during release of floods over the spillway.

An Emergency Action Plan is under preparation and it will be submitted shortly. The operation and maintenance manual is under preparation it will be submitted shortly.

65 11.2.1 Operation and maintenance manual of the dam comprising all the elements systematically and comprehensively essential for its operation, inspection, maintenance, instrumentation and monitoring the health of the dam regularly as well as sometimes need based should be prepared

The operation and maintenance manual is under preparation it will be submitted shortly.

ANNEXURES

SALIENT FEATURES OF TUNGABHADRA PROJECT

1. LOCATION

River	Tungabhadra
Village	Mallapuram
Taluk	Hospet
District	Bellary (Present Vijayanagara)
State	Karnataka
Longitude	76° - 20' - 10"
Elatitude	15° - 15' - 19" N

2. RESERVOIR

Catchment area	28177 Sq Km (10880 Sq M)
Gross storage (1953)	3751.17 M Cum (132.471 TMC)
Live Storage (1953)	3718.34 M Cum (131.312 TMC)
Dead storage (1953)	32.83 M Cum (1.159 TMC)
Live storage(2016)	2995.541 M Cum (105.788 TMC)
Gross storage (2016)	2995.541 M Cum (105.788 TMC)
Dead storage (2016)	0
Water spread	378.1 Sq Km
Length of reservoir	80 Km (50 M)
Estimated Annual yield (average)	11,528 M Cum (407.107 TMC)
75% Dependable Annual yield	7263.2 M Cum (256.50 TMC) (336 TMC – upstream abstractions of 79.50 TMC = 256.50 TMC)
Maximum observed flood discharge	10453 Cumecs (369152 cusecs) (Nov 92)
Designed flood discharge	18406 cumecs (650000 cusecs)
Villages affected in (1953)	90 Nos.
Population displaced in (1953)	54,452 Nos.

3. DAM

Length:	
a) Masonry Dam, including Spillway of 2300' (701 m)	1798.28 m (5900')
b) Composite Dam	472.44 m (1550')
c) Earthen Dam	152.40 m (500')
Average height above Foundation level	49.39 m (162')
Average height above river bed	35.37 m (116')
Average height of Composite Dam	21.34 m (70')
Average height of Earthen Dam	9.14 m (30')
Width of roadway on top of Dam	6.71 m (22')
Width of Dam at base	28.5 m (93.5')
Lowest foundation level	+450.50 m (1,478.00')
Sill of spillway crest gate	+491.64 m (1,613.00')
Full reservoir level	+497.74 m (1,633.00')
Maximum Water level	+497.74 m (1633.00')
Top level of dam or road level	+499.88 m (1,640.00')
Number of spillways and size of each	33 Nos. 18.29m x 6.10m(60' x 20')

SALIENT FEATURES OF TUNGABHADRA PROJECT (Contd.)

4. SLUICES

SLUICE (RIGHT SIDE)	Number	Size	Sill level
High level sluices	10	6'x12'	+1585'
24" dia pipe	1	24" dia	+1579'
Raya basava channel	1	6'x12'	+1550'
Hydroelectric turbine pipes	4	11'dia	+1550'
Irrigation & River sluices	2	6'x12'	+1550'
SLUICE (LEFT SIDE)			
Irrigation & Hydro electric Sluice	10	8'9"x11'6"	+1560'
24" diameter	1	24" dia	+1579'
High level sluices	2	4'x5'	+1585'

5. DAM POWER HOUSE - RIGHT SIDE

Head range	11.90 m to 25.90 m (39' to 85')
Number of Power Units	4 numbers 9,000 KW each
Installed capacity	36,000 KW
Energy per day	0.864 MU
Turbines	4 No's vertical Kaplan reaction type
Generators	4 No's of 9,000 KW each

Transformers:

- a) 4 Numbers of 10,600 KVA step up transformers 11/66 KV
- b) 2 Numbers of 1,500 KVA step down transformers 66/11KV
- c) 1 Number 1,000 KVA step down transformer 66/11 KV

6. HAMPI POWER HOUSE

Power canal (Head reach of RBLLC):

- a) Length Km. 20.20 (13 Miles 570 feet)
- b) Capacity 70.79 Cumecs (2,500 cusecs)
- No. of Power units 4 No's 9,000 KW each
- Installed capacity 36,000 KW
- Energy per day 0.480MU
- Approach canal to forebay:
 - a) Length 301.80 m (3 Furlongs)
 - b) Width 13.41 m (44')
 - c) Velocity 1.20 m/Sec (4.01'/second)
 - c) Discharge 70.79 cumecs (2,500 cusecs)
 - d) Full supply depth 3.20 m (10.5')

Forebay:

- e) Total Length 1,557.50 m (5,110')
- f) Composite Dam 378.30 m (1,241')
- g) Earthen Dam with puddle Core 1,100.95 m (3,612')
- h) Earthen Dam with Masonry Core 78.33 m (257')
- I) Maximum height of Dam 24.38 m (80')

SALIENT FEATURES OF TUNGABHADRA PROJECT (Contd.)

Intake structure:	
j) Number of vents	2 No. each 5.49 m x 5.49 m (18' x 18')
k) Sill of pipe	451.72 m (+1,482')
Pipe Line:	
l) Length Low Pressure	797.98 m (2,618')
m) Number of pipes	2
n) Internal diameter	5.49 m (18' - 0") and 12 mm (½") MS shell
o) Maximum discharge	63.71 cumecs (2,250 cusecs)
p) Maximum velocity	2.68 m/sec (8.8 ft per second)
Surge Tank:	
q) Shell	Steel tank of the differential type 18.29 m internal diameter (60')
r) Height	18.29 m (60')
s) Port Holes	6Nos each 1.83m x 1.45m (6'-0"x4'-9")
t) Riser	5.49 m (18')
Penstock Pipes:	
u) Penstock pipes	4 Nos.
v) Penstock length	103.60 m (340')
w) Penstock internal diameter	3.65 m (12'-0') of 12 mm (½") thick MS shell.
x) Penstock maximum discharge	31.90 cumecs (1,128 cusecs)
y) Penstock maximum velocity	About 3.04 m/Sec (10 ft/sec)
z) Gross head - range	31.70 m to 36.30 m (104' to 119')
Tail Race:	
aa) Pond Length	50.60 m (166')
bb) Channel Length	967.50 m (3,174')
cc) Bed width	50' to 120' (15.20 m to 36.60 m)
dd) Discharge - range	(70.70 - 118.90 cumecs) 2,500 - 4,200 cusecs
Turbines	
Generators	4 Nos. vertical Francis reaction type 4 Nos. of 9,000 KW each
Transformers	4 Nos. of 10,600 KVA step-up transformer 11/66 KV 2 Nos. of 20,000 KVA step-up Transformer 66/132 KV.
Transmission lines:	
ee) 66 KV double circuit	lines 20.86 Km (13 Miles) from Dam P.H to Hampi P.H.
ff) 66 KV single circuit lines	67.40 Km (42 Miles) From Dam Power House to Bellary Sub-Station.
Total Power Development:	
gg) Firm	32,000 KWb
hh) Seasonal	58,300 KW

SALIENT FEATURES OF TUNGABHADRA PROJECT (Contd.)

DAM POWER HOUSE - LEFT SIDE

Number of Twin Penstocks, Including one for irrigation	5 sets.
Size of each penstock	3.2m x 4.0m (10'.6" x 13'.2")
Approximate length of each penstock	23.41 m (77')
Maximum tail race level	+ 476.707 m (1,564')
Minimum draw down level	+ 483.108 m (1,585')
Minimum tail race level	+ 474.268 m (1,556')
Maximum capacity of tail race channel	212.37 Cumecs (7,500 Cusecs)
Turbines Installed capacity	4 Nos. Kaplan type vertical 38,000 KW
Generators	02 Nos. 9,000 KW vertical & 02 No. 10,000 KW verticle
Generator transformers	02 Nos.11 KV/110 KV/10,000KVA, 02 Nos 11 KV/110 KV/12,500KVA

Transmission Details

Interconnecting transformers	2 Nos.220 KV/110 KV/100MVA 2 Nos.110 KV/66 KV/20MVA 2 Nos.110KV/33 KV/10MVA 1 Nos.110KV/11 KV/10MVA 1 Nos.33 KV/11 KV/5MVA
Transmission lines	
a) 220kV2 Nos	b) 110kV6 Nos
c) 66kV3 Nos	d) 33kV3 Nos
e) 11kV4 Nos	
Number of Sub-Stations connected	23 Nos.

CONSTITUTION OF TUNGABHADRA BOARD*(Extract of Notification No. DW VI 4 (9) dated 10.3.1955)*

In pursuance of sub-section (4) of section 66 of the Andhra State Act, 1953 (30 of 1953), and in suppression of the Notification of the Government of India in the Ministry of Irrigation and Power dated the 29th September, 1953. The President hereby gives the following directions in regard to the Tungabhadra Project namely:-

1. There shall be established with effect from the 15th March 1955, a Board by the name of the Tungabhadra Board consisting of:

Chairman:

Nominated by the Government of India.

Members:

- I. Representative of the Government of Andhra Pradesh
- ii. Representative of the Government of Karnataka
- iii. Representative of the Government of India

2. The Chairman, if present, shall preside over a meeting of the Board but if the Chairman is absent from any meeting of the Board the Members shall choose one of their members to preside.

3 (i) All matters relating to the project works of common interest to the States of Andhra Pradesh and Karnataka, brought before any meeting of the Board shall be decided by a majority of the Members of the Board present and voting at the meeting before which such matters are brought and the decision of the Board shall be final.

Provided that where with reference to any matter brought before the Board, the

Chairman is satisfied that there is a difference of opinion among the Members on any question of policy or the rights of the States concerned involved in the consideration of such matter, the Chairman shall refer the matter to the Central Government whose decision thereon shall be final.

Explanations:

I. If any Member raises at any meeting of the Board any point as to whether a question is a question of policy or whether any rights of the States concerned are involved in the consideration of a matter before the Board, a decision on the points so raised shall be given by the Chairman.

II. (i) Where any Member dissents from any decision so given by the Chairman, it shall be lawful for the State Government, whose representative that Member is, to represent to the Government of India through the Chairman the matter on which a decision has been given by the Chairman and where this is so done, the Chairman shall refer the matter to the Central Government whose decision thereon shall be final.

(ii) Subject to the provisions of subparagraph (i), the Board may make rules for the conduct of its own business.

(iii) No act or proceedings of the Board shall be invalid merely on the ground of the existence of any vacancy in, or the absence of any member of, the Board.

4. (i) The Board shall take charge of, and deal with, all matters relating to works on, or connected with, the Tungabhadra Project which are common

to both the States of Andhra Pradesh and Karnataka, but nothing in this subparagraph shall be deemed to authorize the Board to deal with any matter in respect of works which relate to only one of the States or in which only one State is interested.

(ii) In particular, and without prejudice to the generality of the foregoing powers, the functions of the Board shall include:

(a) the completion of the construction of the sanctioned Tungabhadra Project;

(b) the regulation of supplies of water and power in accordance with such rules as may be made in this behalf by the Board;

(c) The maintenance of the main canal and of other works common to both the States of Andhra Pradesh and Karnataka.

(d) maintenance of the dam and reservoir of the Project;

(e) the granting of leases of fisheries in the reservoir and in the main canal;

(f) the proper utilization of land acquired for the purposes of the Project; and

(g) any other function incidental to, or connected with, the functions specified in clauses (a) to (f).

5. (i) For the efficient performance of its functions, the Board may appoint a whole-time Secretary and such other officers and servants as it considers necessary.

(ii) During any absence on leave of the Secretary, the Board shall appoint a person to act as Secretary and every person so appointed shall exercise the powers conferred and perform the duties imposed on the Secretary by or under this notification.

(iii) All orders and decisions of the Board shall be authenticated by the signature of the Secretary of the Board.

6. (i) The Government of Andhra Pradesh and Karnataka shall provide at all times the necessary funds for the construction and maintenance of the Tungabhadra Project:

Provided that the liability for the expenditure on the Tungabhadra Project shall be apportioned between the States of Andhra Pradesh and Karnataka in such proportion as may be agreed upon between the two state Governments, and in the absence of any such agreement, in such proportion as may be fixed in this behalf by the Central Government.

(ii) The Governments of Andhra Pradesh and Karnataka shall continue to give the same facilities to the Audit Officer of the Project and other officers engaged in connection with the Project for the payment of moneys into, and withdrawal of the moneys from, the treasuries and sub-treasuries located in their respective territories as were enjoyed by such officers immediately before the commencement of the notification.

7. The Board shall, in relation to the technical sanction, administrative approval, and other sanctions required for the construction and maintenance of the Tungabhadra Project, and in relation to any other administrative matters concerning the Project, exercise the powers of a State Government under the various Codes, Manuals, Rules, and Regulations, specified in the Schedule annexed hereto, as in force in the State of Madras immediately before the 1st day of October, 1953, and any executive

instructions, orders, and directions from time to time issued or made thereunder:

Provided that, in relation to administrative matters concerning the Government servants of the State of Andhra Pradesh employed by the Board in connection with the Project, the corresponding Codes, Manuals, Rules and Regulations as in force in the Mysore State immediately before the said date, shall apply.

8. All contracts to be made in connection with the Tungabhadra Project shall be expressed to be made jointly by, and in the names of, the Governments of Andhra Pradesh and Karnataka and all such contracts shall be executed on behalf of the said Governments by the Secretary of the Board or such other officer as may be authorized by the Board in this behalf but neither the Secretary nor the authorized officer shall be personally liable in respect of anything under such contracts.

9. (i) The staff which immediately before the commencement of this notification was engaged in the construction and maintenance of the Tungabhadra Project shall, after such commencement, continue to be so employed by the Board in connection with the said Project but the Governments of Andhra Pradesh and Karnataka may, if they so think fit, replace any members of the existing staff by other persons in such manner and in such proportion as may be agreed upon between the said State Governments and in the absence of any such agreement as may be determined in this behalf by the Board:

Provided that all correspondence between the State Governments with

respect to such agreements shall be carried on through the Chairman.

(ii) The staff for the time being employed in connection with the Project shall be deemed to be employed under the administrative control of the Board.

10. Plant, machinery, equipment and stores purchased for and in connection with the Tungabhadra Project shall be under the control of the Board and shall be used on the entire Project under the directions of the Board.

11. The Government of Andhra Pradesh and Karnataka may depute such persons as they may nominate or designate either generally or specially to inspect the works on or connected with the Tungabhadra Project which are common to both the States of Andhra Pradesh and Karnataka.

SCHEDULE

(See paragraph 7)

1. Madras Public Works Account Code with Appendices.
2. Madras Public Works Department Code.
3. Madras Detailed Standard Specifications.
4. Madras Account Code.
5. Madras Electricity Manual.
6. Madras Financial Code.
7. Madras Treasury Code.
8. Madras Budget Manual.
9. Fundamental Rules and Subsidiary Rules of the Madras Government.
10. Madras Manual of Special Pay and Allowances.
11. Madras Pension Code.
12. General Provident Fund (Madras) Rules.
13. Contributory Provident Fund (Madras) Rules.

14. Madras Contributory Provident Fund-Pension Insurance Rules, 1950.
15. Madras Security Rules 1937.
16. Madras Services Manual.
17. Madras Commercial Taxes Manual, Volume I to III.
18. Madras Port Manual.
19. Madras Stationery Manual.

Sd/- S. VENKATARAMAN, Dy. Secy.

Extract of Ministry of Water Resources Order, New Delhi, (F. No. 15/1/2014-E. IV), the 28th May, 2014.

In pursuance of sub-section (1) of section 91 of the Andhra Pradesh Reorganization Act, 2014(6 of 2014), the Central Government hereby makes the following further amendments in the notification of the Government of India in the erstwhile Ministry of Irrigation and Power notification No. D.W.VI-4(9), dated the 10th March, 1955 relating to composition of Tungabhadra Board, namely: -

2. In the said notification: -

(I) in paragraph 1, for the heading "Members" and the entries relating there to, the following heading and entries shall be substituted, namely:-

"Members

(2) Engineer-in-Chief (Irrigation), Government of Andhra Pradesh;

3) Engineer-in-Chief (Irrigation), Government of Telangana;

(4) Secretary, Water Resources Department, Government of Karnataka;

(5) Financial Advisor and Joint Secretary, Ministry of Water Resources, Government of India".

(ii) for the word "Andhra" wherever it occurs, the words "Andhra Pradesh and Telangana" shall be substituted.

3. This order shall come into force from the appointed day notified under the Andhra Pradesh Reorganization Act, 2014 (6 of 2014).

Sd/- AJAY KUMAR, Under Secy.

**EXTRACT OF FINAL AWARD OF KRISHNA WATER DISPUTE TRIBUNAL
(CLAUSE IX AND CLAUSE XVI)**

Clause IX

(A) Out of the water allocated to it, the State of Maharashtra shall not use in any water year

(I) More than 7 TMC from the Ghata-prabha (K-3) sub-basin.

(ii) More than the quantity of water specified hereunder from the main stream of the river Bhima. As from the water year commencing on the 1st June next after the date of the publication of the decision of the Tribunal in the Official Gazette up to the water year 1989-90: 90 TMC.

(b) As from the water year 1990-91: 95 TMC.

(B) Out of the water allocated to it the State of Karnataka shall not use in any water year

(I) more than the quantity of water specified here under from the Tungabhadra (K-8) sub-basin.

(a) As from the water year commencing on the 1st June next after the date of the publication of the decision of the Tribunal in the Official Gazette up to the water year 1982-83: 295 TMC.

(b) As from the water year 1983-84 up to the water year 1989-90: 295 TMC plus a quantity of water equivalent of 7½ % of the excess of the average of the annual utilizations for irrigation in the Krishna River basin during the water years 1975-76, 1976-77 and 1977-78 from its own projects using 3 TMC or more annually over the utilizations for such irrigation in the water year 1968-69 from such projects.

(c) as from the water year 1990-91 up to the water year 1997-98:

295 TMC plus a quantity of water equivalent to 7½ % of the excess of the average of the annual utilizations for irrigation in the Krishna River basin during the water years 1982-83, 1983-84 and 1984-85 from its own projects using 3 TMC or more annually over the utilizations for such irrigation in the water year 1968-69 from such projects.

(d) as from the water year 1998-99 onwards: 296 TMC plus a quantity of water equivalent to 7½ % of the excess of the average of the annual utilizations for irrigation in the Krishna River basin during the water years 1990-91, 1991-92 and 1992-93 from its own projects using 3 TMC or more annually over the utilizations for such irrigation in the water year 1968-69 from such projects.

For the limited purpose of this sub-clause, it is declared that the utilizations for irrigation in the Krishna River basin in the water year 1968-69 from projects of the State of Karnataka using 3 TMC or more annually shall be taken to be 176.05 TMC.

Annual utilizations for irrigation in the Krishna River basin in each water year after this Order comes into operation from the projects of the State of Karnataka using 3 TMC or

more annually shall be computed on the basis of the records prepared and maintained by the State under Clause XIII.

Evaporation losses from reservoirs of projects using 3 TMC or more annually shall be excluded in computing the 7½ % figure of the average annual utilizations mentioned above.

- (i) more than 42 TMC from the Vedavathi (K-9) sub-basin, and
 - (ii) more than 15 TMC from the main stream of the river Bhima.
- © Out of the water allocated to it, the State of Andhra Pradesh shall not use in any water year:
- (i) more than 127.5 TMC from the Tungabhadra (K-8) sub-basin and more than 12.5 TMC from the Vedavathi (K-9) sub-basin.
 - (ii) More than 6 TMC from the catchment of the river Kagna in the State of Andhra Pradesh.
- (D)(I) The uses mentioned in sub Clauses (A), (B) and (C) aforesaid include evaporation losses. (ii) The use mentioned in sub-clause (C) (i) does not include use of the water flowing from the Tungabhadra into the river Krishna.
- (E) (1) The following directions shall be observed for use of the water available for utilization in the Tungabhadra Dam in a water year
- (a) The water available for utilization in a water year in the Tungabhadra Dam shall be so utilized that the demands of water for the following projects to the extent mentioned below may be met :

i)Tungabhadra Right Bank Low Level Canal	52.00 TMC
Water available for Tungabhadra Right Bank Low Level Canal shall be shared by the States of Karnataka and Andhra Pradesh in the following proportion:	
State of Karnataka	: 22.50
State of Andhra Pradesh	: 29.50
(ii)Tungabhadra Right Bank High Level Canal-Stage I & II:	50.00 TMC
Water available for Tungabhadra Right Bank High Level Canal shall be shared by the States of Karnataka and Andhra Pradesh in the following proportions.	
State of Karnataka	: 17.50
State of Andhra Pradesh	: 32.50
(iii) Tungabhadra Left Bank Low Level and High Level canals	102.00 TMC
(iv) Raya and Basavanna Channels of the State of Karnataka	7.00 TMC
(v)Assistance by way of regulated discharges to Vijayanagar Channels other than Raya and Basavanna Channels of the State of Karnataka.	2.00 TMC
(vi) Assistance by way of regulated discharges to the Rajolibunda Diversion Scheme for use by the States of Karnataka and Andhra Pradesh in the proportion mentioned in Clause XI.	7.00 TMC
(vii) Assistance by way of regulated discharges to the Kurnool-Cuddapah Canal of the States of Andhra Pradesh.	10.00 TMC
	230.00 TMC

The utilizations of the Projects mentioned in Sub-Clauses (a) (i) (ii) and (iii) above include the evaporation losses in the Tungabhadra Dam, which will be shared in accordance with Clause XI (D).

(b) If, in any water year, water available for utilization in the Tungabhadra Dam is less than the total quantity of water required for all the Projects as mentioned above, the deficiency shall be shared by all the Projects proportionately. The proportions shall be worked out after excluding the evaporation losses.

(C) If, in any water year, available for utilization is more than the total quantity of water required for all the projects as mentioned above, the requirements for all the Projects for the month of June in the succeeding water year as estimated by the Tungabhadra Board or any authority established in its place shall be kept in reserve and the State of Karnataka shall have the right to utilize the remaining water in excess of such reserve in the Tungabhadra Dam for its Projects mentioned in Sub-Clauses (a)(i),(ii) and (iii) above drawing water from that dam even though thereby it may cross in any water year the limit on the utilization of water from Tungabhadra (K-8) sub-basin placed under Clause IX(B) of the Final Order but in no case such utilization shall exceed 320 TMC.

(d) The balance water, if any, shall be kept stored in the dam for use in the next year.

(2) The working tables for the utilization of the water in the Tungabhadra Dam shall be prepared as hitherto fore by the Tungabhadra Board or any other authority established in its place so as to enable the States of Karnataka and Andhra Pradesh to utilize the water available for utilization in the Tungabhadra Dam as aforesaid.

(3) If, in any water year either of the two States of Karnataka and Andhra Pradesh finds it expedient to divert the water available to it in the Tungabhadra Dam for any one of its Projects to any other of its Project or Projects mentioned above for use therein, it may give notice thereof to the Tungabhadra Board or any other authority established in its place and the said Board or authority may, if it is

feasible to do so, prepare or modify the working table accordingly.

(4) The States of Karnataka and Andhra Pradesh may use the water available in the Tungabhadra Dam in accordance with the aforesaid provisions and nothing contained in Clause V shall be construed as overriding the provisions of Clause IX (E) in the matter of utilization of the water available in the Tungabhadra Dam nor shall anything contained in Clause IX (E) be construed as enlarging the total allocation to the State of Karnataka or as enlarging the limit of acquisition of any right by the State of Andhra Pradesh in the waters of the river Krishna.

5) The States of Karnataka and Andhra Pradesh may by agreement without reference to the State of Maharashtra alter or modify any of the provisions for the utilization of the water available in the Tungabhadra Dam mentioned above in any manner.

Clause XVI

In this Order


(a) Use of the water of the river Krishna by any person or entity of any nature whatsoever within the territories of a State shall be reckoned as used by that State.

(b) The expression 'Water Year' shall mean the year commencing on 1st June and ending on 31st May.


(c) The expression 'Krishna River' includes the main stream of the Krishna River, all its tributaries and all other streams contributing water directly or indirectly to the Krishna River.

(d) The expression 'TMC' means Thousand million cubic feet of water.

ORGANIZATION CHART OF TUNGABHADRA BOARD



DETAILED ORGANIZATION CHART OF TUNGABHADRA BOARD



BOARD IN ITS 213TH MEETING HELD ON 27.12.2018 AT HYDERABAD REVIEWED THE GROUND RENT AS BELOW.

Annexure: 2.5

Category	DESCRIPTION	Ground rent per 100 Sqft per Annum				
		Enhanced during 2007 (implemented)	Enhanced during 2015 (Not implemented)	Reviewed the enhancement of 2015 (After Agitation from Tungabhadra Horata Kriya Samithi) and implemented from 01.01.2019	3	4
1	2					
1	Vacant land or with huts	Rs.40	Rs.900	Rs.200		
2	Huts replaced with temporary construction residential use.	Rs.50	Rs.900	Rs.300		
3	Huts replaced with permanent construction residential use (violation)	Rs.70	Rs.900	Rs.900		
4	Huts replaced with temporary construction partly commercial and residential	Rs.70	Rs.900	Rs.900		
5	D & O Traders and huts replaced with permanent construction partly commercial and residential (violation)	Rs.100	Rs.900	Rs.900		
6	Worship Places 1) Less than 5000 sq. ft 2) Above 5000 sq. ft	Rs.500 Rs.1000 (Per annum)	Rs.500 Rs.1000 (Per annum)	Exempted as per Municipal Act		

I. TARIFF RATES VAIKUNTA GUEST HOUSE & ANNEXURE:

SI No	Category	Rate for Govt Officers/Officials per day						Non Govt Officials	
		On Govt Duty			On Private Visits			Existing (Rs.)	Enhanced (Rs.)
		Existing (Rs.)	Enhanced (Rs.)	Existing (Rs.)	Enhanced (Rs.)	Existing (Rs.)	Enhanced (Rs.)		
VAIKUNTA GUEST HOUSE									
1	Room No.1 (VIP)	600	700	750	1500	-	-	-	-
2	Room No.2	500	600	600	1200	1500	3000		
3	Room No.3,4,5 & 6	500	600	600	1200	1200	2500		
ANNEXURE									
1	Room No. 1 & 2 (VIP)	600	700	750	1500	-	4000		
2	Room No. 3,4,5 & 6	500	600	600	1200	1200	2500		

I. INSPECTION BUNGALOW AT TB DAM

SI No	Category	Rate for Govt Officers/Officials per day						Non Govt Officials	
		On Govt Duty			On Private Visits			Existing (Rs.)	Enhanced (Rs.)
		Existing (Rs.)	Enhanced (Rs.)	Existing (Rs.)	Enhanced (Rs.)	Existing (Rs.)	Enhanced (Rs.)		
1	Rooms	350	450	500	1000	600	1500		

**TRANSFER AND POSTING OF OFFICERS TO AND FROM THE BOARD DURING
2022-23**

SL No	Name (Shri/Smt)	Date of Joining	Date of Relief from the Board
	Irrigation Branch		
1	Shri Prasannakumar H, SDO	01.07.2022 FN	
2	Kum Chaitra H Gadad,SO	29.07.2022 FN	
3	Shri Moorugudi Kenchappa, SO	29.07.2022 FN	
4	Shri Maheswarreddy B P, SO	29.07.2022 FN	
5	Shri Vijaya Kumara R, SO	29.07.2022 FN	
6	Shri Anand, SO	29.07.2022 FN	02.06.2023 AN
7	Shri Kiran G, SO	09.09.2022 FN	
8	Smt Lata Hiremath, SO		30.09.2022 AN
9	Shri M.Madhusudhan Rao, SO	01.10.2022 FN	
10	Shri B.Sreekanth Kumar Naik, SO	01.10.2022 FN	
11	Shri L.Durga Vara Prasad, SO	01.10.2022 FN	
12	Shri E.Raja Sekhara Reddy,AS	06.10.2022 FN	
13	Shri M.Neelakanta Reddy,EE	19.10.2022 FN	
14	Shri B.Ajjaiah, SO		30.11.2022 AN
15	Shri Jagadish Parimi,SDO		02.02.2023 AN
16	Shri T.Ravi, SO		04.02.2023 AN
17	Shri Vishwanatha, SO		28.02.2023 AN
18	Shri V Gopi, SDO	14.03.2023 FN	
19	Smt P.Usha Rani,SDO		15.03.2023 AN
20	Shri A Nagaraja Rao, SDO	16.03.2023 FN	
21	Shri P.Navajeevan Reddy,SO	17.03.2023 FN	
22	Shri Shivaputra Shambhu,SOG	17.03.2023 FN	
23	Kum Pooja H, SO	20.03.2023 FN	
24	Shri P.Devendran,SO	31.03.2023 FN	
25	Shri. Rahul,SO		31.03.2023 AN
26	Shri. Suneel Kumar, SO	16.05.2023 FN	
27	Kum.Durga Shravani C, SO	22.05.2023 FN	
28	Shri P.Devendrappa.SDO		31.05.2023 AN

	TBHES		
1	Shri S.Naresh,AEE (APGENCO)		24.06.2022 AN
2	Shri S Wasim Basha, AEE (APGENCO)	02.07.2022 FN	
3	Shri E Linganna Gowd, AEE (APGENCO)	18.07.2022 FN	
4	Shri A Tirupati Rao, EE (APGENCO)	02.09.2022 FN	
5	Shri P Guru Nagendra, AEE, (APGENCO)		08.09.2022 AN
6	Shri B Venu Gopal, DEE (APGENCO)	20.09.2022 FN	
7	Shri N Venu Gopal, DEE (APGENCO)		24.09.2022 AN
8	Smt Shilpa G, AE (KPTCL)	18.10.2022 AN	
9	Vijay Kumar, JE (KPTCL)	07.12.2022 FN	
10	Shri S.H. Nagappa, SE, TBHES		14.12.2022 AN
11	Shri S Rushabendrappa, SE, TBHES	15.12.2022 FN	

IRRIGATION BENEFITS OF TUNGABHADRA PROJECT

SI No	Canal System	Irrigation benefits (in acres)		
		Karnataka	Andhra Pradesh	Total
1	2	3	4	5
1	Right Bank Low Level Canal (RBLLC)	92,670	1,57,062	2,49,732
2	Right Bank High Level Canal (RBHLC)	1,99,920	*2,84,992	4,84,912
3	Left Bank Main Canal (LBMC)	6,02,706	-	6,02,706
4	Left Bank High Level Canal (LBHLC)	1,160	-	1,160
	Total	8,96,456	4,42,054	13,38,510
5	EXISTING AREA BENEFITED Raya & Basavanna Channels (RBC) Vijayanagar Channels other than RBC	7,468	-	7,468
6	Rajolibunda Diversion Scheme (RDS)	17,000	-	17,000
7	Kurnool – Cuddapah Canal System	5,900	**87,000	92,900
8		-	2,78,000	2,78,000
	Total	30,368	3,65,000	3,95,368


* Reference - Annexure 3.15

** Command falling under Telangana

Details of RDS Anicut and Sunkesula Anicut

Sl. No.	Description	Rajolibunda Diversion Scheme	Sunkesula Anicut (KC Canal)
1	Length of Anicut	819.90 m (2690 ft)	1328.30 m (4358 ft)
2	Catchment area	53,634 sq km (20719 sq miles)	64,083 sq km (24,985 sq miles)
3	Crest level	Plus 332.20 m (1090 ft)	Plus 288.650 m (947.06 ft)
4	Maximum Design Flood discharge	21,237 Cum (7,50,000 cusecs)	14,864 cum (5,25,000 cusecs)
5	Year of completion	1958	1870

ORGANIZATION CHART OF IRRIGATION WING



AHO : Assistant Horticultural Officer
 DL : Dam Line
 AP : Govt. of Andhra Pradesh
 GS : Garden Section
 HW : Head Works
 GoK : Govt. of Karnataka
 SDO: Sub-Divisional Officer
 HLC: High Level Canal
 PC : Power Canal
 SO : Section Officer
 T : Township
 SS : Service Section
 ST & QC: Soil Testing & Quality Control
 E&HW : Estate & Head Works
 SG : Superintendent Of Gardens

STATEMENT SHOWING THE HYDRAULIC DETAILS OF AYACUT AND DISTRIBUTARIES OF COMMON DISTRIBUTARIES OF RIGHT BANK LOW LEVEL CANAL.

Sl. No	Name of Sluices	Location	Length in Km	Scheduled discharge (C/s)						Ayacut in Acres.					
				Khariff			Rabi			Khariff			Rabi		
				K.A	A.P	Total	K.A	A.P	Total	K.A	A.P	Total	K.A	A.P	Total
1	2	3		4	5	6	7	8	9	10	11	12	13	14	15
1	DP No 37A	131.810	3.20	-	-	-	0.47	1.20	1.67	--	--	--	76.00	143.00	219.00
2	DP No 44	154.000	1.64	-	1.00	1.00	2.75	2.70	5.45	85.00	63.00	148.00	104.00	213.00	317.00
3	DP No 45	154.837	0.70	-	4.00	4.00	0.80	4.00	4.80	15.00	271.00	286.00	76.00	774.00	850.00
4	DP No 60	191.540	1.00	-	1.00	1.00	1.00	--	1.00	--	58.00	58.00	160.00	--	160.00
5	**Kotehal Distributory	193.820	2.50	24.14	-	24.14	24.00	--	24.00	1207.00	--	1207.00	3842.00	--	3842.00
6	DP No 62	196.700	3.80	-	2.50	2.5	0.27	2.50	2.77	--	157.00	157.00	43.66	413.00	456.66
7	Hatcholli Distributory	205.267	10.80	53.66	2.50	56.16	52.90	5.20	58.10	2682.36	171.00	2853.36	8442.88	684.00	9126.88
8	DP No 65	206.980	21.00	4.93	5.00	9.93	6.40	4.50	10.90	241.51	215.00	456.51	1024.46	558.00	1582.46
9	DP No 72	240.388	7.50	-	6.00	6.00	2.05	4.00	6.05	--	359.00	359.00	328.54	560.00	888.54
10	DP No 73	247.972	3.00	1.89	4.00	5.89	6.49	--	6.49	94.53	237.00	331.53	1041.88	--	1041.88
11	T.S. Distributory	250.530	17.80	27.69	22.00	49.69	35.15	16.50	51.65	1378.92	1298.00	2676.92	5605.51	2330.00	7935.51
	TOTAL		72.94	112.31	48.00	160.31	132.28	40.60	172.88	5704.32	2829.00	8533.32	20744.93	5675.00	26419.93

Note: ** The Kotehal Distributory is a common distributory, but it serves ayacut in Karnataka state only.

Annexure: 3.4

DRINKING WATER SCHEMES APPROVED BY BOARD				
Sl.No.	Description	Location	Rate of drawal in Cusecs	Quantum of Water in TMC
1	2	3	4	5
I	<u>TB RESERVOIR</u>			
	1. Water supply to the filter house for drinking to Right Bank official colony through 24" pipe from TBR	Chainage 590 of Dam	1.08	0.034
	2. Water supply to the filter house for drinking to Left Bank colonies through 24" pipe from TBR	Chainage 5700 of Dam	1.08	0.034
	3. Water supply to H.B.Halli, Kudligi, and Kottrur Town	Right side TBR	9.38	0.296
	4. Water supply to Koppal City	Left side TBR	10.50	0.330
	5. Water supply to Upananyakanahalli and other 20 villages Drinking Scheme	Right side TBR	8.73	0.138
	6. Water supply to Basarakodu & other 27 villages & sonna and other 22 villages Drinking Scheme	Right side TBR	2.5	0.041
	7. Water supply to Ankli & other 8 villages and kombli & other 10 villages Drinking Scheme	Right side TBR	1.44	0.023
	8. Kottinakal Drinking scheme	Right side TBR	1.44	0.015
	Total from Reservoir:		36.15	0.911
II	<u>POWER CANAL</u>			
	1. Water supply to Hospet Town	Km 5.334 (right side)	1.70	0.040
	2. Water Supply to P.K. Halli Village	Km 18.870 (right side)	4.00	0.093
	3. Water supply to A.B Vajpayee zoological park, Kamalapura	Km 18.900 (right side)	2.50	0.058
	4. Water supply to Hampi University	Km 19.000 (right side)	2.50	0.058
	5. Water supply to Kamalapur Town	Km 20.360 (left side)	4.00	0.093
	Total from Power Canal:		14.70	0.343
III	<u>RIGHT BANK LOW LEVEL CANAL</u>			
	1. Water supply to Pompa Vidya Peetha	Km 7.946	0.50	0.010
	2. Water Supply to KereKere and Kallukamba	Km 48.300	1.50	0.031
	3. Water Supply to Basavapura	Km 56.800	2.50	0.052
	4. Water Supply to Kurugodu Town	Km 58.600	7.50	0.156
	5. Water Supply to Karur Village & other	Km 70.645	2.00	0.042
	6. Water Supply to Sanavaspura and other villages	Km 76.700	3.00	0.062

	7. Water Supply to Sindhigeri and other villages	Km	83.800	20.00	0.415
	8. Water Supply to Korlagundi and other Villages	Km	99.200	3.00	0.062
	9. Water supply to Vanenur and other villages	Km	105.835	1.50	0.031
	10. Water Supply to Masidipur and other Villages	Km	107.070	1.60	0.033
	11. Water Supply to Gotur and other Villages	Km	110.698	1.50	0.031
	12. Water Supply to Moka and other Villages	Km	113.250	1.50	0.031
	13. Water supply to Bellary city	Km	115.800	58.00	1.200
	14. Water Supply to Byalachinta and other villages	Km	128.875	2.00	0.041
	15. Water supply to Chintakunta, Ramadurgam and other villages	Km	134.800	5.00	0.104
	16. Water supply to Jalihal village	Km	136.850	0.50	0.010
	17. Water supply to Bommanahal village	Km	139.700	0.26	0.005
	18. Water supply to M. Gonehal village	Km	143.500	0.26	0.005
	19. Water supply to Yerragudi village	Km	146.700	2.70	0.057
	20. Water supply to Bapuram village	Km	158.000	20.00	0.415
	21. Water supply to Virupapuram village	Km	167.800	2.00	0.041
	22. Water supply to Sammatageri tank for drinking water to 6 villages under CPWS scheme.	Km	176.100	1.50	0.032
	23. Water supply to Holagunda village	Km	191.600	10.30	0.214
	24. Water supply to Gajjahalli village	Km	197.100	0.26	0.005
	25. Water supply to Vandavagili village	Km	203.800	0.26	0.005
	25. Water supply to Saranala M.I. tank	Km	210.940	5.00	0.104
	26. Water supply to Hebbatam village	Km	218.400	3.00	0.062
	27. Water supply to Naganathahalli village	Km	231.000	10.60	0.220
	28. Water supply to Basapuram village	Km	233.100	3.50	0.070
	29. Water supply to Adoni Town	Km	235.600	58.00	1.202
	30. Water supply to Chinnaharivanam village	Km	239.700	1.50	0.030
	31. Water supply to madiri village	Km	242.200	1.00	0.021
	32. Water supply to Hanawal village	Km	249.000	1.50	0.031
	Total from RBLLC:			233.24	4.830
IV	<u>RIGHT BANK HIGH LEVEL CANAL</u>				
	1. Water supply to Sandur Town	Km	46.750 (DP 2A)	9.00	0.14
	2. Water supply - Release of water for Bellary city for drinking purpose.	Km	82.260	53.06	0.825
	Total from RBHLC:			62.06	0.965
	Grand TOTAL (I+II+III+IV):			346.15	7.049

INDUSTRIAL WATER USERS APPROVED BY BOARD

Sl.No.	Name of the Scheme	Source	Qty per Day in		Remarks
			Cusecs	MGD/TMC	
A	From Left Bank of TB Reservoir				
	i) M/s Kirloskar Ferrous and iron Ltd.(KFIL)	Left bank of T.B Reservoir	3.71	2.00/0.117	
	ii) M/s Kalyani Steels Ltd.	-do-	9.29	5.00/0.293	
	iii) M/s HRG allies and steels Limited, Kasanakidi	-do-	0.73	0.39/0.023	
B	From Power Canal				
	i) M/s Jindal Vijayanagar Steel Ltd.	Power canal (ROFS)	55.3	29.76/1.29	
C	From Right Bank of TB Reservoir				
	i) M/s BMM Ispat Ltd, Danapur.	Right Bank of TB Reservoir	8.20	4.41/0.258	
	ii) M/s SLR Metalics Pvt Ltd.	-do-	8.21	4.42/0.259	
D	Raya Basavanna channel				
	i) M/s Sandur Manganese and Iron Ore Ltd	Raya Basavanna channel	6.20	3.34/0.196	
E	RBHLC				Temporary Approval given for BTPS during Drought years i.e., for 2016-17, 2017-18 & 2018-19 only
	i) Bellary Thermal Power Station	RBHLC KM 57/800	58.00	31.21/0.90	
F	RBLLC				
	i) Bellary Thermal Power Station	RBLLC KM 18/500	60.00	32.29/1.24	

**STATEMENT SHOWING THE CANALWISE DRAWALS OF WATER AGAINST PRO-RATA ENTITLEMENT
FOR THE WATER YEAR 2022-23
(INCLUDING CANAL TRANSMISSION LOSSES)**

Sl. No.	Name of the Canal System	Allocation based on KWDT Award	Actual drawals during the period from 01/06/2022 to 31/05/2023	Pro-rata entitlement on KWDT award out of 188.000 TMC	Excess(-) / Less(+) drawals against pro-rata entitlement out of 188.000 TMC (Col. 5-4)	
					4	5
1	2	3	4	5	6	
	<u>KARNATAKA STATE</u>					
1)	Right Bank Power Canal + Low Level Canal.	19.000	15.386	16.026	0.640	
2)	Right Bank High Level Canal	17.500	16.523	14.760	-1.763	
3)	Raya Basavanna Channel	7.000	4.996	5.904	0.908	
4)	River Releases (VNC+RDS)	2.490	1.442	2.100	0.658	
5)	Left Bank Main Canal + H.L.C. (L.B.)	93.000	82.331	78.442	-3.889	
6)	Debit for lift Irrigation Schemes	0.000	4.123	4.123	0.000	
7)	Debit for drawls by JVSL	0.000	0.886	1.900	1.014	
8)	Bhadra Assistance				1.042	
	Sub-Total:	138.990	125.687	123.255	-1.390	
	<u>ANDHRA PRADESH</u>					
1)	Right Bank Low Level Canal	24.000	19.283	21.283	2.000	
2)	Right Bank High Level Canal	32.500	32.821	28.821	-4.000	
3)	River Releases for KC Canal	10.000	6.868	8.868	2.000	
	Sub Total:	66.500	58.972	58.972	0.000	
	<u>TELANGANA</u>					
1)	River Releases for RDS	6.510	5.773	5.773	0.000	
	Sub Total:	6.510	5.773	5.773	0.000	
	Grand Total:	212.000	190.432	188.000	-1.390	

(All figures are in TMC.)

NOTES:

- The drawals in the canals are inclusive of prorata transmission losses.
- The debit of 4.123 TMC is accounted i.e towards drawals of Irrigation schemes is 2.330 TMC, 0.843 TMC is for Drinking schemes & 0.950 TMC is for industries situated on the periphery of the reservoir as per the decision taken in the 218th meeting of the Board held on 26th May 2022 through Video Conference.
- The debit of 1.900TMC. is towards drawals for M/s JVSL. as per the decision taken in the 162nd & 187th meeting of the Board & Secretary, TB Board, TB Dam approved letter No.1249/SO(V)/2022-23/667 Date:22.06.2022.

TUNGABHADRA RESERVOIR WATER ACCOUNT FOR THE YEAR 2022-23

YIELD		TMC
i	Opening balance as on 01/06/2022 (as per Capacity Table of 2008 surveys) (* from 22.06.2022, 2016 Topographical Survey Capacity table has been adopted)	37.634
ii	Inflows recorded at TB.Dam considering 4.123TMC of water debited towards drawals by Karnataka State for Lift Irrigation Schemes on the periphery of Tungabhadra Reservoir for the water year 2022-23 and also 2.000 TMC of water released from Bhadra Reservoir and realisation considered at TB Reservoir as 1.042TMC	610.182
Total		647.816
<u>UTILISATION</u>		
a)	Drawals for Irrigation by three States during the water year 2022-23.	190.432
b)	Spillway surplus	404.269
c)	Drawals for extra power generation during surplussing period without jeopardizing Irrigation interests	35.374
d)	System losses	4.553
e)	Reservoir evaporation losses.	8.469
f)	Closing balance i.e. residual storage as on 31/05/2023	4.719
Total		647.816
<u>WATER YEAR 2022-23</u>		
1	Actual quantum of water drawn by three States. during the water year 2022-23.	190.432
2	Actual Reservoir evaporation losses to be shared by both the states.	8.469
Total		198.901

UTILIZATION OF WATER DURING THE YEARS FROM 1978-79 TO 2022-23

(in Tmctf)

Water Year	Inflow (June-May)	Total Utilisation (including evaporation)	Drawals for Irrigation				Drawals for Extra Power Gen.	Water let Out over Spillway	Total River outflow	Reservoir evaporation losses	System losses	Remarks
			Karnataka	Andhra Pradesh	Telegana	Total						
1	2	3	4	5	6	7	8	9	10	11	12	13
1978-79	558.775	216.916	134.483	66.391	-	200.874	47.093	300.809	347.902	15.637	-	do
1979-80	291.341	218.758	131.895	70.788	-	202.683	26.415	43.570	69.985	15.705	-	do
1980-81	553.100	231.383	140.367	76.279	-	216.646	42.194	292.187	334.381	14.711	-	do
1981-82	362.649	208.680	128.463	66.159	-	194.622	32.859	126.145	159.004	12.824	-	do
1982-83	369.482	216.660	132.363	72.205	-	204.568	22.726	130.462	153.188	12.062	-	Capacities are as per 1978 surveys
1983-84	316.253	206.149	125.182	68.412	-	193.594	25.373	82.426	107.799	12.422	-	Capacities are as per 1981 surveys
1984-85	303.183	200.562	122.098	63.570	-	185.668	40.485	66.000	106.485	12.446	-	do
1985-86	217.267	192.833	119.026	61.570	-	180.596	10.723	14.329	25.052	11.302	-	do
1986-87	243.331	207.841	128.359	67.228	-	195.587	8.261	27.041	35.302	12.163	-	do
1987-88	163.482	162.491	99.919	52.495	-	152.414	-	-	-	9.006	-	do
1988-89	248.134	178.113	109.565	55.373	-	164.938	23.876	52.180	76.056	11.045	-	do
1989-90	222.061	188.216	112.701	60.205	-	172.906	12.633	18.052	30.685	12.465	3.008	do
1990-91	314.036	191.300	115.183	60.599	-	175.782	17.473	102.163	119.636	12.518	3.000	do
1991-92	364.912	195.314	119.798	60.344	-	180.142	24.855	159.282	184.137	13.105	2.068	do
1992-93(*)	519.609	215.702	129.415	68.381	-	197.796	36.636	267.915	304.551	14.190	3.716	do
1993-94	307.868	206.305	127.795	64.717	-	192.512	15.811	90.141	105.952	9.700	4.093	do
1994-95	538.598	190.504	121.451	54.463	-	175.914	39.403	311.414	350.817	10.330	4.260	do
1995-96	176.307	179.767	110.532	56.575	-	167.107	0.434	-	0.434	9.232	3.428	Capacities are as per 1993 surveys
1996-97	211.524	166.394	101.508	54.899	-	156.407	12.960	28.704	41.664	9.987	2.830	do
1997-98	339.815	174.373	114.321	60.052	-	174.373	18.839	130.887	149.726	10.688	4.171	do
1998-99	323.181	191.742	117.320	62.382	-	179.902	35.485	85.597	121.082	11.84	4.911	do
1999-2000	328.877	194.356	121.167	61.301	-	182.468	22.341	114.93	137.271	11.888	4.117	do
2000-01	322.254	184.832	117.378	56.978	-	174.356	35.495	96.642	132.137	10.476	5.489	do
2001-02	160.082	156.751	98.694	49.474	-	148.168	-	-	-	8.683	4.715	do
2002-03	126.371	122.660	75.909	39.766	-	115.675	-	-	-	6.985	3.581	do
2003-04	117.095	112.142	69.905	36.232	-	106.137	-	-	-	6.005	4.156	do
2004-05	171.145	136.353	84.560	43.571	-	128.131	6.768	23.1	29.868	8.22	4.846	do
2005-06	316.786	160.799	99.918	51.583	-	151.501	30.435	119.411	149.846	9.298	5.294	do
2006-07	296.274	160.694	101.463	49.354	-	150.817	18.978	110.916	129.894	9.877	5.369	do
2007-08	476.018	166.231	104.149	52.025	-	156.174	41.706	252.121	293.827	10.057	5.393	do
2008-09	278.719	165.363	103.940	53.341	-	157.281	20.313	98.214	118.527	8.082	4.506	do
2009-10	366.598	164.383	102.098	53.432	-	155.530	27.819	169.983	197.802	8.853	4.329	do
2010-11	339.651	184.133	113.659	61.91	-	175.569	27.823	121.416	149.239	8.564	5.020	do
2011-12	292.089	161.373	100.615	52.232	-	152.847	26.679	99.605	126.284	8.526	4.618	Capacities are as per 2008 surveys
2012-13	153.252	131.180	81.616	42.094	-	123.710	5.769	13.948	19.717	7.47	5.817	do
2013-14	394.225	145.100	91.121	46.454	-	137.575	26.613	211.146	237.759	7.525	5.440	do
2014-15	348.04	143.387	89.045	46.934	4.176	140.155	21.136	181.287	202.423	7.408	4.742	do
2015-16	117.889	113.816	70.391	37.023	3.378	110.792	-	-	-	6.402	3.298	do
2016-17	85.719	83.710	56.062	23.786	1.638	81.486	-	-	-	3.862	2.249	do
2017-18	125.396	119.084	75.411	35.636	2.410	113.457	-	-	-	5.627	3.28	do
2018-19	357.662	159.587	100.930	46.873	4.628	152.431	17.38	177.593	194.973	7.156	4.586	do
2019-20	419.603	185.835	118.897	54.363	5.486	172.847	15.933	208.185	224.118	7.089	5.813	do
2020-21	299.533	179.493	114.607	52.989	5.251	178.746	20.788	92.443	113.231	6.646	4.474	do
2021-22	411.889	217.310	135.607	66.500	6.510	208.617	34.336	126.161	160.497	8.693	5.134	do
2022-23	610.182	198.901	125.686	58.973	5.773	190.432	35.374	404.269	439.643	8.469	4.553	Capacities are as per 2016 surveys from 22.06.2022

(*) Heavy floods occurred in November 1992
 Bhadra Assistance: 1986-87 - 0.744 Tmctf, 1988-89 - 2.300 Tmctf, 1995-96 - 5.163 Tmctf, 1999-2000 - 3.731 Tmctf, 2000-2001 = 4.651 Tmctf, 2001-2002 = 0.746 Tmctf,
 2005-2006 = 2.683 Tmctf, 2006-07 = 4.360 Tmctf, 2007-2008 = 2.300 Tmctf, 2008-09 = 2.359 Tmctf, 2009-10 = 1.615 Tmctf, 2020-21 = 1.100 Tmctf & 2022-23 = 1.042 Tmctf.

**Statement showing the Pipings / Breaches occurred during the year 2022-23
(From 1-6-2022 to 31-5-2023).**

Sl. No.	Name of the Canal	Piping / Breaches occurred at Km.	Date of occurrence	Date of closing
1	2	3	4	5
I	Power Canal	(a) Pipings		
		Nil		
		(b) Breaches		
		Nil		
II	RB HLC	(a) Arresting leakages of UT at Km 25/505, D/s, R/s divide wall near Nallapur village of RBHLC	24.07.2022	01.08.2022
		Nil		
		(b) Breaches.		
		Nil		
III	RB LLC	(a) Temporary restoration to Hagari Aqueduct	08-09-22	30-11-22
		(b) Permanent Restoration work to Hagari Aqueduct	19-01-23	In progress

STATEMENT SHOWING MAX & MIN RESERVOIR LEVELS AND SPILLWAY DISCHARGES									
Sl. No.	Year	Reservoir				Total Qty. Surplused		Max. Spillway Discharge	
		Maximum		Minimum		No. of Days	In TMC	Date	Discharge c/s
		Date	Level	Date	Level				
1	1963-64	18.10.63	1632.80	11.06.63	1614.10	83	146.428	23.10.63	1,89,338
2	1964-65	19.11.64	1633.00	30.06.64	1600.60	92	249.545	10.08.64	1,50,229
3	1965-66	07.10.65	1631.90	19.06.65	1589.90	47	117.239	25.07.65	1,20,798
4	1966-67	19.10.66	1632.33	09.07.66	1580.80	2	0.302	23.08.66	2,915
5	1967-68	18.10.67	1633.00	02.07.67	1575.80	46	118.182	05.08.67	1,41,808
6	1968-69	29.09.68	1632.99	27.06.68	1584.32	34	70.804	19.08.68	75,705
7	1969-70	11.09.69	1633.00	16.05.69	1576.22	41	121.468	18.08.69	89,714
8	1970-71	20.08.70	1633.00	15.05.70	1599.76	73	214.510	25.08.70	1,18,829
9	1971-72	26.09.70	1633.00	15.05.71	1594.07	20	39.467	26.07.71	73,405
10	1972-73	18.09.72	1631.30	09.05.72	1575.53	0	0	0	0
11	1973-74	09.08.73	1633.00	08.05.73	1569.30	26	49.780	12.08.73	1,03,685
12	1974-75	16.08.74	1633.00	11.05.74	1568.10	32	63.304	14.09.74	1,61,262
13	1975-76	18.07.75	1633.00	08.05.75	1586.18	110	206.986	6.11.75	1,34,700
14	1976-77	17.09.76	1633.00	11.05.76	1599.26	0	0	0	0
15	1977-78	27.08.77	1633.00	15.05.77	1588.26	31	36.318	11.10.77	91,020
16	1978-79	08.09.78	1633.00	13.05.78	1593.75	76	300.809	28.08.78	1,77,696
17	1979-80	30.08.79	1633.00	13.05.79	1594.45	23	43.560	12.08.79	1,32,870
18	1980-81	07.09.80	1633.00	29.04.80	1593.32	78	292.192	06.07.80	1,96,139
19	1981-82	29.08.81	1633.00	27.04.81	1568.93	49	126.146	20.08.81	1,35,159
20	1982-83	11.08.82	1633.00	06.05.82	1568.06	34	130.463	06.08.82	1,63,655
21	1983-84	28.08.83	1633.00	27.04.83	1563.02	34	80.210	15.08.83	1,11,480
22	1984-85	28.09.84	1633.00	17.05.84	1576.61	52	66.000	05.08.84	1,16,777
23	1985-86	18.08.85	1632.62	15.04.85	1565.66	7	14.260	19.08.85	47,027
24	1986-87	14.08.86	1633.00	25.04.86	1561.70	9	27.040	15.08.86	1,05,999
25	1987-88	29.11.87	1618.43	16.05.87	1563.35	0	0	0	0
26	1988-89	15.09.88	1633.00	03.05.88	1569.80	40	52.117	15.08.88	1,05,680
27	1989-90	02.09.89	1633.00	22.04.89	1560.90	17	18.053	26.08.89	68,365
28	1990-91	16.08.90	1633.00	08.05.90	1574.00	30	102.163	17.08.90	131,161
29	1991-92	01.09.91	1633.00	24.04.91	1578.60	42	159.283	30.07.91	1,44,830
30	1992-93	14.09.92	1633.00	10.05.92	1574.08	71	267.916	18.11.92	3,69,152
31	1993-94	31.10.93	1632.95	14.05.93	1578.05	38	90.147	18.10.93	1,89,630
32	1994-95	26.10.94	1633.00	04.06.94	1573.84	73	311.416	17.07.94	2,64,140
33	1995-96	22.09.95	1633.00	25.04.95	1565.50	0	0	0	0
34	1996-97	01.09.96	1633.00	06.04.96	1569.50	26	28.704	06.09.96	96,920
35	1997-98	13.08.97	1633.00	15.05.97	1574.95	36	131.375	08.08.97	1,71,995
36	1998-99	15.08.98	1633.00	10.05.98	1574.64	55	85.597	15.09.98	1,05,680
37	1999-00	04.08.99	1633.00	23.04.99	1581.03	45	114.930	29.07.99	1,38,258
38	2000-01	10.08.00	1633.00	03.05.00	1574.37	55	96.642	26.08.00	72,976
39	2001-02	04.09.01	1631.78	25.05.01	1574.69	0	0	0	0
40	2002-03	18.09.02	1623.70	11.05.02	1563.13	0	0	0	0
41	2003-04	12.10.03	1622.93	26.06.03	1562.75	0	0	0	0
42	2004-05	06.08.20	1633.00	17.05.04	1566.55	11	23.100	15.08.04	97,106
43	2005-06	16.08.05	1633.00	18.04.05	1565.68	46	119.411	06.08.05	1,55,426
44	2006-07	01.08.06	1633.00	09.05.06	1570.20	32	110.916	15.08.06	1,70,569
45	2007-08	14.07.07	1633.00	19.04.07	1570.90	81	291.905	10.08.07	2,54,076
46	2008-09	12.08.08	1633.00	27.05.08	1592.86	24	137.543	15.08.08	2,22,654
47	2009-10	29.07.09	1633.00	24.04.09	1564.75	74	169.983	01.10.09	1,91,617
48	2010-11	22.08.10	1633.00	22.04.10	1571.36	58	121.416	05.10.10	94,054
49	2011-12	05.08.11	1633.00	09.05.11	1579.79	42	126.271	03.09.11	1,42,371
50	2012-13	09.09.12	1633.00	18.04.12	1575.16	9	13.947	03.09.12	45,710
51	2013-14	12.08.13	1633.00	25.05.13	1568.69	59	211.116	05.08.13	1,55,541
52	2014-15	14.08.14	1633.00	25.04.14	1573.29	44	173.640	03.08.14	1,90,602
53	2015-16	22.08.15	1626.40	29.04.15	1573.69	0	0	0	0
54	2016-17	24.08.16	1617.91	29.05.16	1570.08	0	0	0	0
55	2017-18	20.10.17	1630.22	13.06.17	1568.70	0	0	0	0
56	2018-19	31.08.18	1632.95	20.05.18	1575.20	43	177.592	16.08.18	216,040
57	2019-20	15.08.19	1633.00	15.06.19	1574.70	65	208.187	11.08.19	224,539
58	2020-21	24.08.20	1633.00	07.05.20	1577.16	52	92.444	19.08.20	110,160
59	2021-22	14.08.21	1633.00	31.05.21	1588.16	69	126.175	26.07.21	136,358
60	2022-23	24.07.22	1633.00	20.04.22	1586.17	100	404.267	10.08.22	166,203

CAPACITY OF TUNGABHADRA RESERVOIR (From 1953 To 2016)

Year of Survey	Dead storage Capacity		Live Storage Capacity		Gross storage Capacity		Annual rate of decrease in reservoir capacity (between successive surveys)		Remarks
	M.Cum	TMC	M.Cum	TMC	M.Cum	TMC	M.Cum	TMC	
1953	32.83	1.159	3718.293	131.312	3751.108	132.471	-	-	Original survey
1963	7.04	0.249	3239.727	114.411	3246.764	114.660	50.434	1.781	
1972	2.07	0.073	3428.525	121.079	3430.595	121.152	16.869	0.596*	
1978	-	-	3332.705	117.695	3332.705	117.695	16.315	0.576	
1981	-	-	3275.647	115.680	3275.647	115.680	19.019	0.672	
1985	-	-	3166.685	111.832	3166.685	111.832	27.240	0.962	
1993	-	-	3157.284	111.500	3157.284	111.500	1.175	0.041	
2004	-	-	2954.538	104.340	2954.538	104.340	18.431	0.651	
2008	-	-	2855.856	100.855	2855.856	100.855	24.671	0.871	
2016	-	-	2995.541	105.788	2995.541	105.788	7.032	0.248**	Implemented w.e.f 22.06.2022

Notes:

Dead storage is below RL 472.440 m

Live storage in between RL 472.440m and RL 497.738m.

* To find annual rate of decrease in Reservoir capacity for the year 1972, the original capacity of the Reservoir in 1953 has been considered.

** To find annual rate of decrease in Reservoir capacity for the year 2016, the capacity of the Reservoir in 1993 has been considered.

**TUNGABHADRA RESERVOIR PROJECT
ELEVATION AREA - CAPACITY TABLE IN 2016 USING
TOPOGRAPHIC SURVEY**

**TUNGABHADRA RESERVOIR PROJECT
ELEVATION AREA - CAPACITY TABLE IN 2016 USING
TOPOGRAPHIC SURVEY**

Elevation		Water Spread Area (Mm ²)	Capacity (M Cum)	Cumulative Capacity (M Cum)	Cumulative Capacity (TMC)	Remarks
Ft	m					
1555	473.96	0.000	0.000	0.000	0.000	Hydrographic Survey
1556	474.27	0.124	0.010	0.010	0.000	
1557	474.57	0.756	0.132	0.142	0.005	
1558	474.88	1.907	0.395	0.537	0.019	
1559	475.18	2.864	0.731	1.269	0.045	
1560	475.49	4.010	1.031	2.300	0.081	
1561	475.79	5.348	1.429	3.729	0.132	
1562	476.10	6.560	1.818	5.547	0.196	
1563	476.40	7.791	2.182	7.729	0.273	
1564	476.71	9.196	2.591	10.320	0.364	
1565	477.01	10.558	3.014	13.334	0.471	
1566	477.32	12.038	3.438	16.772	0.592	
1567	477.62	13.650	3.923	20.695	0.731	
1568	477.93	15.239	4.383	25.078	0.886	
1569	478.23	16.863	4.894	29.972	1.058	
1570	478.54	18.506	5.392	35.364	1.249	
1571	478.84	20.114	5.885	41.248	1.457	
1572	479.15	21.865	6.393	47.642	1.682	
1573	479.45	23.878	6.955	54.596	1.928	
1574	479.76	26.176	7.617	62.214	2.197	
1575	480.06	28.973	8.418	70.632	2.494	
1576	480.36	31.956	9.306	79.937	2.823	
1577	480.67	34.663	10.154	90.092	3.182	
1578	480.97	38.400	11.022	101.113	3.571	
1579	481.28	41.436	12.198	113.312	4.002	
1580	481.58	44.279	13.075	126.387	4.463	
1581	481.89	48.837	14.476	140.862	4.975	
1582	482.19	51.690	15.338	156.200	5.516	
1583	482.50	54.309	16.154	172.354	6.087	
1584	482.80	57.512	16.991	189.345	6.687	
1585	483.11	61.149	18.003	207.348	7.323	
1586	483.41	63.996	19.073	226.421	7.996	
1587	483.72	66.947	19.952	246.374	8.701	
1588	484.02	70.162	20.885	267.259	9.438	
1589	484.33	73.836	21.941	289.200	10.213	
1590	484.63	77.662	23.097	312.297	11.029	
1591	484.94	81.328	24.232	336.529	11.885	
1592	485.24	85.044	25.354	361.883	12.780	
1593	485.55	88.798	26.493	388.376	13.715	
1594	485.85	92.651	27.646	416.022	14.692	
1595	486.16	96.816	28.873	444.895	15.711	
1596	486.46	101.161	30.173	475.067	16.777	
1597	486.77	105.493	31.490	506.558	17.889	
1598	487.07	109.985	32.838	539.395	19.049	
1599	487.38	114.769	34.248	573.643	20.258	
1600	487.68	119.799	35.742	609.385	21.520	

1601	487.98	125.046	37.304	646.689	22.838
1602	488.29	130.394	38.917	685.606	24.212
1603	488.59	136.052	40.591	726.197	25.646
1604	488.90	142.090	42.378	768.575	27.142
1605	489.20	148.283	44.250	812.826	28.705
1606	489.51	154.461	46.129	858.955	30.334
1607	489.81	160.879	48.046	907.001	32.031
1608	490.12	167.519	50.031	957.032	33.798
1609	490.42	174.758	52.134	1009.166	35.639
1610	490.73	182.689	54.506	1063.672	37.564
1611	491.03	190.396	56.876	1120.548	39.572
1612	491.34	197.819	59.152	1179.700	41.661
1613	491.64	205.323	61.425	1241.124	43.830
1614	491.95	212.805	63.708	1304.832	46.080
1615	492.25	220.209	65.976	1370.808	48.410
1616	492.56	227.769	68.258	1439.065	50.821
1617	492.86	235.547	70.590	1509.655	53.313
1618	493.17	243.675	73.013	1582.668	55.892
1619	493.47	252.084	75.532	1658.200	58.559
1620	493.78	260.661	78.131	1736.331	61.319
1621	494.08	269.005	80.710	1817.041	64.169
1622	494.39	277.404	83.249	1900.290	67.109
1623	494.69	285.880	85.821	1986.111	70.140
1624	495.00	294.622	88.448	2074.560	73.263
1625	495.30	303.481	91.125	2165.684	76.481
1626	495.60	312.663	93.910	2259.595	79.798
1627	495.91	322.062	96.753	2356.347	83.214
1628	496.21	331.226	99.589	2455.936	86.731
1629	496.52	340.204	102.346	2558.282	90.346
1630	496.82	349.359	105.099	2663.381	94.057
1631	497.13	358.340	107.882	2771.263	97.867
1632	497.43	367.137	110.590	2881.853	101.773
1633	497.74	375.741	113.688	2995.541	105.788

Topographic Survey

Note : 1. Below RL +1578 ft is carried out by Hydrographical survey

2. Above RL +1578 ft is carried out by Topographical survey

Dead storage Level : 473.96 m (+1555 ft)

Crest Level : 491.642 m (+1613 ft)

F.R.L. & M.W.L. : 497.738 m (+1633 ft)

**STATEMENT SHOWING THE DETAILS OF AYACUT AND DISCHARGES OF DP'S & DISTRIBUTARIES OF RIGHT BANK
LOW LEVEL CANAL UP TO BOARD LIMIT**

Sl. No.	Name of Sluices	Location KM.	Schedule Discharge (C/s.)						Ayacut in Acres.					
			Khariff			Rabi			Khariff			Rabi		
			K.A	A.P	TOTAL	K.A	A.P	TOTAL	K.A	A.P	TOTAL	K.A	A.P	TOTAL
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
1	Rajan Sluice	10.262	28.00	---	28.00	28.00	---	28.00	150.00	---	150.00	450.00	---	450.00
2	Gowamma Tank	15.260	15.00	---	15.00	15.00	---	15.00	150.00	---	150.00	450.00	---	450.00
3	Sanapura Distributory	18.842	52.00	---	52.00	52.00	---	52.00	2944.00	---	2944.00	896.00	---	896.00
4	Muddapura No.1	21.364	39.00	---	39.00	39.00	---	39.00	2307.45	---	2307.45	528.83	---	528.83
5	D.P.No.1	24.100	4.75	---	4.75	4.75	---	4.75	279.20	---	279.20	191.43	---	191.43
6	D.P.No.2	26.733	12.00	---	12.00	12.00	---	12.00	732.86	---	732.86	0.00	---	0.00
7	D.P.No.3	29.848	3.00	---	3.00	3.00	---	3.00	187.82	---	187.82	0.00	---	0.00
8	Muddapura No.2	32.064	15.00	---	15.00	15.00	---	15.00	752.75	---	752.75	2412.83	---	2412.83
9	D.P.No.4	33.595	1.00	---	1.00	1.00	---	1.00	50.24	---	50.24	162.38	---	162.38
10	D.P.No.5	35.834	---	---	0.00	0.80	---	0.80	---	---	0.00	129.85	---	129.85
11	D.P.No.6	41.112	1.70	---	1.70	1.70	---	1.70	88.18	---	88.18	268.29	---	268.29
12	Sugur Distributory	43.025	41.00	---	41.00	41.00	---	41.00	2065.05	---	2065.05	6612.97	---	6612.97
13	Nadavi Distributory	44.964	20.00	---	20.00	23.93	---	23.93	1152.51	---	1152.51	3680.45	---	3680.45
14	D.P.No.7	47.776	1.40	---	1.40	1.40	---	1.40	70.04	---	70.04	223.90	---	223.90
15	D.P.No.8 & 9	49.886	5.22	---	5.22	4.61	---	4.61	240.76	---	240.76	759.97	---	759.97
16	D.P.No.10 & 11	52.817	1.80	---	1.80	1.80	---	1.80	90.02	---	90.02	288.35	---	288.35
17	D.P.No.12	55.819	1.52	---	1.52	1.41	---	1.41	70.11	---	70.11	224.21	---	224.21
18	D.P.No.13	54.892	---	---	0.00	1.00	---	1.00	---	---	0.00	159.88	---	159.88
19	D.P.No.14	56.783	0.41	---	0.41	0.41	---	0.41	20.96	---	20.96	67.25	---	67.25
20	D.P.No.15	58.417	1.81	---	1.81	---	---	0.00	90.61	---	90.61	---	---	0.00
21	D.P.No.16	59.612	0.85	---	0.85	---	---	0.00	42.73	---	42.73	---	---	0.00
22	D.P.No.17	61.868	1.40	---	1.40	1.85	---	1.85	70.17	---	70.17	223.77	---	223.77
23	D.P.No.17.(A)	63.463	2.63	---	2.63	3.45	---	3.45	131.52	---	131.52	421.30	---	421.30
24	Muddatanur R.S	64.967	13.75	---	13.75	13.51	---	13.51	671.28	---	671.28	2127.00	---	2127.00
25	Bagewadi R.S	68.293	138.60	---	138.60	138.00	---	138.00	7907.51	---	7907.51	6430.74	---	6430.74
26	D.P.No.18	70.645	8.20	---	8.20	8.33	---	8.33	410.00	---	410.00	1312.00	---	1312.00
27	D.P.No.19	73.710	3.86	---	3.86	3.70	---	3.70	191.26	---	191.26	589.05	---	589.05
28	D.P.No.20	74.271	4.82	---	4.82	4.71	---	4.71	241.46	---	241.46	767.93	---	767.93
29	D.P.No.21	79.663	4.09	---	4.09	3.91	---	3.91	199.02	---	199.02	641.09	---	641.09

30	D.P.No.22	87.020	8.53	---	8.53	8.50	---	8.50	426.61	1363.24	---	1363.24	---	1363.24
31	D.P.No.23	89.336	3.62	---	3.62	5.00	---	5.00	250.00	800.00	---	800.00	---	800.00
32	D.P.No.24	92.480	1.28	---	1.28	1.20	---	1.20	60.22	192.54	---	192.54	---	192.54
33	D.P.No.25	97.050	2.00	---	2.00	1.64	---	1.64	100.00	317.02	---	317.02	---	317.02
34	Kuriganur Distributory 26 & 27	102.635	70.19	---	70.19	71.87	---	71.87	4248.35	1800.92	---	1800.92	---	1800.92
35	D.P.No.28	104.341	1.17	---	1.17	0.80	---	0.80	40.74	128.39	---	128.39	---	128.39
36	D.P.No.29	105.835	3.19	---	3.19	2.90	---	2.90	145.46	464.39	---	464.39	---	464.39
37	D.P.No.30 (A)	109.750	1.10	---	1.10	1.87	---	1.87	55.00	300.00	---	300.00	---	300.00
38	D.P.No.30	110.698	2.10	---	2.10	1.33	---	1.33	160.02	513.46	---	513.46	---	513.46
39	D.P.No.31	113.280	3.00	---	3.00	2.93	---	2.93	150.22	480.00	---	480.00	---	480.00
40	D.P.No.32	116.688	1.42	---	1.42	1.40	---	1.40	70.10	224.83	---	224.83	---	224.83
41	D.P.No.33 L.S	118.021 LS	13.06	---	13.06	14.00	---	14.00	653.00	226.50	---	226.50	---	226.50
42	D.P.No.34 R.S	118.021 RS	3.47	---	3.47	3.47	---	3.47	174.00	555.00	---	555.00	---	555.00
43	D.P.No.35	120.05	11.65	---	11.65	11.65	---	11.65	582.55	582.55	---	582.55	---	582.55
44	D.P.No.36	128.728	7.36	---	7.36	6.32	---	6.32	368.43	1013.28	---	1013.28	---	1013.28
45	D.P.No.37	130.921	1.16	---	1.16	---	---	---	58.20	41.36	---	41.36	---	41.36
46	D.P.No.37 (A)	131.810	---	---	---	0.47	1.20	1.67	---	76.00	143.00	143.00	---	219.00
47	D.P.No.38	137.080	5.94	---	5.94	---	---	0.00	278.93	---	---	---	---	0.00
48	D.P.No.39	139.905	0.33	---	0.33	0.33	---	0.33	16.50	46.22	---	46.22	---	46.22
49	D.P.No.40	145.050	3.33	---	3.33	---	---	0.00	166.71	---	---	---	---	0.00
50	D.P.No.41	146.640	1.40	---	1.40	1.40	---	1.40	70.43	217.86	---	217.86	---	217.86
51	D.P.No.42	149.880	1.02	---	1.02	0.91	---	0.91	40.00	117.53	---	117.53	---	117.53
52	D.P.No.43	151.880	1.20	---	1.20	1.18	---	1.18	60.37	190.29	---	190.29	---	190.29
53	D.P.No.44	154.000	---	1.00	1.00	2.75	2.70	5.45	85.00	104.00	63.00	213.00	213.00	317.00
54	D.P.No.45	154.837	---	4.00	4.00	0.80	4.00	4.80	15.00	271.00	271.00	774.00	774.00	850.00
55	D.P.No.46	157.750	---	1.00	1.00	---	1.20	1.20	68.00	144.00	68.00	144.00	144.00	144.00
56	D.P.No.47	161.574	---	1.50	1.50	---	1.50	1.50	107.00	187.00	107.00	187.00	187.00	187.00
57	D.P.No.48	165.590	---	3.50	3.50	---	5.50	5.50	255.00	742.00	255.00	742.00	742.00	742.00
58	D.P.No.49	168.549	---	1.00	1.00	---	2.00	2.00	86.00	272.00	86.00	272.00	272.00	272.00
59	D.P.No.50 (A)	171.70	---	5.00	5.00	---	---	0.00	250.00	0.00	250.00	0.00	0.00	0.00
60	D.P.No.50	173.100	---	4.00	4.00	---	6.00	6.00	469.00	1305.00	469.00	1305.00	1305.00	1305.00
61	D.P.No.51	175.419	---	1.50	1.50	---	2.00	2.00	100.00	240.00	100.00	240.00	240.00	240.00
62	D.P.No.52	178.225	---	0.90	0.90	---	1.00	1.00	59.00	100.00	59.00	100.00	100.00	100.00
63	D.P.No.53	180.525	---	0.90	0.90	---	3.50	3.50	56.00	539.00	56.00	539.00	539.00	539.00
64	D.P.No.54	182.386	---	1.00	1.00	---	1.30	1.30	67.00	189.00	67.00	189.00	189.00	189.00
65	D.P.No.55	183.728	---	2.00	2.00	---	2.30	2.30	148.00	288.00	148.00	288.00	288.00	288.00
66	D.P.No.56	185.044	---	1.50	1.50	---	1.50	1.50	96.00	192.00	96.00	192.00	192.00	192.00

STATEMENT SHOWING THE DETAILS OF AYACUT OF DP'S & DISTRIBUTARIES OF TUNGABHADRA PROJECT LOW LEVEL CANAL (TBPLLC) BEYOND BOARD LIMIT				
SL.No.	DP No.	Ayacut (Acres) Khariff	Ayacut (Acres) Rabi	Ayacut (Acres)
1	2	3	4	5
1	D.P 74 of L.L.C	161.16	429.84	591.00
2	D.P 75 of L.L.C	397.80	1367.72	1765.52
3	Kowthalam Major Distributory	954.24	2603.28	3557.52
4	Madhavaram Major Distributory	3226.32	8432.94	11659.26
5	Chagi Major Distributory	1200.16	3297.62	4497.78
6	Kattododdi Major Distributory	686.26	1584.59	2270.85
7	Halvi Major Distributory	1042.19	2794.34	3836.53
8	Naranapuram Major	782.82	1911.43	2694.25
9	DP .76 of LLC	209.61	484.62	694.23
10	Sugur major	2390.70	3731.11	6121.81
11	DP .77 of LLC	90.93	211.83	302.76
12	DP .78 of LLC	86.64	68.74	155.38
13	Gangavaram Major	3041.66	6430.59	9472.25
14	Nandavaram Major	831.93	2243.44	3075.37
15	C.K. Major	2986.69	6050.14	9036.83
16	DP 79 of TBP LLC	388.82	429.55	818.37
17	DP 80 of TBP LLC	596.73	1339.65	1936.38
18	MSP Major	1169.32	3313.96	4483.28
19	D.P 81 of LLC	137.72	569.44	707.16
20	D.P 82 of LLC	299.21	973.23	1272.44
21	D.P 83 of LLC	89.54	171.53	261.07
22	DP 86 of LLC	303.43	824.6	1128.03
23	P.D Major	1067.45	2993.87	4061.32
24	MLSP	1382.76	3998.13	5380.89
25	Kurnool Branch Canal	4778.1	14468.64	19246.74
26	Gorantla Major	1400.89	3634.06	5034.95
27	Gundrevula Disributory	2653.17	6977.62	9630.79
28	L Polur Dist	3385.72	9004.23	12389.95
29	G.Sinavaram Distributory	1657.03	3992.97	5650.00
	Total	37399.00	94333.71	131732.71

STATEMENT SHOWING THE DETAILS OF AYACUT AND DISCHARGES OF DP'S & DISTRIBUTARIES OF RIGHT BANK HIGH LEVEL CANAL UP TO BOARD LIMIT

Sl No.	Name of Sluice	Location in Km	Scheduled Discharge in(cusecs)	Ayacut in Acres.
1	2	3	4	5
1	Distributary No. 1	9.293	6.00	852.00
2	Distributary No. 1B (Allikere Tank)	17.840	2.00	383.00
3	Distributary No. 1A	21.221	6.40	900.00
4	Distributary	23.485	1.00	200.00
5	Distributary No. 2	33.523	42.02	6100.00
6	Distributary No. 2A1	37.440	19.00	2515.26
7	Distributary No. 2A2	44.740	5.00	461.66
8	Distributary No. 3A (Daroji Tank)	53.922	80.00	3222.73
9	Distributary No. 3	54.982	46.00	6560.00
10	Distributary No. 4	56.615	5.00	647.00
11	Distributary No. 5	59.600	5.00	679.00
12	Distributary No. 6	62.545	40.00	5709.00
13	Distributary No. 7	63.900	399.00	47050.00
14	Distributary No. 8	65.776	6.00	790.00
15	Distributary No. 9	66.123	29.00	4214.00
16	Distributary No. 10	70.411	25.00	3594.00
17	Distributary No. 11	75.114	34.00	4854.00
18	Distributary No. 12	77.110	53.00	7661.00
19	Distributary No. 13	79.700	158.00	22750.00
20	Distributary No. 14	82.702	243.00	34984.00
21	Distributary No. 14A	91.900	7.50	613.86
22	Distributary No. 15	93.455	113.00	16300.00
23	Distributary No. 16	101.170	90.00	14950.00
24	Distributary No. 16A	103.700	26.00	3867.00
		TOTAL	1440.92	189857.51

STATEMENT SHOWING THE DETAILS OF AYACUT OF MAIN CANAL AND BRANCH CANALS OF RIGHT BANK HIGH LEVEL CANAL BEYOND BOARD LIMIT						
Sl. No.	Name of the Canal / Branch Canal	Number of Distributaries	Ayacut in acres			Entitled water out of 32.50 TMC as per KWDT
			WET	ID	Total	
A. T.B.P HLC STAGE - I						
1	High Level Main Canal	15	28488	7053	35541	7.32
2	Mid Pennar North Canal	19	4438	8887	13325	1.87
3	Mid Pennar South Canal	29	8290	24886	33176	4.32
4	Tadipatri Branch Canal	13	8821	22310	31131	3.70
B. T.B.P HLC STAGE - II						
5	Guntakal Branch Canal	23	10446	5346	15792	2.77
6	Gooty Sub Branch Canal	2	0	16271	16271	1.75
7	Alur Brach Canal	19	7861	6394	14255	2.37
8	Mylavaram North Canal	8	0	47214	47214	2.66
9	Mylavaram South Canal	15	0	22708	22708	1.34
10	Pulivendula Branch Canal	33	0	55579	55579	4.40
	Total :	176	68344	216648	284992	32.50

STATEMENT SHOWING THE DETAILS OF AYACUT AND DISCHARGES OF DISTRIBUTARIES OF LEFT BANK MAIN CANAL (LBMC)				
	Name of Distributary	Location in Kms	Design Discharge in cusecs	Ayacut in Acres (Kharif / Rabi)
1	2	3	4	5
1	Distributary No.1	0.803	27.97	675.16
2	Distributary No.2	4.620	15.64	523.14
3	Distributary No.3A	6.870	25.00	799.37
4	Distributary No.5	9.060	4.12	129.26
5	Distributary No.6	11.580	5.62	251.02
6	Distributary No.7	12.000	6.62	234.36
7	Distributary No.8	12.990	20.45	683.24
8	Distributary No.9	15.090	25.12	674.02
9	Distributary No.10	17.040	12.53	183.13
10	Distributary No.10A	18.120	20.00	558.19
11	Distributary No.11	25.290	34.72	1504.34
12	Distributary No.11A	27.150	3.67	287.12
13	Distributary No.12 Extra Sluice	23.250	1.95	122.20
14	Distributary No.13	32.130	15.26	902.01
15	Distributary No.14	33.000	10.56	742.36
16	Distributary No.15	34.590	2.75	116.01
17	Distributary No.16	36.660	13.37	684.18
18	Distributary No.17	39.450	93.03	9773.00
19	Distributary No.18	42.930	3.92	100.00
20	Distributary No.19	43.650	27.00	1685.00
21	Distributary No.20	46.050	4.00	287.00
22	Distributary No.21	47.910	61.18	4706.00
23	Distributary No.22	49.380	3.00	419.00
24	Distributary No.23	50.940	3.00	168.00
25	Distributary No.23A	51.840	15.49	458.00
26	Distributary No.25	55.410	172.26	18516.00
27	Distributary No.27	58.410	16.90	1230.00
28	Distributary No.28	58.650	14.84	1511.00
29	Distributary No.29	62.250	10.64	1274.00
30	Distributary No.30	64.950	22.30	1339.00
31	Distributary No.31	68.070	280.00	43305.00
32	Distributary No.32	69.960	175.00	24687.00
33	Distributary No.33	71.670	2.80	358.00
34	Distributary No.34	74.160	2.80	358.00
35	Distributary No.36	75.660	208.00	44963.30

36	Distributary No.37	78.300	8.86	1589.32
37	Distributary No.38	79.500	2.80	621.22
38	Distributary No.40	83.430	68.00	14249.27
39	Distributary No.41	85.785	2.00	498.09
40	Distributary No.42	87.300	6.40	1460.11
41	Distributary No.44	89.070	1.83	245.30
42	Distributary No.45	91.410	44.42	9551.08
43	Distributary No.46	92.550	34.80	4283.07
44	Distributary No.48	94.950	19.56	4152.20
45	Distributary No.49	98.460	8.20	1542.00
46	Distributary No.51	101.100	1.12	218.10
47	Distributary No.52	102.900	5.15	1173.14
48	Distributary No.54	103.860	379.00	87085.17
49	Distributary No.55	106.680	81.24	16022.16
50	Distributary No.56	107.280	5.05	1030.22
51	Distributary No.62	117.600	10.37	2105.09
52	Distributary No.65	122.700	56.30	7859.10
53	Distributary No.66	124.200	16.33	3241.26
54	Distributary No.69	128.700	16.27	3409.18
55	Distributary No.71/A	134.250	14.21	3049.22
56	Distributary No.73	137.208	22.54	3106.28
57	Distributary No.74	138.120	5.13	766.28
58	Distributary No.76	141.180	428.30	57878.38
59	Distributary No.78	143.880	16.30	2051.07
60	Distributary No.79	144.780	10.24	1130.11
61	Distributary No.81	149.190	3.59	612.28
62	Distributary No.82	152.190	73.03	9602.20
63	Distributary No.84	154.770	24.00	2327.34
64	Distributary No.85	156.000	240.40	25739.10
65	Distributary No.87	159.120	7.08	1419.18
66	Distributary No.89	159.990	244.90	33254.18
67	Distributary No.90	163.620	40.34	3595.21
68	Distributary No.91	164.970	12.48	1134.12
69	Distributary No.92	166.710	80.00	11582.38
70	Distributary No.94	170.070	3.86	540.29
71	Distributary No.95	178.155	28.94	7479.10
72	Distributary No.96	179.640	32.08	4496.65
73	Distributary No.98	193.781	175.86	31958.18
74	Distributary No.98A	190.620	4.89	368.35
75	Distributary No.98B	191.910	8.03	461.07
76	Distributary No.99	193.110	135.06	15305.34
77	Distributary No.99A	193.410	10.01	1243.21
78	Distributary No.100	198.660	52.05	5242.76
79	Distributary No.102	204.960	110.20	17065.08
80	Distributary No.102A	206.070	74.58	14100.73
81	Distributary No.103	211.740	11.27	2130.24
82	Distributary No.104	217.950	23.28	5323.19
83	Distributary No.104ABC	218.340	9.27	1987.29
84	Distributary No.105	221.910	3.98	794.11
85	Distributary No.106	232.000	66.95	12407.63
	Total		4102.06	602692.04

**STATEMENT SHOWING THE DETAILS OF AYACUT AND
DISCHARGES OF LEFT BANK HIGH LEVEL CANAL (LBHLC)
AND RAYA BASAVANNA CANAL**

Sl. No.	Name of the Canal	Design Discharge in cusecs	Ayacut in Acres	
			Kharif	Rabi
1	2	3	4	5
1	LBHLC	33.00	1160.00	0.00
<i>Raya Basavanna Canals</i>				
A	Raya Canal	170.00	5110.00	5110.00
B	Basavanna Canal	80.00	2358.00	2358.00
	TOTAL	250.00	7468.00	7468.00


Details of Telemetry locations installed in TB Project Canals

S.No	Name of Telemetry Station	Telemetry Location			Type of Sensor
		On	Longitude	Latitude	
	A. RBHLC				
1	RBHLC At KM 2.483	Main Canal	76° 21' 40.788"	15° 15' 38.5596"	Side- Looking Doppler flow sensor
2	RBHLC At KM 45.00	Main Canal	76° 38' 32.629"	15° 12' 55.5084"	
3	DP 3A of RBHLC At KM 53.922	Distry. Head	76° 41' 27.960"	15° 13' 31.1808"	
4	DP3 of RBHLC At KM 54.982 @ Distributary	Distry. Canal	76° 68' 62.880"	15° 22' 58.0280"	
5	D7 of RBHLC At KM 63.900 Distry. Head	Distry. Head	76° 45' 25.992"	15° 14' 15.9972"	
6	D11 of RBHLC At KM 75.114 @ Distributary	Distry. Canal	76° 83' 43.840"	15° 21' 24.0210"	
7	D12 of RBHLC At KM 77.175	Distry. Head	76° 50' 47.364"	15° 11' 57.5520"	
8	D13 of RBHLC At KM 79.702	Distry. Head	76° 51' 45.954"	15° 11' 05.5068"	
9	D14 of RBHLC At KM 82.000 @Distry. Head	Distry. Head	76° 52' 38.470"	15° 09' 57.3696"	
10	D15 of RBHLC At KM 93.465 @ Distry. Head	Distry. Head	76° 55' 07.500"	15° 05' 42.6000"	
11	D16 of RBHLC At KM 101.000 @ Distry. Head	Distry. Canal	76° 57' 54.205"	15° 02' 59.5320"	
12	D16 -A of RBHLC At KM 103.000 @ Distry Head	Distry. Head	76° 58' 29.827"	15° 01' 54.5736"	
13	AP Border At KM 104.787	Main Canal	76° 58' 31.512"	15° 01' 24.0276"	

	B. Power canal								
14	Power Canal At Km 0.500		Main Canal	76° 20' 35.282"	15° 16' 03.9504"			Side- Looking Doppler flow sensor	
	C. Raya Basavanna Canal								
15	Raya Basavanna Canal At KM.0.200		Main Canal	76° 20' 29.760"	15° 15' 47.0502"			Side- Looking Doppler flow sensor	
	D. TLBC								
16	TLBC Ch. 28		Main Canal	76° 19' 51.001"	15° 16' 30.0004"				
17	TLBC Mile 10		Main Canal	76° 22' 11.704"	15° 20' 52.2708"				
18	TLBC Mile 19		Main Canal	76° 28' 55.819"	15° 23' 29.3748"				
19	TLBC Mile 24		Main Canal	76° 28' 08.112"	15° 26' 59.5536"				
20	TLBC Mile 36		Main Canal	76° 32' 33.009"	15° 34' 21.0008"				
21	TLBC Mile 46		Main Canal	76° 36' 13.003"	15° 40' 52.0001"				
22	TLBC Mile 60		Main Canal	76° 36' 55.098"	15° 51' 17.9892"				
23	TLBC Mile 69		Main Canal	76° 39' 42.426"	15° 57' 00.5688"				
24	TLBC Mile 90		Main Canal	76° 51' 52.052"	16° 04' 25.5504"				
25	TLBC Mile 104		Main Canal	76° 00' 57.146"	16° 12' 13.2552"				
	E. LBHLC								
26	LBHLC @ Km 0.5		Main Canal	76° 19' 19.300"	15° 16' 42.4344"			Side- Looking Doppler flow sensor	
	F. RBLLC								
27	RBLLC Head @ LLC km 2.842		Main Canal	76° 31' 22.066"	15° 20' 04.9146"				
28	Sanapura Dy. At LLC Km 18.846 at Disty. Head		Distry. Head	76° 40' 56.028"	15° 25' 54.0000"			Side- Looking Doppler flow sensor	
29	Muddapura No.1 @ LLC Km 21.356		Distry. Head	76° 37' 36.984"	15° 21' 24.0084"				

30	LLC Km 23.100	Main. Canal	76° 64' 07.087"	15° 35' 22.0099"	Side- Looking Doppler flow sensor
31	LLC Km 40.00	Main. Canal	76° 73' 63.053"	15° 34' 48.0052"	
32	Sugur Dy. @ LLC Km 43.019	Distry. Head	76° 44' 49.848"	15° 21' 36.0378"	
33	Nadavi Dy. @ LLC Km 44.964	Distry. Canal	76° 45' 31.068"	15° 22' 22.0098"	
34	Bagewadi Dy. @ LLC 68.293 at Distry. Head	Distry. Head	76° 52' 56.776"	15° 25' 29.2404"	
35	LLC Km 70.00	Main Canal	76° 53' 43.728"	15° 25' 48.6264"	
36	LLC Km 85.00	Main. Canal	76° 93' 84.078"	15° 36' 16.0047"	
37	Kuriganur Dy. @ LLC Km 102.60 @ Distry. Canal	Distry. Head	77° 00' 28.003"	15° 17' 57.0008"	
38	LLC Km 103.00	Main. Canal	77° 00' 93.510"	15° 29' 89.0069"	
39	LLC Km 121.00	Main. Canal	77° 05' 87.090"	15° 19' 77.0033"	
40	LLC Km 133.700	Main Canal	77° 07' 52.000"	15° 13' 56.0000"	
41	LLC Km 184.00	Main Canal	77° 02' 11.256"	15° 29' 20.4432"	
42	Kotehal Dy. At LLC Km 193.800	Disty. Canal	77° 03' 08.061"	15° 32' 05.0055"	
43	Hatcholli Dy. @ LLC Km 205.250	Distry. Canal	77° 04' 58.436"	15° 34' 16.8096"	
44	T.S. Dystry @ Km 250.580 Dystry. Head	Distry. Head	77° 08' 52.003"	15° 41' 01.0007"	
45	AP Border @ Km 251.100 Main Canal	Main. Canal	77° 08' 52.003"	15° 41' 01.0007"	

ORGANIZATION CHART OF HYDRO – ELECTRIC WING




POWER GENERATION AND UTILISATION (Million Units)

Sl.No.	Description	2008-09	2009-10	2010-11	2011-12	2012-13	2013-14	2014-15	2015-16	2016-17	2017-18	2018-19	2019-20	2020-21	2021-22	2022-23
1	POWER GENERATION															
	i. Dehu Power House	97.9404	90.1190	96.3670	100.9700	59.7209	81.245	73.130	49.927	30.0302	32.7071	60.059	77.526	76.448	102.211	88.551
	ii. Hampi Power House	107.69	93.941	86.424	87.163	68.364	93.709	91.148	66.748	50.335	54.6174	74.616	99.447	96.67	102.993	104.746
	iii. Ncl Mini Hydel Power House	21.6504	25.4079	26.2684	24.6874	20.1279	25.5666	26.919	12.8913	3.432	12.97226	20.369	27.717	26.069	33.82	30.6998
	iv. Khandaleru Power House	--	--	--	--	--	4.1816	6.759	5.0443	3.391	3.7935	7.00	6.364	6.3249	7.765	9.0853
	TOTAL	227.2808	215.47	211.08	212.8269	148.2128	204.7031	197.957	134.611	87.1882	104.0903	162.044	211.054	205.512	246.789	233.082
2	AUXILIARY CONSUMPTION (Consumption of common loads)	7.14742	6.96	7.32066	7.81632	7.20428	7.119037	7.0835	6.80904	6.2033	6.38735	6.053	5.766	5.8014	5.857	5.68559
3	POWER GENERATED FOR SHARING	220.13338	219.07404	203.75934	205.01058	141.00852	197.58406	190.8735	122.2761	78.4613	93.4185	148.99	197.678	193.386	233.167	218.311
4	IMPORT OF POWER	1.1246	1.869	0.7705	1.467	0.648	1.445638	0.293	0.881	1.9943	1.514	0.751	1.263	0.5515	0.563	0.666
		1.7836	4.002	3.4245	2.636	3.1715	2.4626	2.247	3.0345	3.8943	2.347	1.733	2.045	1.7977	0.914	0.046
5	Total gross units available at TBHES bus bars for utilisation by	229.064	219.475	214.504	215.539	151.384	207.165	200.203	137.646	91.082	106.637	163.778	213.101	207.236	248.277	233.993
5	GOVT. OF KARNATAKA	42.71829	40.33412	39.4048	39.67774	27.87286	43.855651	43.6005	24.7262	16.9052	19.6804	25.373	40.388	38.7147	46.769	37.081
		40.25189	41.22076	41.05881	35.56872	24.49896	42.841190	42.1914	24.4444	13.9347	20.5244	27.054	38.421	43.3826	51.650	35.094
6	GOVT. OF ANDHRA PRADESH	170.87316	161.33651	157.61921	158.71097	111.49144	153.95265	148.1755	97.53438	61.5434	73.7202	99.47	157.28	153.8822	184.382	148.006
		173.33956	160.44988	155.96520	162.820	114.86534	154.96711	149.5846	97.81620	61.5138	72.8816	97.79	159.796	149.2143	179.502	149.993
7	TOTAL UTILISATION	213.59145	201.67064	197.02401	198.38872	139.3643	197.81	191.776	122.2606	78.4486	93.406	124.844	198.217	192.597	231.152	185.087
8	System losses	7.162	6.845	7.48645	7.34	2.26867	2.119	1.3321	3.51656	3.0269	3.03786	5.509	3.292	2.5918	3.582	3.4358
9	% System losses	3.13%	3.12%	3.49%	3.41%	1.50%	1.02%	0.67%	2.55%	3.32%	2.85%	3.36%	1.54%	1.25%	1.44%	1.47%

GENERATION COST PER UNIT

Sl.No	Year	Water utilization TMC	Power generated M.Units	Direct expenditure (Lakhs)	Indirect expenditure		Total expenditure (Lakhs)	Cost of generation (paise)
					Depreciation (Lakhs)	Interest on Capital (Lakhs)		
1	2	3	4	5	6	7	8	9
1	2004-05	39.200	148.521	599.67	2.29	34.19	636.15	42.83
2	2005-06	61.363	205.221	597.89	2.29	34.19	634.37	30.91
3	2006-07	50.820	196.8737	975.41	2.29	34.19	1011.89	51.40
4	2007-08	57.858	224.13691	846.48	2.29	34.19	882.96	39.40
5	2008-09	54.08	205.6304	848.43	2.29	34.19	884.91	43.03
6	2009-10	57.828	190.0605	952.58	2.29	34.19	989.06	52.04
7	2010-11	62.533	184.8116	849.04	1.9	34.19	885.13	47.89
8	2011-12	67.17	188.1395	1555.03	1.9	34.19	1591.12	84.57
9	2012-13	42.748	128.0849	1527.35	1.9	34.19	1563.44	122.06
10	2013-14	50.438	174.955	1688.87	1.9	34.19	1724.96	98.59
11	2014-15	81.163	164.2784	1849.81	0	22.31	1872.12	113.96
12	2015-16	56.274	116.6759	2006.18	0	0	2006.18	171.94
13	2016-17	39.86	80.3652	2353.38	0	0	2353.38	292.84
14	2017-18	32.752	87.3245	2549.44	0	0	2549.44	291.95
15	2018-19	47.604	134.67	2438.137	0	0	2438.137	181.05
16	2019-20	55.688	176.98	2000	0	0	2000	113.01
17	2020-21	53.425	173.118	2188.91	0	0	2188.91	126.44
18	2021-22	70.401	205.203	2568.29	0	0	2568.29	125.16
19	2022-23	66.956	193.296	3437.21	0	0	3437.21	177.82


ORGANIZATION CHART OF FISHERIES WING




PHYSICAL PERFORMANCE OF FISHERIES WING

Period	Fish Farm Unit		Reservoir Unit			Ice cum Cold storage plant
	Production of spawn (lakhs)	Supply of Fish Feed (lakhs)	Area of Pens erected (ha.)	Spawn (lakhs)	Direct stocking of finger lings. (lakh)	Production of ice (Tonnes)
1	2	3	4	5	6	7
2007-2008	477.30	268.00 Spawn 36.90 Fry 28.49 Fingerlings	3	240	11.42	2118.55
2008-2009	315.85	130.35 Spawn 27.34 Fry 26.26 Fingerlings	3	114	11.62	2483.65
2009-2010	527.40	301.40 Spawn 30.67 Fry 35.52 Fingerlings	3	231	9.89	2702.30
2010-2011	615.90	454.85 Spawn 12.02 Fry 33.56 Fingerlings	3	223	11.00	2447.05
2011-2012	649.25	480.10 Spawn 12.40 Fry 35.92 Fingerlings	3	265	14.12	2823.45
2012-2013	494.98	330.00 Spawn 7.77 Fry 43.56 Fingerlings	5	190	15.97	2358.95
2013-2014	659.95	447.90 Spawn 10.63 Fry 45.71 Fingerlings	5	230	24.85	2236.33
2014-2015	569.00	322.84 Spawn 2.73 Fry 56.54 Fingerlings	5	259	28.94	2069.30
2015-2016	465.10	247.50 Spawn 2.06 Fry 52.82 Fingerlings	1	66	30.43	1707.65
2016-2017	444.87	151.80 Spawn 2.65 Fry 47.90 Fingerlings	-	-	35.15	1305.55
2017-2018	503.89	349.50 Spawn 0.00 Fry 44.73 Fingerlings	-	-	26.71	1631.55
2018-2019	450.13	235.40 Spawn 0.00 Fry 31.49 Fingerlings	-	-	34.50	792.35
2019-2020	507.00	262.00 Spawn 4.66 Fry 31.28 Fingerlings	-	-	31.09	1915.90
2020-2021	676.00	419.00 Spawn 0.00 Fry 60.29 Fingerlings	-	-	35.94	1687.75
2021-2022	856.50	646.50 Spawn 0.00 Fry 48.40 Fingerlings	-	-	34.45	1856.20
2022-2023	Outsourced Fish Farm & Ice Factory including Fishery rights in the TB Reservoir on PPP basis from 01.06.2022.					

ORGANIZATION CHART OF HEALTH AND MEDICAL UNIT



ORGANIZATION CHART OF SECURITY SECTION



ABBREVIATIONS

AP	Andhra Pradesh
APERL	Andhra Pradesh Engineering Research Lab
APGENCO	Andhra Pradesh Generation Corporation
APTRANSCO	Andhra Pradesh Transmission Corporation
BOOT	Built Own Operate and Transfer
CEA	Central Electricity Authority
Cumecs	Cubic Metre per second
Cusecs	Cubic feet per second
CWC	Central Water Commission
CWPRS	Central Water and Power Research Station
FFU	Fish Farm Unit
FNMP	Fish Net Making Plant
FRL	Full Reservoir Level
Ft.	Feet
FW	Fisheries Wing
GESCOM	Gulbarga Electricity Supply Company
GoAP	Government of Andhra Pradesh
GoK	Government of Karnataka
GoT	Government of Telangana
GU	Garden Unit
ha	Hectare
HC	Head Constable
HEW	Hydro Electric Wing
ICZ	Irrigation Central Zone
IW	Irrigation Wing
KC Canal	Kurnool Cuddapah Canal
KERS	Karnataka Engineering Research Station
KGBO	Krishna Godavari Basin Organization
KRMB	Krishna River Management Board
Km	Kilometer
KPCL	Karnataka Power Corporation Limited
KPTCL	Karnataka Power Transmission Corporation Limited
KV	Kilo Volt
KWDT	Krishna Water Disputes Tribunal
m	Metre
M. Cum	Million Cubic Metre
mm	Millimeter
MOWR	Ministry of Water Resources
MW	Mega Watt.
MWL	Maximum Water Level
O&M	Operation & Maintenance
RBHLC	Right Bank High level Canal
RBLLC	Right Bank Low Level Canal
RDS	Rajolibanda Diversion Scheme
RM & U	Renovation Modernization & Up-gradation
RU	Reservoir Unit
RWT	Revised Working Table
Sq. Km	Square Kilometer
TB Dam	Tungabhadra Dam
TBHES	Tungabhadra Hydro Electric Scheme
TMC	Thousand Million Cubic feet

RAMASAGARAM TUNNEL AT KM. 9.257 OF RBLLC



HAGARI AQUEDUCT AT KM. 121.000 OF RBLLC





हम सबको जल बचाना है, आने वाले कल को सजाना है